

913.011

ASI

1544



913.011
ASI

No 250/

A
8/6

1544

British
Library
Acquisition Unit (UK)

ARCHÆOLOGICAL SURVEY

OF

WESTERN INDIA.

VOL. V.





15448
R
5

REPORT

ON THE

ELURA CAVE TEMPLES

AND

THE BRAHMANICAL AND JAINA CAVES IN WESTERN INDIA

COMPLETING

THE RESULTS OF THE FIFTH, SIXTH, AND SEVENTH SEASONS' OPERATIONS
OF THE ARCHÆOLOGICAL SURVEY

1877-78, 1878-79, 1879-80.

SUPPLEMENTARY TO THE VOLUME ON "THE CAVE TEMPLES OF INDIA."

BY

JAS. BURGESS, LL.D., F.R.G.S.,

MEMBER OF THE ROYAL ASIATIC SOCIETY, OF THE SOCIÉTÉ ASIATIQUE, &c.

ARCHÆOLOGICAL SURVEYOR AND REPORTER TO GOVERNMENT

FOR WESTERN AND SOUTHERN INDIA.

1544

913.012
BUR / W.I


1883

LONDON:

TRÜBNER & CO., LUDGATE HILL.

1883.

[All rights reserved.]





PREFACE.

As the object of the present volume is sufficiently explained in the introductory chapter, very little need be added by way of preface to it. Like the preceding one, it is intended as a supplement to the volume on *The Cave Temples of India*, which was intended as a general *resumé* of the whole subject, but required for its completion special descriptions, such as those contained in this work on the Elura Caves, and on the Brahmanical and Jaina Caves elsewhere in Western India. These three volumes thus complete the description and illustration of the Cave Temples in Western India, so far as the Archaeological Survey of the Bombay Presidency is at present concerned; and though they are far from exhausting the subject, they may be considered as giving a fair presentation of it. The illustrations of the art and mythology which these works contain, it is believed, will be found interesting and instructive by a numerous and varied class of cultivated and scientific readers.

The inscriptions from Kanheri Caves contained in this volume belong rather to the preceding one; but the first arrangements made for their translation having failed, they were delayed, and finally undertaken by Dr. G. Bühler, C.I.E., of Vienna, whose able versions will be valued by scholars. To him and to Mr. James Fergusson, D.C.L., LL.D., F.R.S., whose valuable help and suggestions have been most readily afforded me, I owe my most hearty thanks.

Materials have been partly collected for a full description of the Mediæval Temples of the Canarese Districts of the Bombay Presidency, especially those at Gadag, Lakshmêśvar, Lakkundi, Dambal, &c., which it is intended shall form the next volume of these reports; and that will probably be followed by another on the Architectural Remains in Gujarât and other districts in the northern parts of the Presidency.

JAS. BURGESS.

EDINBURGH, 14th Oct. 1882.

CONTENTS.

CHAP.	PAGE
I. INTRODUCTORY—the Elurā Caves	1
II. THE BUDDHIST CAVES AT ELURĀ—the Southern Group	4
Caves I-VI	5
Caves VII and VIII	7
Cave IX.	8
III. THE THREE LARGER BUDDHIST CAVES, or Northern Group	9
The Viśvakarma Chaitya Cave, No. X.	9
The Doñ Thāl Cave, No. XI.	13
The Tin Thāl Cave, No. XII.	16
IV. THE ELURĀ BRAHMANICAL CAVE TEMPLES :—	
The Dās Avatāra	23
The Kailāsa or Rang Mahāl	26
V. ELURĀ BRAHMANICAL CAVES NORTH OF KAILĀSA :—	
Caves XVII. to XX.	37
Cave XXI : Rāmésvara	38
Caves XXII. to XXVII.	40
Cave XXIX. : Dumar Lena	41
VI. THE JAINA CAVES AT ELURĀ :—	
The Indra Sabhā	44
The Jagannāth Sabhā	48
Cave XXXIV.	49
VII. THE CAVES AT BĀDĀMI AND AHIHOLE	50
VIII. JŌGĒSVARĪ OR AMBOLĪ AND LONAD CAVES	52
Lonād	53
IX. ELEPHANTA CAVES	55
X. HARĪSCHRANDRAGAD AND PĀTNA CAVES	57
Patna Caves	57
XI. ANKĀI CAVES—BRAHMANICAL AND JAINA	58
XII. INSCRIPTIONS BY PROFESSOR G. BÜHLER, C.I.E., Vienna :—	
1. Nānāghāt Inscriptions	59
2. Kanheri Inscriptions	74
3. Dāsa Avatāra Inscription at Elurā	87



LIST OF PLATES.


PLATE	PAGE
I. VIEW OF KAILASA ROCK TEMPLE AT ELURÄ FROM THE NORTH-WEST (Autotype Plate)	<i>Frontispiece.</i>
II. GENERAL PLAN OF THE ELURÄ CAVES AND PLAN OF CAVES XXIII, XXIV.	4
III. Fig. 1, Section through the front of Viśvakarma Chaitya Cave; 2, Side View of the Dāgaba; 3, North Door of the Cave	9
IV. Figs. 1-5, Windows in Kailāsa Hall; 6, Sculpture of Mahishamardini on the wall; 7, Ditto in the front of the Court	28
V. FRONT OF THE RĀMĒŚVARA BRAHMANICAL CAVE (Autotype)	38
VI. THE INDRA SAGRĀ JAINA CAVE (Autotype)	44
VII. FAÇADE OF THE CAVES ON THE WEST SIDE OF THE INDRA SAGRĀ COURT (Autotype)	47
VIII. FRIEZE IN THE VERANDA OF THE BĀDĀMI BRAHMANICAL CAVE NO. II.	50
IX. ROOF OF THE BRAHMANICAL CAVE AT AIHOLE	51
X. DOOR OF THE SHRINE IN THE BRAHMANICAL CAVE OF JĠGĒŚVARĠ	53
XI. THE TRIMURTI AND ARDDHANĀRI SCULPTURES ON THE BACK WALL OF ELEPHANTA (Autotype)	56
XII. ANKĀI JAINA CAVES NOS. I. AND II. (Autotype)	58
<i>At the end—</i>	
XIII. ELURÄ BUDDHIST CAVES: Fig. 1, Pāṇḍarā Tārā in Cave II; 2, Tārā in Cave VI; 3, Pilaster in Cave V.; 4, Sculpture on the right side of the shrine in Cave VI; 5, Ditto on the left side; 6, Bodhisattva in Cave IX.	
XIV. ELURÄ: Plan of Buddha Caves Nos. VII. and VIII.; 2, Tin Thāl, Plan of second storey.	
XV. ELURÄ: Plans of the three floors of the Dōn Thāl Cave.	
XVI. ELURÄ: Fig. 1, Transverse section of the Viśvakarma Cave; 2, Padmapāṇi in Cave IV.; 3, Sarasvatī in Cave VI; 4, Pillar in Cave IX.; 5, Pillar in upper floor of the Dōn Thāl Cave.	
XVII. DETAILS FROM THE VIŚVAKARMA CAVE: 1, Sculpture on the inner side of the gallery; 2, Part of the Triforium; 3, Sculptures from the Dāgaba.	
XVIII. ELURÄ: Fig. 1, Inscription on the Viśvakarma Cave; 2, Pillar under the gallery in Viśvakarma; 3, Sculpture in the Tin Thāl Cave; 4, Buddha and attendants, from the Bāgh Caves.	
XIX. ELURÄ: Figs. 1, 2, Female heads from Viśvakarma Cave; 3, Head of Avalōkitēśvara from the same; 4, Vajrapāṇi, from the same; 5, Sculpture to the left of the shrine door in the upper storey of the Tin Thāl; 6, Panel in the Tin Thāl.	
XX. ELURÄ: Fig. 1, Bodhisattvas on the right side of the shrine in the Tin Thāl; 2 and 3, Bodhisattvas from the Bāgh Caves.	
XXI. ELURÄ BRAHMANICAL CAVES: Fig. 1, Pillar in the Dās Avatāra; 2, Shaft of Pilaster in ditto; 3, Śiva in the flaming Liṅga; 4, Śiva dancing the Tāṇḍava in the Dās Avatāra.	
XXII. ELURÄ: Fig. 1, Narasiṃha and Hiraṇyakaśipu; 2, Bhairava, in the Dās Avatāra.	
XXIII. ELURÄ: Fig. 1, Transverse section of Kailāsa; 2, Section of the Dās Avatāra Cave.	
XXIV. ELURÄ: Fig. 1, Śiva and Mārkaṇḍēya—from the Dās Avatāra Cave; 2, The same from Kailāsa corridor.	
XXV. ELURÄ: Fig. 1.	
XXVI. KAILĀSA: Fig. 1, Sculpture from the front of the Maṇḍapa; 2, Kāmadēva and Ratī, from the Court; 3, 4, Lions on the roof of the Maṇḍapa.	
XXVII. THREE SCULPTURES FROM THE NORTH CORRIDOR IN THE COURT OF KAILĀSA.	

At the end—

- XXVIII. KAILĀSA COLUMNS: Fig. 1, Pillar in the Hall; 2, Pilaster in the same; 3, Pillar in the north side of the Court.
- XXIX. KAILĀSA: Fig. 1, Pillar in the Central area of Lankēśvara; 2, Siva in the front aisle; 3, Varāha on the back wall of Lankēśvara.
- XXX. LANKĒŚVARA SCULPTURES: 1, Sūrya; 2, Umā; 3, Brahmā, Siva, and Vishṇu, from the back wall.
- XXXI. KAILĀSA: Figs. 1 and 2, Panels on the south side of the shrine; 3, Panel on the south side of the basement of the Nandī Maṇḍapa.
- XXXII. ELURĀ: Fig. 1, Plan of Caves XVII. and XVIII.; 2, Plan of Cave XIX.; 3, Of Cave XX.; 4, Of Cave XXII., Nilakanṭha; 5, Of Cave XXVI., Janwasa.
- XXXIII. ELURĀ: Fig. 1, Pillar in Cave XVII.; 2, Another pillar in Cave XVII.; 3, Pillar in Rāmēśvara (No. XXI)
- XXXIV. ELURĀ: Fig. 1, Saptamātris in Rāmēśvara; 2, In Nilakanṭha.
- XXXV. ELURĀ: Fig. 1, Brahmā at the end of the verandah, Cave XVII.; 2, Pillar in Cave XXV.; 3, Plan of Kumbarwādā Cave XXV.; 4, Plan of Cave XXVII.
- XXXVI. ELURĀ: Fig. 1, Marriage of Siva; 2, Dwārapālas at the corner of the shrine, in the Dumar Lena.
- XXXVII. ELURĀ: Fig. 1, Section of the Dumar Lena Cave; 2, Section of the Indra Sabhā Jaina Cave.
- XXXVIII. ELURĀ JAINA CAVES: Figs. 1, 3, and 4, Pillars in the central hall, upper floor, of the Indra Sabhā Cave; 2, Pillar in the small chapel of the Indra Sabhā.
- XXXIX. ELURĀ JAINA CAVES: Fig. 1, Column between the verandah and hall; 2, One in the front of the upper central hall; 3, Pillar in the west wing; 4, Sculpture of the opposite pilaster in the west wing of the Indra Sabhā.
- XL. ELURĀ JAINA CAVES: Fig. 1, Roof of the Maṇḍapa in the court of the Indra Sabhā; 2, Ambikā from a chapel; 3, Pillar in the Jagannāth Sabhā, ground floor; 4, Pillar in the last Jaina Cave.
- XLI. Fig. 1, Gomatēśvara from Indra Sabhā; 2, General plan of the Bādāmi Caves; 3, Siva dancing from Bādāmi Cave I.
- XLII. BĀDĀMI: Part of the Sculptures on the frieze in Cave III.
- XLIII. AIHOLE BRAHMANICAL CAVE: Fig. 1, Siva and the River Triad; 2, Siva; 3, Varāha and Prithvi in the antechamber; 4, Mahishamardini; 5, Siva dancing.
- XLIV. JŌGĒŚVARĪ BRAHMANICAL CAVES: 1, Plan; 2, Eastern door of the great hall.
- XLV. LONAD CAVE: Fig. 1, Left portion of the frieze on the façade; 2, Central door and figure; 3, Sculpture to the right of the façade.
- XLVI. ELEPHANTA, &c.: Fig. 1, Plans of Caves II. and III.; 2, Plan of Cave IV.; 3, Plan of Lonad Cave.
- XLVII. Figs. 1-3, Plans of Harischandragad Caves; 4, Transverse section of Pātna Jaina Cave; 5, Door of Śringar Chāvaḍi at Patna; 6, Door of Jaina Cave No. II. at Ankāi.
- XLVIII. PĀTNA CAVES: Fig. 1, Section of Śringar Chāvaḍi; 2, Plan of ditto; 3, Section of Nāgārjuna Kotri; 4, Plan of ditto.
- XLIX. ANKĀI CAVES: Fig. 1, Section of the Jaina Cave No. II.; 2, Plan of upper storey; 3, Plan of ground floor of Cave II.; 4, Plan of Jaina Cave No. III.; 5, Plan of Jaina Cave No. IV.; 6, Plan of Brahmanical Cave No. 1.
- L. ANKĀI CAVES: Fig. 1, Roof of the Jaina Cave No. III.; 2, Front of the shrine in the Brahmanical Cave No. II.; 3, Sculpture to the left of the entrance of the same.
- LI. INSCRIPTIONS: Nos. 1, 2, Nānāghāt large Cave Inscription; 3-9, Smaller Inscriptions; Kanheri Inscriptions Nos. 1-15.

LIST OF WOODCUTS.

No.	PAGE
1. The Southern Bauddha Caves at Elura, from a photograph	5
2. Dâgaba on the Wall of Cave II.	6
3. Façade of the Viśvakarma Cave, from Fergusson's <i>Ind. and East. Architecture</i>	9
4. Interior of the Viśvakarma Cave, from a photograph	10
5. Avalôkitêśvara from the Aurangâbâd Caves	11
6. Triśula Ornament from Amarâvatî	12
7. Triśula Symbol from Sâuchi	12
8. Vajra from Nepâl	12
9. Vajra from China	12
10. Indian Vajra, from Elurâ	12
11. Viśvavajra from Nepâl, from Oldfield's <i>Sketches from Nipal</i>	12
12. The Dâs Avatâra Brahmanical Cave Elurâ, from a photograph	23
13. View of Kailâsa, from Fergusson's <i>Ind. and East. Arch.</i>	27
14. Eaves of the second storey of the Cave on the south side of the Court of Kailâsa	27
15. Dwarf Figure from the roof of the gôpuram of Kailâsa	34
16. Shrine of the River Goddesses in Kailâsa Court, from a photograph	34
17. Pillar in the front of Râmêśvara, from a photograph	39
18. Pillars and Corner of the Shrine in Elephanta, from a photograph	55



KAILĀSA TEMPLE AT ELLURĀ FROM THE NORTH WEST.





REPORT

OF THE

ARCHÆOLOGICAL SURVEY OF WESTERN INDIA.

THE ELURA CAVES

AND

OTHER BRAHMANICAL AND JAINA CAVE TEMPLES.

CHAPTER I.

INTRODUCTORY: THE ELURÂ CAVES.

IN the preceding volume the description of the more notable groups of Buddhist Rock Temples, as given in the work on *The Cave Temples of India*, was considerably amplified by additional details and numerous illustrations, which will enable the architect and student to form a tolerably accurate idea of the style and character of the plans and ornamentation, as well as of the sculptures of these ancient and interesting works. And in addition to these, the facsimiles and translations of the inscriptions will afford fresh materials of a trustworthy character for the epigraphist and philologist, with a certain amount of important information of historical importance. But even that volume by no means exhausts the illustrations that might have been given, especially from Ajanṭā, of the artistic decorative work on columns, doors, windows, and friezes, or of the extensive mythological sculptures found in such rich abundance there and at Kaṇheri.

The intention of the present volume is to apply the same process to the illustration of the remaining Rock Temples of Western India. The principal of these are—the whole of the well-known and magnificent group at Elurâ, consisting of splendid representatives of the three classes—Buddha, Brahmanical, and Jaina Cave Temples; the Brahmanical and Jaina Caves at Bādâmi, at Aihole, at Ankâi Tankâi, and at Pâtna; and the Brahmanical Caves, chiefly at Jôgêśwari on Salsette Island, at Lonāḍ, and at Hariśchandragāḍ. To give anything like a complete illustration of these Cave Temples, or even of those at Elurâ alone, however, would occupy double the number of plates that can be given in this volume; but with those in *The Cave Temples*, as here supplemented, the reader may form some adequate conception of the characteristics of the different groups, and of the variety of architectural and mythological sculpture that is presented in these early monuments of the religious

A

faiths of India. ("All commentary," remarks M. Baudrillart,¹ "grows pale before the magnificent ruins of the temples of Elurâ, which, more than any other ruins, confuse the human imagination. At the sight of these astounding edifices . . . the development of the plastic arts and of public religious luxury amongst the Hindus receives the most striking attestation in the magnificence of these temples, in the infinite diversity of their details, and the minute variety of the carvings.")

In this volume it seems preferable to treat the Elurâ Caves as a whole, and to illustrate the temples found there—Buddhist, Brahmanical, and Jaina—as a series complete in itself. In *The Cave Temples*, three separate chapters were devoted to the three sections of this group,² illustrated by about thirty-one plates, and to each section was assigned its relative place among the other excavations of the same character. In the supplementary information to be now given such a distribution is no longer required, as it is only proposed to amplify the illustration of the Elurâ Caves, as given in the former work, in their topographical order from south to north—which, as it happens, is also that of their religious character, and pretty nearly of their relative ages. This is the arrangement adopted by Dr. James Fergusson in his *Rock-Cut Temples of India*, who was the first to point out the religious characteristics of the different groups, which this mode of describing them brought to light.

It is only thus by treating of the Elurâ group as a whole that an adequate idea can be obtained of this series of cave temples, which is probably the most magnificent and most interesting in India. The only other group that can rival it in interest is that at Ajantâ.³ There, however, the caves all belong to one religion, and beginning at a very much earlier period than anything found at Elurâ, carry on the history of the Buddhist religion and architecture for nearly 1000 years; and though the series at Elurâ commenced nearly at the time when the excavations at Ajantâ ceased, an immense additional interest was added there by the introduction of temples of a novel form belonging to the Hindu religion, and subsequently by others of the Jaina faith, affording a varied picture of the mythology of India during the period of its greatest vigour, such as is nowhere else to be found. Moreover, besides the interest attaching to the individual members of the group, which in themselves are probably equal to any found elsewhere, the whole culminates worthily in the Kailâsa, which is certainly the most magnificent rock-cut temple in India, and by itself is sufficient to give a dignity and importance to this group beyond any other series of rock-cut temples which India possesses.⁴

At Ajantâ one feels that there is a homogeneity in the mythology represented in the painting and sculpture throughout the whole range of the caves; they are all manifestly the work of one sect as it developed its art and its mythology. At Kanheri, also, we have the same thing; but while at Ajantâ the art rapidly develops in richness, at Kanheri the architecture is, from the earliest to the latest example, exceedingly plain and unadorned; by the style or order of the pillars and the arrangements of the caves, however, we readily see that they are spread over a long period of time, and the mythological figures mark the progress of the school of the Greater Vehicle, but there is no such marked advance in decorative sculpture as we find at Ajantâ. The two groups differ in the same manner as

¹ *Histoire du Luxe, Privé et Public, depuis l'Antiquité jusqu'à nos Jours.*

² See *Cave Temples*, Bk. II., chap. iv, pp. 367–384, and plates lvii to lxx for the Buddhist Caves; Bk. III., chap. v, pp. 431–463, and plates lxx to lxxxiv for the Brahmanical Caves; and Bk. IV., chap. iii, pp. 495–502, and plates lxxxvi to xcii for the Jaina Caves.

the quarter of a royal city containing the palaces of the king and his nobles does from the suburbs of the working-classes.

The Elurā Buddhist Caves (on the other hand) differ in many respects from both these groups; they are on quite as large a scale as any at Ajantā, but differ in their arrangements, and though they contain abundance of sculpture, it varies markedly both in its subjects and in details from that at Ajantā, while the ornamentation is much less elaborate. They differ also from the Kanheri group in their vastly larger dimensions, their plans, and in the greater amount both of sculptured ornamentation and mythology, but especially in the character of the latter. Thus, while the *dāgoba* is a frequent object of representation in the bas-reliefs at Kanheri, it only occurs once or twice at Elurā, and then in very small examples, and in positions by no means prominent. Nāga-hooded figures, so often represented both in the sculptures and paintings at Ajantā, as well as at Amarāvati, Bōrō Būdūr, Sānchī, and Bharhut, are not found here; and while both at Kanheri and Ajantā the Buddha is represented without any supporters or only with two, at Elurā he is most frequently attended by six, eight, or ten of the Bodhisattvas, whilst *śaktis* or *dēvīs*—later additions to the Bauddha pantheon—figure much more frequently and prominently on the walls of these caves than they do at either of the two groups just named. When we compare them again with the sculptures on the *stūpas* at Sānchī, Bharhut, Amarāvati, and Bōrō Būdūr,¹ we note still further differences, and are led to consider whether these variations may not be very largely due to the difference of sects or schools into which the Buddhists were very early divided, and whether each of the greater schools—which were probably to a large extent practically local—may not have developed much that was special to itself in its mythology or the modes of representing the beings in the pantheon. This would help to account for differences in the characteristics of the sculptures at Amarāvati, Kanheri, Elurā, Ajantā, and Sānchī. True, much of this variety is due to differences of age; and the lack of sculpture in the Junnar, Nāsik, and other caves, is doubtless to some extent owing to their early age; but the recent discovery of an inscription of Vasishṭhīputra Puṣṭamāvi at Amarāvati, shows that the difference between the sculptures there and at Nāsik and Kārlē, where other inscriptions of the same king are found, is due to other causes, such as we have just indicated, quite as much as to difference of age. Moreover, (we learn from I-tsing, a writer of the end of the seventh century, that the Sarvāstivādin schools were less honoured in the Marāṭha country than in Magadha, but that the Sammatīyas were particularly respected. In the south the Mahāsthavira school was universally honoured; and in Eastern India each of the four schools (Mahāsaṅghika, Āryasthavira, Sarvāstivādin, and Sammatīya) had its adherents in different districts.² It seems, moreover, to be more than a mere surmise that the varieties in sculptures are largely owing to the various schools that constructed different *stūpas* or excavated special groups of caves, for, on comparing the sculptures in these Elurā Caves with the mythology of the Yogāchārya school of the Mahāyāna, founded by Āryāsaṅga,³ we find the agreement so marked that we may conclude they were the works

¹ See the magnificent illustrations of Bōrō Būdūr, published by order of H. E. the Minister of the Dutch Colonies (Leide, 1874).


² Beal's *Buddhist Literature in China*, p. 65. The Sammatīyas were followers of the Hinayāna, and were split into three schools. Most of the early schools were, however, afterwards more or less influenced by the doctrines of Nāgārjuna and Asaṅga.

³ He is said by Tārānātha to have lived 900 years after Buddha, and by others 100 years after Nāgārjuna: perhaps early in the fourth century, Vassilief, *Bouddh.*, pp. 31, 52, 65; St. Julien's *Mém. des Cont. Occid.*, tome i, pp. 105, 269.



Facing Page 4

GENERAL PLAN OF THE ELURA CAVES.



hārṇadā—are on a considerably larger scale and more magnificent in their arrangements, but they seem to have been pushed in at a higher level than the adjoining Caves I., III., and VII., and were probably contemporary with the great Chaitya Cave—the Viśvakarma—which with two or three others was probably excavated during the seventh century A.D. Nos. VIII., IX., and XI. were probably even later than this, and may be considered as marking the expiring efforts of the Buddhists in Western India.

CAVES NOS. I.-VI.

The first six caves have been described in some detail in *The Cave Temples* (pp. 368-375, and plates lvii to lxi). The accompanying woodcut (No. 1) presents a view of Caves



No. 1.—The Southern Buddhist Caves at Elurā, from a photograph.

Nos. II. to V. Cave I. is hidden by the mass of debris in front of it, but it is just under the right side of Cave II., of which the door and large window to the right of it are seen near the right-hand side of the view. Cave III. is at a lower level to the left. Cave V., with the fragments of a large chapel belonging to it on the south side (of which the whole west half has fallen away), extends from over the left side of Cave III. to behind a parapet wall recently erected to afford a safe passage along the face of the scarp. The interior of Cave IV., which is very much ruined, is seen under the chapel of Cave V.


Sculptured in a large panel on the inside of the front wall of Cave No. II. is the figure represented in fig. 1 of plate xiii, where we have either Pāṇḍarā the mother of Padmapāṇi or some other of the Tārās. Both her two attendants have flowers in their hands; and here, though somewhat abraded by time, are six *Vidyādhara*s or cherubs over the head of the goddess. In her right hand she probably held up a *mālā* or rosary, but it is now obliterated. Behind the head is the aureole or *bhāmaṇḍala*, which indicates that she is a celestial personage; and in her ears are large earrings of different forms. On the front of the *mukuta* or headdress is a *dāgaba*, which must be taken as her *chinha* or cognisance; and as it is also associated with Akshōbhya, the second Jñāni Buddha, we may

perhaps identify her with Lōchanī : in later mythology, however, Lōchanī has also an upright *vajra* on the lotuses which she holds in each hand.

In the back of this cave, No. II., is one of the few examples of a *dâgaba* among the sculptures at Elurâ. It is a small bas-relief on the wall by itself, without any worshippers

or other accessories, and is represented in the accompanying woodcut (No. 2). The style of it is plain, but the type is not an early one.

In Cave IV., the hall of which is almost entirely ruined, in the left end of the aisle or antechamber that crosses in front of the shrine and two cells that are in the back wall, is a sculpture,¹ represented in fig. 2, pl. xvi, where we have Padmapâni or Avalôkitêsvara seated with his feet on the lotus. He has his proper cognizances, having a small deerskin over his left shoulder, holding the rosary or *mâlâ* in his right hand, and attended as usual by two female *dêvis*—one with a bottle and rosary, and the other with only a flower. Above, on each side, is a figure of Buddha, the one standing and the other seated cross-legged in the *abhaya mudrâ* or attitude of blessing.



No. 2.—Dâgaba on the Wall of Cave II.

At the entrance to Cave V., on the right side, is the pilaster represented on plate xiii, fig. 3, in which the amount and character of the carving remind us of the richly sculptured pilasters so frequent at Ajantâ.

The antechamber to the shrine of Cave VI. is richly sculptured. The back wall and shrine door were represented in *Cave Temples*, plate lxi ; and to this is now added the sculptured compartments on the end walls of the same room. The principal figure in the left end seems to be Pâṇḍarâ or Padmanī (plate xiii, fig. 2), the *śakti* of Amitâbha and mother of Padmapâni,² who acts the part of a *dwârapâla* on the left side of the shrine door. She has a lotus stalk in her left hand, and wears a high *jaṭâ* headdress ; her locks descend over her shoulders, and a small deerskin lies over the left one, as is often the case in figures of Padmapâni. She is attended by Vidyâdharas on clouds, and by a small female figure on each side. The headdresses of these small figures, and of most others in these caves, is a sufficient index of their late age. Over the panel is a *torana*, dipping in the centre, and with *makaras*³ at each end of it, over the capitals of small pilasters.

¹ *Cave Temples*, p. 372, and plate lvii.

² It should be noticed that while much of the sculpture at Bôrô-Bûdâr bears a close analogy to that of Amarâvatî and to the sculpture and paintings of Ajantâ, the Bodhisattvas and Buddhisaktis are entirely absent at the two former places, and even at Ajantâ we find only the two leading Bodhisattvas represented. Hence the futility of Dr. Leeman's attempt to distinguish the Jñâni Buddhas.—*Bôrô-Boudour*, pp. 446-471.

³ The *makara* is a fabulous animal, described as having an elephant's trunk, a snake's tongue, and a crocodile's teeth.

On the right-hand wall of this antechamber, facing the figure above described (pl. xiii, fig. 2), and close to the *dwârapala*, on the right side of the door, supposed to represent Mañjuśrî, is the sculpture given on plate xvi, fig. 3. The right hand of the central female figure is broken, but the attendant peacock and the paṇḍit reading at her right, seem sufficient to point her out as Sarasvatî,¹ who with the Hindus is the goddess of learning and eloquence, and with the Buddhists is one of the wives of Mañjuśrî, and is perhaps the same as Lôchanî.

On the right side of the shrine is a panel containing three figures (plate xiii, fig. 4) on lotus seats. The left one may easily be identified as Avalôkitêśvara or Padmapâṇi, with the lotus and rosary, and the deerskin over his shoulder; also a small figure of Amitâbha Buddha on the front of his headdress. Whom the other two figures respectively represent is not so clear; the central one is very fat and holds what resembles a small book in his left hand, and some round object in his right, while his headdress is unlike any other. He has rich armlets, heavy earrings, a necklace and *jânvi* or sacred thread, as a Brahman. The third figure holds a small flower in his right hand, wears a high dress with a *dâgaba* on the front of it, a necklace, long ear-pendants, armlets, bracelets, and a thick cord worn as the *jânvi*. Probably this is Mañjuśrî. All three have aureoles behind their heads. On the left side wall of the same room is a similar compartment, which contains first, to the right, a male figure with rich headdress, earrings, necklace, and *jânvi* on bended knees, and attended by a female *chauri*-bearer presenting an offering. Behind him is a female figure, probably his wife, also with rich turban² and enormous earrings, on her knees and with her hands in the attitude of adoration. She is attended by a female dwarf, who bears a box or tray with presents, and over her head is a bird apparently placed as a sort of cognisance. Behind the female, again, bends on one knee a male figure with necklace and Brahmanical cord, holding something like a long bag or purse. Close to him is an elephant's head and fore-foot, with a small figure representing the driver leaning over its brow. This must be intended to represent some wealthy family making an offering to the cave or its priests: it may be a prince with his wife and Diwân.

On each wall, above these panels, are three rows of three Buddhas each—all in the *dharmachakra mudrâ*,³ as is also the great central figure.⁴

CAVES VII. AND VIII.

Plate xiv, fig. 1, gives the plans of Caves VII. and VIII., on the same scale as the Caves on plate lvii of *The Cave Temples*, of which they form the continuation on the north side, but are not marked on the general plan of the caves (plate ii) in consequence of their being under Nos. VI. and IX. Cave VII. is a vihâra, just under No. VI., which has never been finished, and is now much ruined. It is 51½ feet wide by 43½ feet deep. The roof was supported by four square pillars, but three of them are broken away. In the back wall five cells are commenced, of which only two at the right end are finished. There are also three

¹ She is a favourite with the Buddhists everywhere; in Japan she is called Benten, and in Tibet, *Dvagschan-ma*.—*Asiat. Res.*, vol. xx, pp. 515, 535.

² Observe the jewelled crescent on the left side of each turban.

³ This *mudrâ*, so prevalent everywhere in India, is either not represented at all at Bôrô-Bôdûr, or depicted in a somewhat different form.—*Bôrô-Boodoer*, plate viii. The other *mudrâs* also differ slightly, e.g., in the *Bhumi-sparśa*, the right hand does not come so far over the knee as in Indian images.

⁴ See *Cave Temples*, plate lxi.



unfinished cells in the right end wall, and four in the left. The thresholds of the doors to these are unusually high—the first step, even in the two that are finished, being 18 to 20 inches high. Through the back wall of the first cell, in the left side, an opening has been broken into Cave No. VIII. The front wall is quite unfinished, the door in the middle only having been hewn out, and the rock being left of considerable thickness on the north side of it, through which another entrance has been made at the left corner, with a descent of two or three steps in front and a wide passage on the inner side. At the right, or south-west corner, an entrance is also broken into the hall from the foot of the stair, which there ascends to Cave VI.

The arrangements of Cave No. VIII., as described in *The Cave Temples* (p. 376), will be better understood by the plan (pl. xiv), which at once shows its resemblance to the Brahmanical Caves, such as the Rāvana-kā Khāi and Rāmésvara, and also to the Aurangābād Baudhdha Caves,—a pretty clear indication of its late date. The two pillars in front of the shrine being of the Elephanta type, as in Cave II., is a further proof that it is one of the latest Buddhist excavations here. The other two pillars, dividing it from the outer apartment, have high square bases; the shafts have 32 flutes, and the capitals are square, with pendent ears at the corners, carved with scroll-leaf pattern. The slender columns in front of the little chapel on the north side of this room are also of the Elephanta type.

CAVE IX.

This cave, if not an appendage of Cave VI., or, rather to a small cave in front of its north wing, now destroyed by the falling away of the rock (see plan, *Cave Temples*, pl. ix), is quite different from any we elsewhere meet with. It forms a sort of upper storey to the last, but consists of a mere chapel with two pillars in front,¹ and is quite in the same style, both of architecture and sculpture, as Cave VIII. Over the front pillars is a sculptured façade, the architrave or lower member being divided into compartments by divisions carved with arabesques, the compartments alternately containing a sitting and a standing Buddha, with attendants. On the frieze above are carved three Chaitya window ornaments, and at a higher level other two—each row with half ones at the ends; and in a third and shorter belt is a single one. Each of these is occupied by a figure of Buddha, and between the projecting members on which they are carved are many smaller human figures. Above, at each corner, is a Bodhisattva with female attendants.² One of the pillars is represented in plate xvi, fig. 4.

Inside, the chapel is about 23 feet by 10 feet, with two attached pillars on the back wall, dividing it into three compartments. The centre one contains a Buddha with four *gandharvas* above, and the side ones contain the two attendant Bodhisattvas; the right side one—probably Mañjuśrī—is represented on pl. xiii, fig. 6. The other is Avalôkitesvara, also with two female attendants, and four *gandharvas* above.

¹ See *Cave Temples*, p. 375.

² Compare this with the similar façade of the left wing of the Indra Sabhā.


ELURÄ.




1. SECTION THROUGH THE FRONT OF VISVAKARMA CHAITYA CAVE.

Scale to figs 1 & 2.

2. DAGOBA.



3. NORTH DOOR OF VISVAKARMA CHAITYA CAVE.



Scale to fig. 1.



CHAPTER III.

THE THREE LARGER BUDDHIST CAVES.

VIŚVAKARMA CAVE, No. X.

CAVE X. is the great Chaitya rock temple, the only one of the kind at Elurā, and locally known as Viśvakarma's, or "the Carpenter's shop." It is a splendid temple, with a fine façade and large open court in front, surrounded by a corridor, and worthily concludes the series of Buddhist Chaitya caves, which, taken altogether, are perhaps the most interesting group of buildings or caves in India. We can now trace the sequence of them from the early wood-fronted examples at Pitalkhorā, Kondāṇe, and Bhājā, through the

stone-fronted caves of Beḍṣā and Kārîlê, to the elaborately decorated façades of the two latest at Ajantā, till at last it loses nearly all its characteristic external features in this one at Elurā. The earlier ones are all certainly anterior to the Christian era—some probably as early as 200 or 250 B.C.—and as this one can hardly be dated before 650 A.D., the series extends in nearly unbroken continuity for about nine centuries. During this long period we can easily trace the progress from the great open front of a cave covered by an external screen, first in wood, and then in stone ornamented in wood, till subsequently we find it constructed entirely in stone with limited dimensions for the opening, and at last the great horse-shoe window was



No. 3.—Façade of the Viśvakarma Cave.¹

contracted into the triple Venetian window of this Viśvakarma Cave, as represented in the annexed woodcut (No. 3); and the screen in front had entirely disappeared. So altered, however, is it from the grand simplicity of the great arched window at Kārîlê, that if we had not all the intermediate steps by which the changes can be followed out we should hardly be able to trace it back to its original form, or to feel sure that it was the same architectural feature.

The interior of this temple is 85 feet 10 inches long inside, by 43 feet 2 inches wide,

¹ From Fergusson's *Ind. and East. Archit.*, p. 128.

and 33 feet 11 inches from the floor to the under edge of the stone ridge board. The pillars that separate the nave from the aisles are 14 feet high, and the triforium 4 feet deep. Its arrangements, however, may be best studied on the ground plan and details given in *The Cave Temples* (plates lxii and lxiii). To these are here added a longitudinal section (plate iii, fig. 1) through the front of the cave, showing the corridor on the right hand or south side of the court below—with portions of the sculptured panels on the back walls—the wide balcony over the entrance portico, and the deep gallery above the front cross aisle, which advances considerably into the cave,—differing in this respect from the earlier Chaitya temples in that the great arch, besides being altered in front and the window divided, is of much less depth than usual and than the gallery; and a transverse section (plate xvi, fig. 1).

The narrow triforium over the pillars of the nave is divided into compartments, each containing a figure of Buddha, seated with his hands in the *dharmachakra mudra*, with various groups of attendants (see plate xvii, fig. 2); and on a band below is a line of rollicking dwarfs or *gana*, similar to what we find on the basements of the Bādāmi Brahmanical caves of the sixth century, and on the Vaishnava temple at Aihole. Above this triforium the ribs of the roof spring, each from a small Nāga figure, the alternate ones being males in an attitude of adoration, and the females each holding a flower in their right hands. On the inner side of the gallery, the band of *gana* is continued, but the upper and broader portion (see fig. 1) is divided into a large central and two smaller side panels,

each filled with standing figures, which it is difficult to identify with any scene in the Bauddha legends.

The pattern of the pillars is also shown in the section (plate iii, fig. 1), and one of the pair under the gallery, which are more elaborately carved, is drawn to a larger scale on plate xviii, fig. 2. At the end of the verandah that passes the entrance is a chapel, in which may be seen the central figure—that of Avalôkitêśvara or Padmapâni, and to the right, that of Dharma or “the law,” always personified as a female, with four arms, holding a bottle, a *triśāla*, and a rosary. The figure on the other side is also a female, but with only two arms.



No. 4.—Interior of the Viśvakarma Cave, from a photograph.

those of the earlier caves, and even from those of Ajaṇṭā.¹ It is 26 feet 10 inches high, and the circular part of it is 15 feet 6 inches in diameter. The capital, no longer square as in all the early examples, is cut up by numerous offsets, like the shafts of some of the pillars in the large cave at Bādāmi. The body of it is carved round about with alternate broad and narrow panels (plate xvii, fig. 3) containing figures of Buddha

¹ See Vol. iv, plates xv, xvii, xxxi and xxxvi.

seated with his feet on the lotus, his hands in the *dharmachakra mudrā*, with and without attendant *chauri*-bearers. On the front of it a large mass of rock, 16 feet 10 inches high, is left as a frontispiece, and is carved with a huge image of Buddha, 10 feet 11 inches from the feet to the top of the head, seated with his hands in the favourite *dharmachakra mudrā*, with the usual pair of Bodhisattva attendants,¹—Avalōkitēśvara and Mañjuśrī. The accompanying woodcut, No. 4, shows the front of this dagoba. Two pairs of *gandharvas* with offerings appear above the Buddha, on an arch the upper part of which is also carved with the *Bōdhi* tree.

The simple but elegant side-door into the left side aisle is represented to scale in fig. 3 (pl. iii). The central door has small figures in pairs all round the architrave, with Nāga guardians at the bottom on each side. Outside the architrave is the usual leaf-border.

In the balcony in front of the window is a portico on each side, with cells behind.² The stair lands in the one on the north side, and opposite the landing, over the door of a cell in the east end, is the same group of two males and a female, which we meet with again in the Tin Thāl (pl. xviii, fig. 3). On the right side of this same door is a standing figure of Buddha, with two small attendants, and on the left a figure seated cross-legged, and another with the right foot down, wearing a necklace and holding a lotus. There are also numbers of figures of Buddha on the walls, some in little arched niches.

A recess on the right side of the front window contains Avalōkitēśvara, with two female attendants and *gandharvas*. His head is represented on plate xix, fig. 3; and on the frieze of this recess is a fine group of dwarfs. A similar recess on the north side contains Mañjuśrī. In the north end of the balcony is a female figure in the centre, holding a lotus, and eight figures of Buddha in line above; six figures with the lotus, and seated with one foot down, are on her left, and five on her right—one of them, a female, with four arms. On the south side is a recess in which is another statue of Avalōkitēśvara with female attendants.

To the west of this was a portico similar to that on the north side, which has had two pillars in front, but they have fallen away along with the roof. In the back are three cells, and one in the east end, with several seated and standing figures, also a four-armed standing figure (pl. xix, fig. 4), differing considerably from the usual ones of Bodhisattvas, but which may be compared with that of Padmapāṇi, represented in the annexed woodcut (No. 5), from the Auraṅgābād Caves.³ This Elurā one evidently is meant for Vajrapāṇi, and it is to be observed that while he holds a *vajra* in his left hand, the end of another is represented over his head, as if emerging from it. The other symbols he holds are too much injured to be recognised. This figure is possibly an early form of Vajrapāṇi, as now represented in Tibet, in the terrific aspect of Chyag-rdor—"the subduer of evil spirits."⁴



No. 5.—Avalōkitēśvara from the Auraṅgābād Caves.

¹ *Cave Temples*, pp. 379–381.

² See the plan of the balcony in *The Cave Temples*, plate lxii.

³ *Report*, vol. iii, p. 80.


⁴ Schlagentweit's *Buddhism in Tibet*, p. 114. Curiously enough, the Buddhists have got a version of the Hindu story of the churning of the ocean for the *Amṛta*, which was given in charge to Vajrapāṇi, but stolen by Rāhu.

Next to this is a figure of Buddha, with Padmapāṇi and Vajrapāṇi as supporters, the latter of whom holds up the *vajra* in his right hand, and has an opening flower-bud in his left. The other figures are too numerous to describe, but the sculptures here and in the Tin Thāl alone would form a most important contribution to a Buddha pantheon. Two of the heads of female figures in this verandah are represented in figs. 1 and 2 of plate xix. These may be compared with those in other illustrations in this volume, and with the heads from Aurangābād caves given in volume iii, plates xlix, liii, liv, and lv.

The *vajra* or fulmen is so frequently represented in the sculptures here that it seems



No. 6.—Triśūla ornament from Amarāvati.




No. 7.—Triśūla symbol from Sānchi.

to demand a word of explanation. In Nepāl it has become a favourite symbol of Buddhism, and is constantly sculptured about their temples. In its simplest form, with only one set of prongs, it would almost seem that possibly it may have been derived from the *triśūla* symbol so frequently represented at Amarāvati and Sānchi, and figured in the accompanying woodcuts (Nos. 6 and 7).

It is usually, however, repre-

sented with two similar ends, as in the accompanying representations of sculptured *vajras*,—(No. 8) from Nepāl, and (No. 9) from China, and of the usual form found at Elurā (No. 10),



No. 8.—Vajra from Nepāl.



No. 9.—Vajra from China.



No. 10.—Indian vajra.

though here it is also found with only one end. It is to be remembered, however, that the *triśūla* is also a Brahmanical symbol (see pl. xxx, fig. 3), and so also is the *vajra*.

But in Tibet and Nepāl a sort of double *vajra*, having a hooked prong on four sides of the central one, is often made of metal, richly moulded and gilt, and is placed on an altar or a *Dharmadhātumaṇḍala*, in front of or inside the temples, where it is an object of worship. This is called a *Viśvavajra*, and the accompanying woodcut (No. 11) represents



No. 11.—Viśvavajra from Nepāl.¹

one of these instruments, about five feet in length, made of copper by one of the Nepāl rājas in the middle of the seventeenth century, and placed in front of the great temple of Adi-Buddha at Svayambhunāth. The *viśva* is the symbol of Amoghasiddha, the fifth Jñāni Buddha, and of his Bodhisattva Viśvapāṇi.

Every lama in Tibet and every Bāṇḍya priest in Nepāl must possess a small *vajra*, which they use when repeating their prayers and at all ceremonies of importance, as at marriages, the initiation of novices, &c., and in the latter country the priests receive the title of *Vajra-Achāryas* from the use

¹ From Oldfield's *Sketches from Nepāl*, vol. ii, p. 220.

of this instrument.¹ It is the symbol of Akshobhya, the second Jñāni Buddha, and of his Bodhisattva, Vajrapāni.²

In this balcony there remains to be noticed the only inscription at all of an early date found among the Bauddha caves here; but it is only the *mantra* of the Mahāyāna school,³ carved in characters of perhaps the eighth or ninth century, probably about the time when the figures over which it is found were inserted (see pl. xviii, No. 1). It reads—

*Yé dharma hētu prabhavā hētum, tēshām tathāgato, hyavadattēshām cha yō ni-
rōdha, évañ vādi mahāśramaṇa[h.]*

“All things proceed from cause; this cause has been declared by the Tathāgata; all things will cease to exist; this is that which is declared by the great Śramaṇa (Buddha).”

Though to this mantra is ascribed the conversion of Maudgalyāyana and Śāriputtra, the two chief disciples of Buddha, it probably owes its origin to some of the early Mahāyāna teachers. It was found on a stone slab and on several clay seals at Sarnāth, near Banāras, and on a copperplate in the *stūpa* excavated by Dr. Bird at Kanheri, on numerous clay seals discovered at the same place by Mr. West in 1853, and the first part of it is given in a short inscription cut into the square body of a dāgoba in bas-relief on the right-hand side wall in the court of the great Chaitya cave.⁴ This celebrated philosophical formula has also been found in inscriptions from Afghanistan, Tirhut, Burma, Singhapur, and Java, and is well known in the Bauddha literature of Nepāl, Tibet, China, and Ceylon.

THE DON THAI CAVE, NO. XI.

The next cave is the Don Thai, so called because it was long supposed to consist of only two storeys. In 1876, however, the lower storey was excavated of the earth which had completely buried it. The plans of all three floors are given in plate xv, from which it will be observed that the upper storey has been carried farthest into the rock, though apparently it never was nearly completed. It may be doubtful whether it was originally intended to form cells in the blocks left at the back of the verandah, but several cells have just been commenced in the walls, whether for residence or small chapels is not quite clear. The second storey consists only of a verandah with eight massive square pillars in front, a small shrine at one end, and three larger ones in the back, the central one (otherwise the smaller) having a room in front with two square pillars. The larger shrines on each side

¹ Huc's *Travels in Tartary*, &c., vol. ii, p. 221; Oldfield's *Sketches from Nepal*, vol. ii, p. 201; Hodgson's *Essays*, pp. 41, 63.

² This was the case even in Fah-hian's time, who speaks of it as “the golden mace.”—Beal's *Fah-hian*, p. 94; and conf. Julien, *Mém. sur les Cont. Occid.*, tome i, pp. 340, 134, 319; ii, 114.

³ The following are the principal references on this formula:—*Jour. As. Soc. Beng.*, vol. iv, pp. 133, 211, 286, 713; vol. v, pp. 157, 158, 658; vol. x, p. 95; vol. xvi, p. 78, and plate i; vol. xviii, pt. i, p. 247, and plate x; *Asiat. Res.*, vol. v, p. 131; vol. xx, p. 52, or Feer's French translation in *Ann. Mus. Guimet*, tome ii, p. 155; Hodgson's *Essays*, 1st ed. p. 158, or 2nd ed. p. 111; Hardy's *Man. of Buik.*, 2nd ed. p. 201 (1st ed. p. 196); Wilson's *Ariana Antiqua*, p. 51; Bird's *Historical Researches*, p. 64; Crawford's *Hist. of the Indian Archipelago*, vol. ii, p. 212, and plate 31, which strongly resembles this Elurā example in the character of the alphabet; Schlagentweit's *Buddhism in Tibet*, p. 17, or French transl. p. 13; Beal's *Romantic Legend*, p. 329; and Wong Puh's *Memorial of Śākya Buddha* in *Jour. R. As. Soc.*, vol. xx, p. 166; Burnouf's *Introd. à l'Hist. du Buddh. Ind.*, 2me ed. p. 308 note (1re ed. p. 345); and *Lotus*, pp. 522-526; Kern, *Hist. du Bouddh.* in *Rev. de l'Hist. des Relig.*, tome v, p. 149; Sykes, in *J. R. As. Soc.*, vol. xvi, pp. 37-53, and plates i-iii; West, *Jour. Bom. B. R. As. Soc.*, vol. vi, pp. 158, 159, and plates v and vii a-d.

⁴ *Jour. Bom. B. R. As. Soc.*, vol. vi, p. 4, No. 8.



contain colossal figures of Buddha seated cross-legged with the soles of his feet turned up, but here, as in the Tin Thāl also, each side of the chamber is carved with tall attendant Bodhisattvas, which will be more particularly noticed below. The ground-floor consists of a verandah about 89 feet in length by $6\frac{1}{2}$ wide, and 8 feet 4 inches high, with seven square pillars in front, though it was intended to add an eighth at the left end. In the back wall of this verandah are three rooms or shrines, two of them quite unfinished, but the central one, containing a cross-legged image of Buddha with Padmapāṇi and Vajrapāṇi as attendants, one on each side.

The court in front is about 102 feet wide by 45 deep, with an approach on the west about 50 feet wide. In the left, or north-west corner of this court, is a large irregular room with a bench round the inner walls of it, and beside it is a chapel containing two images and attendants—that on the back or north side being Avalōkitēśvara seated on a *siṃhāsana* or lion-throne, with a female figure seated cross-legged on each side of him—the one on the left having four arms. Above, on each side, are seated figures. To the left is another four-armed *dēvi*—probably Dharma—with a rosary (*mālā*) and a flower. On the right side of the room is a headless figure of Buddha, behind whom stand two Bōdhisattvas, and at the sides *chauri*-bearers. There are also other figures on the walls.

On the right side of the entrance to the court is a smaller, rudely cut chamber, and there are some others quite filled up with earth.

The verandah of the first floor above is $102\frac{1}{2}$ feet long by 9 feet wide and 10 feet 3 inches high, with three shrines in the back, and two cells—one of them only begun. There is also a fourth shrine at the south end, having an arched door. This last contains a figure of Buddha, seated cross-legged on a high square block; above his shoulders are two *gandharvas* or Bauddha cherubs, while Avalōkitēśvara or Padmapāṇi¹ and Mañjuśrī or Vajrapāṇi² attend him as *chauri*-bearers. By the side of the latter stand three male figures with

¹ Avalōkitēśvara, Padmapāṇi, or Karuṇārṇava—in Tibetan *Pyan-ras-gzigs-drang-phyug* (pronounced Chenresivanchug)—is the “on-looking lord,” called also Abhayaṇāda—“the remover of fear,” Abhyutgatarāja—“the great august king,” and in China Kwan-yin. He was apparently unknown till about the third century, but is mentioned as a hearer in the *Saddharma-puṇḍarīka Sūtra* (cir. 300 A.D.), of which Mañjuśrī is the mythical author. Avalōkitēśvara is held in special reverence in Tibet as the protector of the country; and the Dalai-Lamas are regarded as his successive incarnations.—See *Reports*, vol. iii, pp. 75, 76; Beal's *Fah-hian*, p. 60; *Ind. Ant.*, vol. viii, pp. 249–253; *Cave Temples*, p. 357, &c.

² Vajrapāṇi is one of the names of Śakra or Indra, the god of thunder, who with his bolt (*vajra*) slays the enemies of Buddhism, and, in Nepāl, is the Jñāni Bōdhisattva of Akshōbhya. He is represented in a blue robe, and is called in Tibet *Lag-na-rdo-rje* or *Phyag-na-rdo-rje*. Hodgson calls him “the son of Vajrasattva Buddha,” who is the Magnus Apollo of the Tāntrikas (*Essays*, 2nd ed. pp. 15 and 17, note; or, 1st ed. pp. 23 and 25, n.) The Yogācāra school make Vajrapāṇi identical with Mañjuśrī; but in China they seem to be regarded as distinct personages, called respectively Chi-kin-kang-shin and Miao-ki-ts'iang or Wen-shu. In all the Northern schools, however, Mañjuśrī is ranked along with Avalōkitēśvara; conf. Vassilief, p. 125; Burnouf, *Introd.*, pp. 100, 101. Ghantāpāṇi is the proper Bodhisattva of Vajrasattva (Hodgson, *Essays*, p. 94). In China, the place to the left of Buddha is often occupied by Ta-shi-chi-p'u-sa or Mahāsthānaprāpta, who properly belongs to the retinue of Amitābha, the favourite Jñāni Buddha. It is apparently doubtful whom he represents; Schott says Maudgalyāyana, but we find in some of their temples groups consisting of Dipaṅkara, Avalōkitēśvara, Samantabhadra, Mañjuśrī, Śāriputra, Mahāsthānaprāpta, and Maudgalyāyana (Tei-tseu). Maudgalyāyana, however, was “the disciple of the left hand,” and this agrees with the position assigned to Mahāsthānaprāpta in China, and that given to Vajrapāṇi in India. Śāriputra, as the representative of complete esoteric wisdom, might be supposed to be the proper analogue of Mañjuśrī; and Maudgalyāyana—pre-eminent for the force of divine faculties—as that of Avalōkitēśvara. Neither Mahāsthānaprāpta nor Samantabhadra are mentioned by Hiwen Tsang. As the former is represented with a small chaitya or dāgaba on his forehead to contain the relics (*śarīra*) of Buddha, and a *vajra*, he is probably the same as the Vajrapāṇi of the caves. He is called Seisai in Japan; and Samantabhadra is called Fu-gwen.

high beaddresses and aureoles behind their heads, and opposite to them are three females or Dêvis—one bearing a flower-stalk. These are, doubtless, the Târâs or female counterparts (*bodhisattvasamuchchayâs*) of the Bodhisattvas. Close to this, in the back of the verandah, is a door into a cell with a low broad bench or bed on the right side. Next to this is a shrine, with Buddha seated cross-legged on a throne, with four armed dwarfs at the corners, his hands in the *bhūmisparśa mudrâ*,¹ that is, the left lying open in the lap and the right over the knee, with the back turned outwards. A small half figure of a female, in front of the throne and towards Buddha's right, holds up a jar. This is probably intended to represent Sujâtâ,² the daughter of Senâni, who offered boiled milk to Gautama, just before he became a Buddha.

The *chauri*-bearers are, as usual here, the two Bodhisattvas, the *vajra* or bolt of the left one being supported on a flower by his side. On the same side are also three other standing figures, the first with a flower, the second with a large round bud, and the third with a pennon. Opposite these last are other three—the last with a long straight sword. A pair of *gandharvas* appear over each shoulder of the Buddha, and on the side walls over the Bodhisattvas are six Buddhas seated cross-legged on two shelves. To the north of the door into this shrine, a little figure kneels in an arched recess.

The central door leads into a room about 30 feet wide by 20 feet deep, and 8 feet 9 inches high, with two square pillars in the middle, and partially lighted by an opening in the wall on each side of the door. In the shrine behind it, 13 feet wide and 8 feet 9 inches high, is an image of Buddha on a *simhâsana*, in the *bhūmisparśa mudrâ*, with the usual Bodhisattvas as attendants—Vajrapâni holding the thunderbolt in his uplifted right hand.

The shrine door to the left of this has mouldings round it, and lions carved at the foot of the jambs on the step. The sculpture inside is very similar to that on the other side of the principal shrine, but with the addition of a fat male figure on the front wall to the left of the entrance, and a female on the right.

On the verandah wall, between this and the door into an unfinished cell, is a figure of Dharma—that might be mistaken for Lakshmî—four-armed, with water-pot, lotus, and rosary,—also two other female figures.

A stair in the rock leads up to the third storey, which has a hall 101 feet long, by 21 feet deep and 9 feet 7 inches high, but badly lighted on account of two large blocks left on each side the vestibule leading into it from the verandah. All the light admitted comes through this vestibule 30 feet wide and 15 feet deep, and through a narrow door and passage at each end. In the hall is one row of eight square pillars running from end to end. The pillars of the verandah have very thin plain brackets, and but little ornament on their square shafts (pl. xvi, fig. 5). Outside them is a low parapet wall. Inside, the pillars are perfectly plain. At the south end of the verandah is an empty cell, and in the inner walls are three slight cuttings, the beginnings of cells. In the middle of the back wall is an ante-chamber with two square pillars in front, and through it is the shrine containing a

¹ Also called the *dharma-parśa mudrâ*; the fingers of the right hand usually touch the seat.

² Sujâtâ = Eugenia: for the story, see Bigandet's *Legend of Gaudama* (3rd ed.), vol. i. p. 82; S. Hardy's *Manual of Buddhism*, p. 170; Beal's *Fa-hian*, p. 121, and *Romantic Legend*, p. 194, where Sujâtâ's father is called Nandika. In the *Lalitâ Vistara*, as in some of the other versions, there are two sisters, Trapushâ and Bhallikâ, who prepare the milk for him; in other accounts they are called Nandâ and Nandabalâ, daughters of Sujâta, the lord of the village. E. Arnold, in his *Light of Asia*, quite alters the legend.

seated Buddha in the teaching attitude, with Avalôkitêśvara or Padmapâni and Mañjuśrî or Vajrapâni only as attendants. At the north end of the hall is another shrine, with a Buddha squatted on a throne and attendants. On the walls of this cave are many small figures of Buddha, a Padmapâni with four arms, figures seated on lotuses, in the *lalitâsana mudrâ*, with one foot under them and the other on the ground—both male and female. Figures of Mahîśāsuri and Gaṇapati on the south wall are evidently of late date.

CAVE XII.—THE TIN THÂL.

The twelfth and last of the series of Baudhdha caves here is the Tin Thâl or three-storeyed cave-temple, adapted for worship rather than as a monastery. This is, of its class, one of the most important and interesting caves at Elurâ. In no other series do we find a three-storeyed vihâra carried out with the same consistency of design and the like magnificence as in this example, and from these circumstances there is a grandeur and propriety in its appearance that it would be difficult to surpass in cave architecture. The greatest interest, however, lies in its being a transitional example between the styles of the two great religions which divide between them the principal examples of the architectural magnificence of the place. On comparing it with the Dâs Avatâra Cave, that all but immediately succeeds, it seems almost as if the builders of this cave had been persuaded to change their faith and by gentle means to adopt the new religion, and not that they had been converted by persecution, as has been very generally supposed. So gently, indeed, does the change seem to take place, that we can hardly detect it in the architecture, though the sculptures announce it with sufficient distinctness. But the mode in which sculpture is substituted in the upper storey of this cave for the arrangement of cells in the older and genuine vihâras, shows that a change was creeping over the form of the religion long before it pronounced itself by the acceptance and adoration of the new gods.

The inner portion of the court is 107 feet wide by about 46 deep, but just inside the entrance an area of 46 feet by 19 feet has to be added to this. On the right side of this latter is a stair leading up to the top of the front wall of the court.

The lower hall, which is open in front, measures about 116 feet by 42 feet and is 11 feet high, the roof being supported by twenty-four square pillars in three rows, with pilasters along the back wall. In the left or north end wall are three cells, each with a stone bench in it, and in the south end are two cells and an open apartment forming a lobby to the stair leading up to the first floor. In the back wall are also four cells, two near each end, and in the middle is a large antechamber to the shrine, 37 feet wide and 40 feet deep, with two square pillars in front, and four more supporting the roof, with corresponding pilasters on each side wall, having a cell on each side between the first and second pilasters.

Between the two pilasters, on the back wall of the hall to the left of the antechamber, is a large compartment carved in nine square panels (plate xix, fig. 6), each sculptured with a different figure. Buddha himself occupies the centre with Avalôkitêśvara on his right hand and Vajrapâni or Mañjuśrî on his left. The figure in the middle of the upper row has a sword supported on a lotus flower—a symbol borne by different Lôkêśvaras, such as Mañjuśrî, Simhanâtha, and Mahâsthânâprâpta; possibly it may be the last of these. The figures on each side of him have branches of different sorts, and those in the lower corners have a pennon and a book similarly upheld, while the middle one has a closed

lotus bud.¹ Which of the Bôdhisattvas each of these is we can hardly say, but the corner four may perhaps be Ratnapâni, Ghaṇṭâpâni, Maitrêya, and Samantabhadra; or the six above and below may be analogous to a group sometimes met with in China, including Śāriputtra and Maudgalyāyana (the two *agraśrāvakas*), Samantabhadra, Ānanda, Kāśyapa (the *Ārya Sthavira*), and Râhula (Gautama's son).² But it is not improbable that such designations as Vajrapâni, Padmapâni, Mahâsthânâprâpta, Kshitigarbha, Ghaṇṭâpâni, &c., were first given for obvious reasons to figures of the favourite disciples of Buddha, and that afterwards the original names dropped out of use, and the epithets became designations of Bôdhisattvas—a class of beings not recognised by the schools of the Hīnayāna. But whatever be their names, they correspond with the standing figures we meet with so frequently in the shrines at Elurâ, arranged side by side along either wall.

In a corresponding area to the south of the antechamber has been a figure of Buddha seated cross-legged with Avalôkitêśvara and Mañjuśrî³ as attendants, but this sculpture is very much destroyed.

On all the pilasters of the antechamber figures have been sculptured; in three cases Buddha occupies the upper part of the area with the usual Bôdhisattva attendants; and below, on one, is a female, Târâ, with the lotus; on another, Buddha alone; on a third, the same with attendants; on a fourth, another female; and on a fifth, Buddha with a four-armed *dêvî*—perhaps Dharma (repeated thrice below) having an elongated object in her lap and a sort of sceptre in one of her left hands.

In recesses on the right are large figures of Buddha cross-legged on *siṃhâsanas*, with attendants having flowers of different sorts in their hands. On each side of the shrine door are seated fat guardian figures, each holding a flower stalk; that on the right (south) side has a book laid over the opening bud, and hence may represent Mañjuśrî.⁴

On the wall of the small lobby from which the stair ascends, the sculpture of nine panels is repeated, but is much defaced; there is also above it a Buddha between two *chauri*-bearers, one with a flower and the other with a bud covered by a book, to his right a female holding a flower-stalk, and to the left a four-armed Dêvî with a rosary and bottle or goglet.

Ascending the stair, at the turning we enter a small room about 23 feet by 15, with two pillars in front, looking into the court, on the back wall of which is carved a large cross-

¹ Mr. Beal suggests that this may be Kshitigarbha, the Ti-tsang p'u-sa of the Chinese; see Vassilief, pp. 170, 175.

² In China Ānanda and Kāśyapa often stand next to Buddha in the shrines, and with Mañjuśrî, Samantabhadra, Śāriputtra, and Maudgalyāyana, form a group of six; but in China and Japan, Buddha has sometimes Mañjuśrî on his left mounted on a lion, and Samantabhadra on an elephant at his right.—Edkins, *Rel. in China*, p. 229, and *Ann. du Mus. Guimet*, tome iv, p. 276, and plate vii, p. 110. In Ceylon the usual attendant figures are Mogallano and Sariputto (the two *aggasāvakas*), Râhulo, Ānando, and Kassapo.

³ Mañjuśrî appears under many names, as Mañjunâtha, Mahâmati, Kumârarâja, Khadgin, Vajradhara, Vibhuṣana, Sârdûlavâhana, Simhakêli, &c., and sometimes bears a sword in his right hand, and a book on a lotus flower in the left. He is the apotheosis of transcendental wisdom, as Avalôkitêśvara is of mercy. He has two wives, Sarasvatî and Lakshmî, and in China is regarded as presiding over air [wind]. He is the prince of eloquence and spiritual son of Sâkyâ. The worship of Mañjuśrî and Avalôkitêśvara seems to have come into vogue in India before the time of Fah-hian (A.D. 400). He is regarded as the special protector of Nepâl, and the Emperor of China is styled his incarnation.—Beal's *Fah-hian*, p. 60; *Jour. R. As. Soc.*, vol. xvi, p. 204; Caoma, *Tibet. Gram.*, p. 182 ff; *As. Res.*, vol. xvi, pp. 459–473; *Jour. As. Soc. Ben.*, vol. xii, pt. i, pp. 402, 404, 408; Barnouf, *Lotus*, p. 498 ff.

⁴ The shrine has been fully described in *The Cave Temples*, p. 382.

legged Buddha seated on a *simhāsana*, with Gandharvas above him and the two favourite Bôdhisattvas as *chauri*-bearers. To the right and left of this are the nine panels again repeated, and over that to the right are three arched compartments containing figures of four-armed goddesses similar to those representing Dharma and Saṅgha in the mythology of the northern Buddhists, the second with lotus bud and attendants, and the third with perhaps a bottle and *shankh* or conch shell. On the east wall is a four-armed Dêvī with something like a dish filled with fruit or food in one of her left hands on her lap, and holding a lotus, &c. Then Buddha and attendants; and again two figures of the four-armed goddess, her two front hands laid on her knees; and lastly, Buddha with attendants.

On the west wall is Padmapāṇi seated with one leg tucked under him and his hands on his knees (plate xviii, fig. 3). To his left is a goddess, probably Tārā or Prajñā, with a dāgaba on the front of her headdress, and with the right foot down over the *padmāsana* or lotus seat, and the left doubled up on it (*lalitāsana mudrā*). Her right hand lies over her knee with the palm turned outwards (*vardha* or *vara mudrā*), the attitude of bestowal, and the left holds the stalk of a flower. On the other side is a fat figure with the right foot raised upon the seat, and a bud at his elbow.¹ Outside this compartment to the left are two females in the attitude of supplication, and above them a male figure with a flower-stalk—the usual badge of a Bôdhisattva.

Ascending the other half of the stair, we land in a small room at the south end of the verandah of the second storey, which is on the same plan as the upper floor of the last cave, but with a larger hall (pl. xiv, fig. 2). The verandah is 116 feet long by 11 feet wide and 12 feet 2 inches high, with eight square pillars in front, and with a small room at each end, forming at the south the landing for the stair from the ground floor, and at the north the entrance to the stair ascending to the upper floor. From each of these a still smaller apartment opens; that at the south, a small cell with a stone bench; the other, a recess, with an image of Buddha seated with the wheel-emblem between his feet, his hands in the *dharmachakra* or teaching *mudrā*, and in front, on the ground, two deer. Padmapāṇi and Vajrapāṇi, with *chauris*, stand on each side, coarsely executed. On the wall, opposite the foot of the stair, are Padmapāṇi and two female figures, and, above them, a dāgaba, a Buddha, and a male and female, each with flower-stalks.

The hall lies back from the verandah, and is entered through a vestibule about 36 feet wide by 18 feet deep, with two square pillars in front and back, and also by side doors at the ends of the verandah. In each of the large blocks of rock left two cells are carved, facing the hall, which is 118 feet from north to south, by about 34 feet deep and 11 feet 5 inches high, divided into three aisles by rows of eight square pillars each—two of them partly hewn away. In each end of this hall, including the passage from the end door, are four cells; and in the back wall are five more. The antechamber to the shrine is 36 feet wide, with two pillars in front.

In the north end of the vestibule of the hall is a large sculpture of Avalôkitêśvara seated between two females (Lôchani² and Tārā), the one on his left hand having a bottle

¹ This is apparently one of the Triads of which the Bauddha sects have so many, in one of the chief of which Padmapāṇi is identified with the Saṅgha, the other two being Buddha and Prajñā who represents the Dharma. It is in connection with this Triad that the Northern Buddhists have the famous mantra,—

Oṃ saraa vidye hoṃ | Oṃ Prajñāya hoṃ | Oṃ maṇi-padme hoṃ ||

² She occupies a high place in the Mahāyāna mythology, and is represented as the second constituent of the *Trikāya* or "threefold body," or that endued with the *sambhōgakāya* of absolute completeness, and the equivalent or counterpart of the Saṅgha in the *Triratna*. In Nepāl she is the *śakti* of Akshôbhya.

before her; the other had a flower-stalk by her side. On the pilaster to the left are a squatting figure of Buddha, two male figures, and four females, with different flowers. On that to the right is a dāgaba and flag, a squatting Buddha, and a Bodhisattva with a flower. Behind this is a repetition of the sculpture with the nine figures, only here Buddha is in the centre of the upper row. On the south end is a repetition of the sculpture on a smaller scale, but with two *Dēvīs* on each side.

On the north pilaster of the antechamber to the shrine is carved a dāgaba, with a Buddha on the front of it; below it a squatting Buddha, and still lower a *Dēvi* with a flower branch. The shrine door is plain, but has large figures of Padmapāṇi with his lotus and rosary, and Vajrapāṇi with his *fulmen*, as guardians.

The shrine itself is about 22 feet wide, 19 feet deep, and 13 feet 8 inches high. It contains an enormous image of Buddha seated cross-legged in the *bhāmisparsā mūdṛā*, with the left hand in the lap and the right lying over the knee. In front of the low *padmāsana* or *Bōdhiṃaṇḍa*, on which he is seated, is a female (Sujātā?) holding up a jar, and to the left is another standing over a prostrate human figure. Against each side wall stand five tall Bodhisattvas. On the right side are (1.) Avalōkitēśvara or Padmapāṇi as *chauri*-bearer (*chāmarika*); (2.) a figure with a bud in his right hand; (3.) another with a sword; (4.) a fourth with his hand raised; and (5.) one with a lotus flower; and on the front wall on a high seat squats a female holding a flower-stalk. On the left side, as in the upper shrine represented in plate xx, fig. 1, are (1.) Vajrapāṇi, with the *vajra* on the top of the flower-stalk; (2.) the second with an opening flower, and holding some small object in his right hand; (3.) with a full-blown flower and a small object; (4.) with a flag and small object; and (5.) with only a bud in the right hand. On the front wall is a stout male, with a round object in the right and a long curling one in the left hand. This is probably the excavator of the cave. On shelves above are seven Buddhas on each side seated cross-legged.

On the jamb of a window that lights the stair ascending to the upper storey is a small figure on horseback with two attendants, and above is a female with a flower.

The upper floor of the Tin Thāl is by far the most splendid hall among the Bauddha Caves of India. It measures 115 feet in length by 64 deep from the inside of the first row of pillars, and 12 feet 2½ inches high, the roof being supported by forty square pillars in five rows, inclusive of the front one. At the back also it has an open antechamber 37½ feet wide, the front divided by two pillars, and 16½ feet deep. Unlike the monastic halls of the Ajanṭā vihāras, this has no cells for residents. Five recesses in the south and four in the north end wall contain nine colossal images of Buddhas¹ with their attendants, but unfortunately all the sculptures have been more or less broken, scarcely a figure being left entire in this splendid cave.

Along the back wall of the hall are fourteen large cross-legged figures of Buddhas, seven on the north, and as many to the south of entrance of the antechamber to the shrine. Those on the north side have each his hands in his lap—in the *Jñāna mudṛā*, aureoles behind their heads, and trees rising from behind them, with foliage carefully varied in each case. These must represent the supposed seven last Buddhas, viz. (1.) Vipasyī; (2.) Śikhī; (3.) Viśvabhū; (4.) Krakuchchanda; (5.) Kanaka Muni; (6.) Kaśyapa; and (7.) Śākya Siṃha, whose *Bodhiṃrikshas* or sacred trees, according to Mahanāmo in his

¹ Possibly Dipaṅkara, Ratnagarbha, Vipasyī, Śikhī, Viśvabhū, Krakuchchanda, Kanaka Muni, Kaśyapa, and Śākya Siṃha.

Tika on the *Mahāvanso*,¹ were respectively (1.) the Pātali or trumpet-flower, *Bignonia suaveolens*; (2.) the Puṇḍarika, a fragrant kind of mango; (3.) the Śāla, *Shorea robusta*; (4.) the Śirisha, *Acacia sirisa*; (5.) the Udumbara, *Ficus glomerata*; (6.) the Nyagrōdha, *Ficus Indica*; and (7.) the Pippala or Aśvattha, *Ficus religiosa*. Corresponding to these, on the southern portion of the wall, are other seven very similar figures, all in the *dharmachakra mudrā*, or having the hands in the teaching attitude. From the nimbus behind each head springs a circular flower forming the centre of the underpart of an umbrella (*chhatra*), with a *gandharva* at each side supporting it and carrying a gift. If these, as is probable, are different from the seven to the north of them, I would venture to suggest that they may be the divine Buddhas—Vairōcana,² Akshōbhya, Ratnasambhava, Amitābha, Amōghasiddha, Vajrasatwa and Vajrarāja; but they may really be only the Mānushiya Buddhas differently arranged.

The researches of modern scholars have done much to illustrate the ethical system of the Bauddha doctors, and to acquaint us with the legends that fill their works, but so little attention has as yet been devoted to the practical creed and mythology of the common people, and the liturgical ceremonies of the worship that was daily practised in their temples, that in the whole round of the literature on Buddhism published within the last fifty years,³ we have but little to help us in identifying the sculptures on the walls of these Bauddha Cave Temples, though representing the beings that the great mass of Buddhists were most taught to reverence, and which occupied their minds far more than the subtle distinction between the heinousness of a *pārājikā* and a *dukkata* sin, or the contents and meaning of the *suttas*. The result of this is, that Western opinions of Buddhism, founded on the abridged legends of an idealised Buddha and the moral maxims of Buddhist philosophers, is one-sided and very defective. Special and detailed researches have still to be made into the progressive developments of Buddhism and Bauddha ritual, and for these there doubtless exist abundant materials in the Sanskrit works found in Nepāl, and in the translations of China and Tibet, as well as in the ceremonials still in vogue in these countries. For though Buddhism began with a purely ethical theory, and, as an atheistic system must do, it made little at all of worship—yet in course of time, as the cave sculptures testify, it began to develop a mythology which went on increasing, until, in all countries where the Mahāyāna schools prevailed, Buddhism became one of the most fantastic and grossly idolatrous religious systems in the world. The earlier elements of their pantheon are represented in the Cave Temples of Kaṇheri, Ajanṭā, Aurangābād, Bhājā, and Elurā; its later developments are described in the great *Sāstras* of Northern Buddhism, most of which are as yet inaccessible except to a very few Sanskrit scholars. Indian Buddhism, as we learn from the records of the early Chinese pilgrims and the cave sculptures, was to a very large extent of the Mahāyāna form, and it is only from the literature of the schools of that sect we can hope to learn much about it.⁴

¹ Turnour's *Mahāvanso*, int. p. xxxiii, xxxiv; conf. Cunningham, *Bharhut Stūpa*, pp. 113, 114, and plates xxix, xxx.

² Vairōcana is the sun, and also the counterpart of *Dharma* in the *Triratna*, as representing the essence of Buddha and Lōchanā.

³ The works of Burnouf, Köppen, Hodgson, and the fragment published by Vassilief in 1859, are the best we have on this branch of the subject, and even these only treat of it incidentally.

⁴ It is much to be regretted that the valuable collection of drawings presented by Mr. B. H. Hodgson to the French Institute in 1863 have not been published. His papers and illustrations in the *Trans. R. A. Soc.*, vol. ii, and *Jour. R. As. Soc.*, vol. xviii, are most valuable, but we need many more details to illustrate satisfactorily the pantheon of the Buddhists.

On each end wall of the antechamber leading to the shrine are three Dêvis—the inner one on each side with four arms, and holding a rosary and crooked rod—perhaps Dharma as Prajñâpâramitâ. The others have only two arms each; all are seated on open lotus flowers on raised thrones, have high crowns or tiaras and aureoles, and the left hand is raised, the fingers extended, and with the tips of the forefinger and thumb each holds the stalk of a lotus or similar flower; the right hand on the knee holds another stalk, and all have bracelets formed of many rings, and necklaces. Three other figures on each side the shrine door cover the back wall. Each has her left foot tucked up before or under her, and the right down upon a lotus flower, or in the *lalitâsana mudrâ*. The thrones are supported by Nâgas, &c. One of these figures, to the left of the shrine door (plate xix, fig. 5), has an upright *vajra* supported on the flower she holds, and as this identifies her as Lôchanî, the *Buddhîśaktî* of Akshobhya, we may regard the other four on one side the room as her associated goddesses,—Vajradhatêśvarî, Mâmukhî, Pândarâ, and Târâ.¹ The other five, if different, must then be the five Târâs—Sîtâ-târâ, Ugrâ-târâ, Ratnâ-târâ, Bhṛīkuṭî-târâ, and Viśvâ-târâ.² Above these are four Buddhas on the back wall, on each side the door, and five on each end wall.

The shrine door is plain with bold mouldings and but little carving. The *dwârapâlas* have very high caps, and stand with their arms crossed, and by the door jambs are small couchant lions.

The shrine is 21 feet wide, about 24 feet deep, and 14 feet 4 inches high, and the large Buddha is fully 11 feet high, and from knee to knee is 9 feet, while his feet measure 2 feet 6 inches in length. He is seated cross-legged in the *bhâmisparśa mudrâ*, or that in which he attained Buddhahood, with the left hand in the lap and the right over the knee, pointing to the ground.

His nose and lips have been broken off by the Musalmans, but are supplied in plaster, and the whole figure is frequently whitewashed. Round the seat and image is a dark passage by which it may be circumambulated. On the floor against the front of the throne are the two female figures already noticed as found in the same position in other shrines.

On the sides of the shrine are five tall standing figures of Bôdhisattvas against each wall. On the left side are (1.) Padmapâni with a *châmara*, his face destroyed but restored with plaster, as Hanuman's; (2.) a Bôdhisattva with a flower bud; (3.) another (perhaps Viśvapâni) with a long sword in the left hand, and a bud or small fly-flap in the right; (4.) the next has a pear-shaped object, and a similar small *chauri*; and (5.) the last has some object not recognisable in his left, and a similar bud or small fly-flap in the right.

The sculpture on the left wall is represented on plate xx, fig. 1. Here on the upper part of the wall are five figures of Buddha, all in the *Jñâna mudrâ* or attitude of meditation. Below on the left and next to the great image of the shrine is Vajrapâni acting as *châmara*-bearer to the Buddha, and easily recognised by his very rich headdress, necklaces, jewelled belt, armlets, &c., as well as by the *vajra* or fulmen, supported on a half-opened bud which rises over his left arm. To his left are other four smaller figures—though all much larger than life size—each holding some symbol by which he might be recognised. Thus, the next carries a book, and is perhaps Samantabhadra, the third and fifth hold buds in their left hands, and perhaps some sort of fruit in the right, and the fourth has a small flag or pennon; all stand on lotus flowers, and have very rich headdresses, which vary,

¹ These are respectively the *śaktîs* of Vairochana, Ratnasambhava, Amitâbha, and Amôghasiddha.

² These are the wives or *śaktîs* of Samantabhadra, Vajrapâni, Ratnapâni, Padmapâni, and Viśvapâni respectively, but even their names are scarcely to be found in any Sanskrit dictionary.

however, in minute details. On the front wall is a seated male figure with an object like a purse on his left knee, and something like money in his right hand; below him is a *kamanḍalu* or water-jar, with flowers growing out of it; on the other side of the door is a female figure squatting and holding a bud. On the walls above are Buddhas seated cross-legged, five on each side wall, and two on the front wall.

Before leaving these figures it may be worth while comparing them with the analogous ones in the Bāgh caves in Mālwa.¹ In the antechamber of the shrine of the most entire cave there (No. I.) are four large sculptured panels; on each end Buddha between two attendants (plate xviii, fig. 4), and on each side the shrine door is a Bôdhisattva about 10 feet high, represented in figs. 2 and 3 of plate xx.² That on the right has had his right hand broken off, so that its original position is no longer recognisable; but the general style of both figures is so like those we find at Elurā, that they cannot be mistaken; and the resemblance to the Bôdhisattvas in the Aurangābād caves is still more striking.³ In both places the figure of Avalôkitêśvara is distinguished by the scantiness of the dress and the absence of jewellery, while that of the other Bodhisattva is marked by the jewelled belt, armlets, bracelets, rich *mukuta* and necklaces, while he wears a jewelled cord like the Brahmanical *jânvi*.

The figures that attend on Buddha in the panels in the ends of the antechamber (plate xviii, fig. 4), are perhaps different persons, though the one with the *chāmara* on his right is again distinguished by his rich *mukuta*, jewelled belt, *jânvi*, and necklace, from the other who bears only flowers in his hands. They are each about $7\frac{1}{2}$ feet high.

This is the last of the series of Bauddha Caves here, and probably one of the last excavated in India. In plan and arrangements, it bears a striking resemblance to the Dās Avatāra Brahmanical Cave close by,⁴ and, as already indicated, it is very probable they were excavated about the same period. It exhibits the early Mahāyāna mythology of the Yôgāchārya school⁵ in a more developed state than any other cave in India, and can hardly be ascribed to an earlier date than about 700 A.D.

CHAPTER IV.

THE ELURĀ BRAHMANICAL CAVE TEMPLES.—THE DĀS AVATĀRA AND KAILĀSA.

THE Brahmanical Caves⁶ begin at a distance of about fifty yards north of the Tin Thāl, the first we meet with being a large plain room, probably intended as a rest-house for pilgrims (see plate ii).

In the large cave close to this, known as Rāvaṇa-ka-Khāi, the transition to the Brahmanical form is complete. There is nothing in either its architecture or its sculpture that can be mistaken for anything the Buddhists ever did. There are, however, as yet, no

¹ *Cave Temples*, pp. 363 ff.

² In Captain Dangerfield's account of the Bāgh Caves, *Trans. Liter. Soc. Bombay*, vol. ii, pp. 194 ff, are drawings of these figures, but very inaccurate. Dr. Impey's description of the caves, *Jour. Bom. B. R. As. Soc.*, vol. v, pp. 543 ff, is not illustrated.

³ Compare plate liii in *Reports*, vol. iii, p. 76.

⁴ Compare *Cave Temples*, plates lxiv, lxv, with plates lxxiii and lxxiv.

⁵ This school, founded as already mentioned, perhaps about A.D. 300, acknowledged the existence of a soul in the universe. The other principal school of the Mahāyāna was the Madhyamika or followers of Nāgārjuna. See Vassilief, pp. 262, 286 f., 321.

⁶ See *Cave Temples*, introduction to chapter v of Book III, p. 431.

violent contrasts. The plan of the temple and the position of the shrine¹ are not unlike what we find in the latest caves at Aurangâbâd and in Cave No. VIII. and the ruined south wing of Cave V. here; and the substitution of sculpture for cells—which are not required in Brahmanical caves—is only carrying out the system inaugurated in the Tin Thâl.

A plan of this Cave will be found in *The Cave Temples*, plate lxx, fig. 2, and its sculptures are described in sufficient detail, pp. 432–435 of that work, to dispense with anything further being said on the subject here. It has almost certainly been dedicated to one of the goddesses—forms of Pârvati, but—like the Dâs Avatâra, a large cave at Karusâ, a small one at Aihole, and some of the earlier temples—its sculptures are partly Vaishnava and partly Śaiva.

THE DÂS AVATÂRA CAVE.

The next cave is a two-storeyed one, and one of the largest in the Brahmanical group. Plans of both floors are given in *The Cave Temples*, plates lxxiii and lxxiv, and on plate xxiii, fig. 2, of this volume is added a transverse section of the cave and through the court, with its central maṇḍapa. Though on a small scale, this will help to illustrate the arrangements of the cave, and show how the sculptures are disposed on the left wall of the upper floor. Outside, on the end of the balcony, is a four-armed Rudra in a state of frantic excitement, but a leg and one of the hands are broken off.



No. 12.—The Dâs Avatâra Cave, from a photograph.

The general appearance of the front of this cave, as seen from one side of the court, is illustrated by the accompanying woodcut (No. 12), in which the roof of the hall in the court is seen in the foreground.

¹ We observe the earlier approaches to this arrangement in the isolation of the image in some of the Ajantâ caves, and in a more marked form in the shrine of Cave XVI there. See *Cave Temples*, pl. xxxiii.

The front pillars only have any carving upon them, all the rest inside being plain square shafts. One of these pillars in the upper storey is represented on plate xxi, fig. 1, and the shaft of the pilaster in the north end of the balcony in fig. 2, and a glance at them will show how strangely like Buddhist work they are. In the pilaster the little figure of Lakshmi in the lotus flower might readily be mistaken for a Buddha one, and the dancing female and musicians below we have the exact counterpart of in the Aurangâbâd Buddhist shrine No. VII,¹ while the *gandharvas* and *gana* are quite as common in the works of that sect as in those of the Brahmans.

The pillar (fig. 1) is at first sight still more strikingly Buddhist. The figure on the end of the bracket most closely resembles Buddha in the *bhūmisparśa mudrâ*, and the figures coming out of the mouths of *mākaras* are what are found behind most figures of Buddha in the shrines. How this came here is difficult to surmise. On the lower part of the capital the sculptures are more Brahmanical: the *nāga*-like figure in the centre is Vishnu, and the flying one below him is Garuḍa, while the Nāgas and their wives at each side are found also in other Vaishnava sculptures.²

The stair lands in the north end of the front aisle, so there is no carving there; but in the end of the next cross aisle is the figure of Bhairava trampling on Kālī, which forms one of the most terrible and expressive sculptures in these caves (see plate xxii, fig. 2). The next compartment or chapel has Śiva, eight-armed, dancing the dread *tāṇḍava* amid his followers (pl. xxi, fig. 4). At the end of the fourth aisle is an altar, but without any image now. The next contains Śiva, four-armed, seated with Pārvatī, two-armed, and supposed to be playing *chausar*; while below, or in front of the seat, is the Nandī or bull and the dwarf *gana* frolicking about him. The sixth has the usual sculpture of Rāvaṇa under Kailāsa, attempting to carry off Śiva and his consort, while the *gana* are represented as expressing their contempt for the many-handed monster in the vilest way. The next two compartments, being on the back wall, do not appear in the section; the first of them contains Śiva springing from out of the *liṅga* to rescue his worshipper Mārkaṇḍeya from Yamadaitya, the messenger of death (plate xxiv, fig. 1)—a myth but rarely represented in Hindu sculpture, but which also occurs in the corridor behind Kailāsa, which is also represented on the same plate. The second compartment contains Śiva and his consort, with Nandī and attendants. The pillars in the front of the antechamber have struts, each carved with a pair of figures and foliage somewhat like those in the great cave at Bādāmi,³ but of much ruder workmanship. On the left side of the chamber is a very large figure of Gaṇeśa or Gaṇapati, the god of policy—a figure which, though in modern times so universal a favourite and so constantly represented, is but sparingly so in the earlier mythology of the caves. On the back wall, to the right of this last, is a goddess—perhaps Pārvatī—with a rosary in her hand, and musicians on each side. She sits on a lotus, and two figures below, among foliage, hold the stalk, as the Nāga figures do under the images of Buddha. The *dwārapālas* of the shrine-door are four-armed, and have the *vajra*, snake, and club. The *śāṭṭhāṅka*, or altar round the *liṅga*, in the shrine, has been destroyed by the Muhammadans, but the *liṅga* has perhaps been left unmoved. Whether any valuables were found around its base is, of course, unknown.

¹ *Reports*, vol. iii, plate liv, fig. 5, and p. 78.

² *E.g.*, in Bādāmi Cave III. See *Reports*, vol. i, plate xx.

³ *Archæol. Reports*, vol. i, pl. xxiv to xxx. Compare also *Cave Temples*, pl. xlv, fig. 2.

The other side of the cave is similarly sculptured. On the right of the shrine-door is Lakshmi, with four elephants pouring water on her. She is seated, similarly to the figure on the other side, on a lotus upheld by figures below, and holds a lotus and a custard-apple in her hands. Two four-armed attendants offer jars of water, and hold the *śankh*, *chakra*, and lotus. On the right end of the antechamber is a figure of Vishnu, with his *trīśula* and lotus, attended by a large bird, which eats from his right hand, and a dwarf stands at his left.

On the back wall is a figure of Śiva inside a great pillar or *līṅga*, from the sides of which issue flames (plate xxi, fig. 3). On the right hand Vishnu is represented worshipping it, and again as Varāha digging down to try and find the bottom of it. On the other side is Brahma worshipping, and also flying up to try to discover its summit. The legend here referred to is well known among the Lingayats. The next compartment contains Śiva also, represented in a chariot with shield, sword, and bow, while Brahma drives the four horses (the *Vedas*) yoked to it.

The south wall is devoted to Vishnu, and the back compartment contains that god as Kṛishṇa with six arms, holding up Govardhan Hill above the flocks of Vraj. The next is the usual representation of Nārāyaṇa resting on Śēsha, who has here a human head, with seven seated figures below. The third is Vishnu riding on Garuḍa. The fourth niche contains a *vēdi* or pedestal for an image; the fifth has Varāha bearing Prithvi; the sixth is the Trivikrama or Vāmana avatāra, represented as at Bādāmi; and the seventh is Nara-siṃha wrestling with Hiraṇyakaśipu (plate xxii, fig. 1), who is armed with sword and shield. Outside the cave on the wall is a gigantic Śaiva dwārapāla, with long curly locks, and two cherubs above.

The maṇḍap in the front of the court is about 31 feet wide by 26 feet deep and 10½ feet high, the roof being supported by four square pillars with plain square brackets and moulded bases. It had a porch, in front of a perforated window, on the west side, supported by two pillars in front, but the right-hand or south pillar, with most of the roof, is broken away. Over this window are the remains of an inscription in fourteen long lines, containing twenty-nine and a half verses, now much abraded, but which has been partially deciphered by Paṇḍit Bhagvānlāl Indrajī,¹ and from which is made out a genealogy of the Rāshṭra-kuṭa dynasty, which ruled over the Dekhan from about A.D. 600 till towards the end of the tenth century.² The names here enumerated are:—

1. Dantivarmā I. (cir. A.D. 600-630).
2. Indrarāja I., his son (630-650).
3. Govindarāja I., son of Indrarāja (650-675).
4. Karkarāja I. (or Kakka), son of Govinda (675-700).
5. Indrarāja II., son of Karka (700-730).
6. Dantidurga (or Dantivarmā II.) Khadgavalōka, son of Indra II., A.D. 753,³ who overcame Vallabha, or the Western Chalukya king, Kirttivarmā II.

Nothing is made out respecting the construction of the temple, but the inscription may be taken as proving that it was finished, or at least in an advanced condition, when Dantidurga visited Elurā in the middle of the eighth century; and it is not improbable that he had

¹ *Cave Temple Inscriptions* (Bombay, 1881), p. 92; see also below, p. 59.

² Vide *ante*, vol. iii, pp. 31-33; *Ind. Ant.*, vol. vi, pp. 59-72; vol. i, p. 205; vol. v, p. 144; and vol. xi, p. 108; *Jour. A. S. Beng.*, vol. viii, p. 292; Fleet's *Dynasties of the Kanarese Districts*, sect. v.

³ This is the date of the Sāmangadh grant, *Ind. Ant.*, vol. xi, p. 110.



constructed it. The inscription breaks off, however, in the 30th verse, and has never been finished. Moreover, in an inscription of Kṛishṇarāja, the uncle and successor of Dantidurga, he is said to have established himself at the hill or hill-fort of Elāpūra, where was a splendid temple of Svayambhu Śiva.¹ May not this Elāpūra have been Elurā? There was a Hindu city on the hill, of which extensive remains are yet to be seen.

On the north and south sides of the maṇḍap are also perforated windows, and the door faces the cave. On the flat roof are tigers or lions at the corners, and three human or mythological figures between on each side. The door is in the style usual in the caves, with a plain architrave, and very small pairs of figures of gods and animals in the miniature representations of temples on the lintel. On each jamb of the door is a female figure with a small umbrella over the headdress, and a *chauri* on each side the head. On the corner pilasters are pairs of figures in embrace; and on the spaces between, in separate compartments, on each side, are one larger and two smaller male figures. On the north end are one male and three female figures on the four pilasters, and females in the larger intervening panels and in one of the smaller. On the north side is a curious *torāṇa* over the window; the corresponding one on the south side is empty. On the west side there are females on the corner pilasters only, and their hair is done up in the same style as in the figures in the temple of Virūpāksha at Pattadakal; two of the smaller panels are empty, and males fill two larger and two smaller ones.

In a small room on the left of the entrance to the court, Brahmā and Viṣṇu with a Dēvī occupy the left wall, and Gaṇapati the right. Inside is a shrine, which has never been finished, containing a round *śaḷuṅkha* bearing a *līṅga*, and behind it on the wall is a Trimurti. This excavation is of a very rude character, and probably belongs to a later age than the cave.

KAILĀSA OR RANG MAHĀL.

This Rock-Temple, strictly so called, is No. XVII. of the series as reckoned from the south, and has been pretty fully described in *The Cave Temples*, pp. 448 to 463, and illustrated in the six plates lxxx to lxxxiv. It was there shown that the resemblances both in plan and details between this and the temple of Virūpāksha at Pattadakal,² which was erected by the queen-consort of Vikramāditya II., of the Western Chalukya dynasty, about A.D. 730,³ give us strong confirmation to the conclusion, which is also supported by a fragment of an inscription found upon it, and other corroborative circumstances, that it was constructed in the reign of Dantidurga, the great Rāthod king (cir. A.D. 730-755).

It is by far the most extensive and elaborate rock-cut temple in India, and the most interesting as well as the most magnificent of all the architectural objects which that country possesses. It is therefore well worthy, not only of the few additional illustrations which this volume contains, but of even a much more complete series of drawings than the means at our disposal will allow.

¹ *Jour. As. Soc. Beng.*, vol. viii, pp. 295, 301; *Ind. Ant.*, vol. vi, p. 61. Al Mas'ūdī (cir. 940 A.D.) mentioned the caves probably under the name of *Alura* (B. de Meynard's transl., tome iv, p. 95; and *Cave Temples*, p. 367). The statement of the *Māhātmya* that the caves from Kailāsa to the Bauddha Caves were constructed by Ilarāja of Illichpur (*As. Res.*, vol. vi, p. 385) is, of course, of no authority, but it may have arisen from some tradition of this rāja of Elāpūra. Other forms of it say that Ilu or Ilarāja only cleaned and painted the caves about A.D. 900. See *Cave Temples*, p. 455 note.

² Described in the first *Archæological Report*, pp. 29-33, and plates xxxviii, xxxix, xl.

³ Conf. inscriptions from the temple, *Ind. Ant.*, vol. x, pp. 164-166; and *Arch. Sur. Reports*, vol. iii, pp. 125, 126.

In *The Cave Temples* are given plans of both storeys (plates lxxxi and lxxxii A) and the elevation of the south side of the temple itself. To these are now added in this volume plates iv, xxiii, fig. 1, and xxv to xxxi.


Plate xxiii, fig. 1, is a transverse section, on the same scale (20 feet to 1 inch) as the elevation (*Cave Temples*, pl. lxxxii), through the centre of the great hall, and continued north and south through the side excavations. This, together with the views in the frontispiece and the woodcut No. 13, will give a clear idea how the central fane is raised on a solid basement of rock about 27 feet high. Along the court, on each side, are seen the pillars of the colonnade and under the scarp of the rock on the east. On the north or left side, the section passes through a wider part of the colonnade below,¹ and through the hall of the Lankêśvara temple above, looking towards the door of its shrine, with its river goddesses on each side.



No. 13.—View of Kailāsa from the south-west.²

On the right side of the great temple, it will be observed that the rock has been excavated in four storeys, none of them ever quite finished. On this side there was a bridge from the south balcony of the great hall into the second storey, but it had been cut too thin for the rock to support so long a bearing, and had broken down. These halls on the south side are not carved with much sculpture, except the one containing the female mātṛis or demons,³ to the south-west of the central hall, and through which this section does not pass.

The fronts of the second and third storeys are protected above by handsome drips carved in the rock, quadrantal on the outer surface, and the under side carved in imitation of ribs, with a bearing rafter running horizontally through them, in the most perfect imitation of a carefully-jointed wooden construction. As may be seen from the accompanying woodcut (No. 14), the effect of this is very pleasing.



No. 14.—Eaves of the Second Storey on the south side of Kailāsa.

¹ Marked M on the plan, *Cave Temples*, pl. lxxxii.

² From a sketch by Dr. Jas. Fergusson, *Ind. and East. Arch.*, p. 335.

³ Marked E' on the plan, *Cave Temples*, pl. lxxxii A.

In the third storey, the four pillars which support the roof are connected by a sort of arches, and the roof of the area within the pillars is considerably raised by a deep cornice. A square area is left in the centre of the roof, opening into the small room above, and just filling the area between the four pillars in it, similar to opening in the roof of the rock excavation in the Uparkoṭ at Junāgaḍh.¹ The fourth storey has an opening from the outside on the top of the rock, where there is some carving on the surface, near to the highroad.

THE HALL, &c.

Among the details worth noting are the windows and panels of the great maṇḍapa or hall. There are six windows, two in front and two on each side, of which the one on the south-east is very much broken; the other five are represented in plate iv, figs. 1-5, of which figs. 1 and 2 are those in front, figs. 3 and 4 on the north side, and fig. 5 the remaining window on the south. Three of them are arabesques, of very rich but entirely different designs, and the other two are formed of a combination of animal and vegetable designs:² then the spaces left uncarved are pierced through to admit the light. They may seem scarcely adequate for the purpose for which they were intended, but as light also enters from the five doors, these admit sufficient additional light to dispel the darkness in the corners of the hall, as far as is really necessary in an Indian temple.

Among the sculptures may be noticed two representations of a favourite subject in the Brahmanical works of the eighth century—the destruction of Mahishāsura³ or the buffalo-headed demon, by Chaṇḍī or Durgā, an event commemorated in the festival of the Durgā-pujā or Daśarā, in the month of Āśvin (Sept.-Oct.)⁴ Fig. 6 is the representation on a panel on the outside of the north wall of the great maṇḍapa to the west of the balcony. Mahishāsura is here and in fig. 7 represented with a human body, as he is also in the large and spirited sculpture in the Yamapuri or Mahishamardini cave at Mahāvallipur,⁵ and differs chiefly in his not having the high *mukuta* or regal cap which he wears in the latter. In later sculptures he is almost always represented with the body of a buffalo⁶ and a man's head, or with a man's head coming out of the throat of a buffalo from which the goddess has cut off the head. In the Rāvaṇa-ka-Khāi the scene is represented on the left of the entrance, but there the demon is in the form of a buffalo which she has seized with one hand by the mouth, while with another she drives her *triśula* into him, and with another right hand holds a long sword. In both these sculptures he wears a rich necklace, and in the first has a heavy sword or bill in his hand. Her tiger, from which she has dismounted, has seized by the head one of the Asuras behind her. In fig. 7, which represents the large sculpture on the side of the porch by which the court is entered, and on its north wall, we find more accessories: the goddess Mahishamardini is mounted, but not astride, on

¹ *Archæol. Reports*, vol. ii, pl. xxi to xxiii.

² In the temple of Virūpākṣa, at Paṭṭadakal, which so closely resembles the Kailāsa in plan and details, the windows are of similar device.

³ He is identical with the Siṃhamukhāsura of the Tāmiḷ districts.


⁴ The *Chaṇḍīpāṭha*, an episode from the *Mārkaṇḍeya Purāṇa* celebrating her victories over the Asuras, is read daily in her temples.

⁵ *Cave Temples*, pp. 145-147. This cave is No. 32 in Carr's *Seven Pagodas*, pp. 7, 32, 49, 96, 149, 208, and *Trans. R. As. Soc.*, vol. ii, p. 261.


⁶ At Bādāmi there is a sculpture in a small cell off Cave I, in which he is also represented simply as a buffalo, *Arch. Sur. Reports*, vol. i, p. 16, and plate xix, fig. 1; *Cave Temples*, p. 404.

ELURA.-KAILASA.



FIG 1.




2.



3.



5.



6.



Scale of 1 Foot.

J. Burgess.

H. Conner, del.

1000
1000

1000
1000

her lion, as at the Seven Pagodas near Madras, and is trampling down the Asura's assistants, while she attacks him with her arrows, several of which have pierced his right arm, with which he wields a heavy club. His left hand and shield are broken away. Above are the Dévas and Maharshis rejoicing over the victory; among the former of whom may be recognised Indra on his elephant, Agni on the ram, Yama on the buffalo with mace and noose, Vishnu on Garuḍa; the fourth and the last in the upper row are probably Śāni or Saturn and Varuna, and below the latter is Śiva on Nandi. The remainder of the lower line consists of other superhuman beings, Rishis, Gandharvas, and Apsaras. Below the panel are some other figures, too much abraded to be identified.

On the right or south side of the entrance into the court, in a panel with a pediment over it, is another representation of this scene, in which the Asura is represented between the body and the head of the buffalo.

On the front of the maṇḍapa, to the north of the entrance, is a panel about $6\frac{1}{2}$ feet by 5 (plate xxvi, fig. 1), in which we easily recognise Śiva, four-armed, and standing on the back of a kneeling figure, with Umā or Pārvatī at his left side; he holds with one of his right hands what seems to be a long lock of hair, or else a cord coming out of the top of his head-dress, and at the same time apparently supports a Nāga-like female, perhaps intended for Gaṅgā, the widening tail representing the stream in its descent. Lower it reaches an ascetic Jāhnu, and (being drunk up by him) it again issues from his ear and descends among rocks, and is visited by an elephant and a goat. Beneath are seven half figures, possibly the Sapta-sindhava. The ascetic above standing on one leg may perhaps represent Bhagiratha, who by his asceticism prevailed on Śiva to bring down the Viyad-Gaṅgā¹ to the earth.

Two other panels are represented in plate xxv, figs. 2 and 3,—the first, from the east side of the south porch, and the other from the west side of the same. The first is doubtless intended to represent some scene from the *Rāmāyaṇa*, and the two men in the lower right corner may be Rāma and Lakshmaṇa. In the other a divinity is carrying off a chariot and its rider while a bird is pecking at him.

THE CORRIDOR IN THE COURT.

The corridor round the back of the temple, extending across the end of the court and nearly 120 feet along the south and north sides, contains quite a pantheon itself, the back wall being divided by pilasters into a series of large panels, each filled with a separate sculpture. The corridor at the east end of the south side measures 118 feet in length, and contains twelve of these panels, containing the following sculptures:—(1) Perhaps Anna-pūrṇa, a form of Durgā, with four arms, holding a pot, a rosary, a spike or bud, and with her hair in the jaṭā or ascetic style; it may possibly, however, be a form of Lakshmi. (2) The next is known as Balaji, a form of Śiva who slew Indrajit or Meghanāda, the son of Rāvaṇa. One version of the *Rāmāyaṇa* ascribes this feat to Lakshmaṇa, and this figure, like Vishnu, is four-armed, with club, *chakra* or discus, *śaṅkh* or conch; and a suppliant and small female figure appear in front of his club. (3) Vishnu as Kṛishṇa, four-armed, with the *śaṅkh* and sword, having his foot on the throat of the serpent Kāliya, and holding it

¹ A representation of the descent of the Ganges and Jamnā is found at Udayagiri in Bhopāl. See Cunningham's *Arch. Survey Reports*, vol. x, p. 48, and plate xviii.

by the tail.¹ (4) Varāha, the boar incarnation of Vishṇu raising Prithvī, the earth-goddess; he is four-armed, with *chakra* and *śankh*, and has the Nāga or snake under his foot. (5) A four-armed Vishṇu on Garuḍa, the winged man who carries him. (6) Trivikrama or Vāmana, the dwarf avatāra of Vishṇu, somewhat like the representation of the same subject in the Dās Avatāra Cave, and in the second and third caves at Bādāmi, and at Mahavallipuram;² he is represented with six arms, holding a long sword, club, shield, discus, and conch, with his foot uplifted over the head of Bali holding his pot. (7) A four-armed Vishṇu as Kṛishṇa, upholding the lintel of the compartment, intended to represent the base of the hill Govardhana held up over the flocks of Vraj.³ (8) Śesha Nārāyaṇa, or Vishṇu, reclining on the great snake,⁴ with a lotus springing from his navel, on which is Brahmā. Five fat little figures are carved below. (9) Narasiṃha, or the lion avatāra of Vishṇu, tearing out the entrails of Hiranyakaśipu. (10) A figure with three faces and four arms trying to tear up a *līṅga*. (11) Śiva, four-armed, attended by his vehicle, the bull Nandi; and (12) Arddhanārī, the androgynous personification of Śiva, four-armed, and attended by Nandi.

Following the nineteen sculptures⁵ in the east corridor (189 feet in length) from south to north, we have—(1) Śiva, locally known as Kāla Bhairava, four-armed, with the *triśula*, and accompanied by a small figure of Pārvatī, whose hair is dressed in a peculiar style. (2) A god stepping out from lotuses, with a small figure of a goddess holding him by the finger. (3) Śiva, four-armed, with the *triśula*, beside Pārvatī, with one right hand on her head and the other on her breast. (4) Śiva, four-armed, with the *triśula* in one of the left hands, and gandharvas above and other attendants below. (5) Śiva dancing on a dwarf, with a long-shafted *triśula* in one of his left hands. (6) Chanda, or Śiva Dhūrjati, locally called Bhupāla Bhairava, with only a ribbon over his thighs, a *triśula* over his right shoulder, a begging-bowl in the left hand, and a *ḍamaru* or small drum in the right, with Pārvatī in front of him. (7) Śiva or Bhairava, four-armed as usual, holding a cobra, with Nandi on his right and Pārvatī on his left hand. (8) Śiva again, and Nandi. (9) Brahmā, with his *haṁsa* or sacred goose, three-faced and four-armed, with the ascetic's water-pot (*kamaṇḍalu*) and rosary (*japa-mālā*). (10) Śiva, with a cobra, and Nandi. (11) Vishṇu, four-armed, with *śankh* and lotus; also a worshipper with his hands clasped. (12) Śiva, holding the *triśula*, with Nandi and a worshipper. (13) Śiva, holding a snake and a lock of his hair, while the Ganges, perhaps, is represented as flowing from it and down the outside of his arm; Pārvatī is at his left side, and an elephant⁶ at his right. Above is a figure like Brahmā, but only one face is now distinct, and overhead is a *gandharva* or *vidyādhara*. (14) Śiva in a *līṅga*, with Brahmā and Varāha.⁷ (15) Perhaps Śiva, with four arms, *ḍamaru*, club, and bell, but no third eye. (16) Śiva and Pārvatī sitting

¹ For the legend, see *Harivaṁśa*, § 68.

² See *Archæol. Report*, vol. i, pl. xxiii, fig. 1, and pl. xxxi; *Cave Temples*, p. 150; *Ind. Ant.*, vol. vi, p. 356 and plate, fig. 4.

³ *Harivaṁśa*, § 74; Growse's *Mathura*, p. 58.

⁴ Similar figures are found in the Undavalli Cave, in the Yamapuri Cave at Mahavallipuram, and in the Dās Avatāra Cave (*Cave Temples*, pp. 101, 146, 438).

⁵ This supersedes the lists given in *Cave Temples*, p. 412. Sir Charles Mallet must have followed the information of the ignorant native guides.

⁶ Gajāsura?

⁷ Compare the sculpture in the Dās Avatāra Cave (*Cave Temples*, p. 437), and for the legend see *Jour. R. As. Soc.*, vol. ix, p. 91; or H. H. Wilson's *Works*, vol. ii, p. 211; my *Elephanta*, § 56, n. 10; also the *Chāṇḍa-bāzava Purāṇa* in *J. Bom. B. R. A. Soc.*, vol. viii, p. 142.

together, and Nandi below. (17) Śiva or Sadāśiva, with six arms, going to war against Tripurāsura or Tāraka: Brahmā drives him, armed with *triśula*, club, bow, and quiver, in the sun's chariot, with the four *Vedas* as his horses, and Nandi is represented on the top of the club. (18) Virabhadra, six-armed, holding up his victim Ratnāsura, with *damaru*, bowl, and *triśula*, and accompanied by Pārvatī, Kālī, a goblin and vampire. Every drop, says the myth, of Ratnāsura's blood that fell on the ground produced another Asura like himself. (19) Śiva, with Pārvatī at his left side, and laying his hand on one of hers, while he has a flower in another, and Bhṛngī, his skeleton attendant, waits below.

Turning into the north corridor, which is 120 feet long and has twelve sculptures, we have—(1) Śiva springing from the *liṅga* to protect Mārkaṇḍēya from Yama, the god of death (plate xxiv, fig. 2). (2) Śiva and two worshippers, one of them a huntsman with a bow (plate xxvii, fig. 1). (3) Śiva and Pārvatī, the latter with a very large chignon, playing at *chausar*; below are Nandi and eleven *gana* (fig. 2). Śiva and Pārvatī sitting together; Nārada below is apparently playing some wind instrument. (5) Śiva and Pārvatī above the latter, with her arm entwined in Śiva's; Rāvaṇa has been begun below but never completed. (6) A human figure called Rishi Muchhukunda, with two arms, and a bag on his left shoulder. (7) Śiva and Pārvatī seated facing one another, as if he were speaking to her; nothing below. (8) Śiva, four-armed, with snake and rosary, and Nandi on the right. (9) Śiva and Pārvatī seated, and Nandi couched below (fig. 3). (10) The same pair, with a *liṅga* altar between them, and Nandi couchant below. (11) Śiva with Pārvatī on his left knee, and a seated and a standing figure below. (12) A *liṅga* with nine heads round it, and a kneeling figure of Rāvaṇa upholding the *vēdi* in which it is, and cutting off his tenth head in devotion to Śiva.

PILLARS.

Of the pillars in Kailāsa, some specimens were given in the *Cave Temples* (plate lxxxiv); we here add some further examples. In plate xxviii, fig. 1, is another pillar from the great maṇḍapa, while fig. 2 is one of the pilasters from the side walls. Fig. 3 is an example from the lower storey, under Lankeśvara, from the apartment (*M*) in the north side of the court (*Cave Temples*, plate lxxxi). Above a moulded base the lower half of the square shaft on the side facing the court is carved, below with three capering *ganas* in *basso-relievo* in small ornamented panels, and above in a central panel a human figure standing with a *triśula* in his right hand; the border of this panel, the edges of the pillar opposite to it, and a pretty broad band above it are carved with much care and considerable taste. An extended plain bracket surmounts the shaft under the architrave above.

LANKEŚVARA.

On plate xxix, fig. 1, is given one of the four pillars that surround the central area in the Lankeśvara.¹ These massive piers, with the short shafts square to about half their height, and bold capitals and brackets, produce an almost Egyptian effect of solidity and grandeur, unlike anything else even in the cave architecture of India. The floor of the central area in this hall is somewhat raised above the surrounding aisles, but the roof is correspondingly elevated by a double architrave surrounding it, and shown in section above the pillar, and also in plate xxiii, fig. 1.

¹ One of the outer range is given in the *Cave Temples*, plate lxxxiv, fig. 4.

The sculptures in Laṅkêśvara have been executed with great care and minute detail, but most of them have been very much injured by Muhammadan ignorance. The figure of Śiva dancing the *Tāṇḍava* in the end of the front aisle has often attracted attention,¹ and is represented in plate xxix, fig. 2, where the elaborate headdress in which is fixed a skull and the crescent moon, the necklace, armlets, and jewelled belts may be studied. He is represented with six arms, of which the right front one, which was probably bent forwards, the back one bent downwards and forwards, and the front left one are all broken off, as is the whole of the left leg and the lower half of the right one, which appears to have been twisted quite round.

On the back wall is a series of the principal great gods of the pantheon in six sculptures, of which three are represented in plate xxx. Fig. 1 represents Sūrya or the sun-god at the east end of the wall with his two wives² and two male attendants, his sons, the Aświns. He holds two lotuses growing out of his hands, wears a diadem, and necklace hanging down, with earrings and a girdle (*viyaṅga*),³ but it can hardly be said that in this case he is "clad in the dress of the Northerners, so as to be covered from the feet upwards to the bosom," as in Varāha Mihira's directions for making his image.⁴

Fig. 2 represents Umā or Pārvatī, the consort of Śiva, four-armed, and performing *tapas* or ascetic penance between two fires, while holding up a *liṅga*—the symbol of Śiva—in one right hand, and an image of Gaṇeśa, his reputed son and chief of his followers, in one of the left hands. There are traces under her feet of a crocodile, which being the emblem of Gaṅgā, may also be used by Umā.

In the middle compartment on this wall (fig. 3) are the three Dii Majores of the Brahmans—Brahmā, Śiva, and Viṣṇu—each four-armed, but damaged in their hands, which probably held the usual symbols borne by each god. Brahmā is represented with three faces—the fourth is supposed to be behind the central front one. His consort, Sarasvatī, the goddess of learning, is one of the figures beside him, and his *vāhana* or vehicle, the *haṁsa*-swan or goose, is on his left. The central figure is Śiva holding up his *triśula*, called Pināka, and a snake, with Nandi by his side and an attendant. The third is Viṣṇu, with the discus and a great club, attended by a male and a female. An injured figure of Varāha—the Boar avatāra of Viṣṇu—on this same wall is represented on plate xxix, fig. 3, with his left foot on the heads of a pair of Nāgas.

THE CHAPELS, ŚIKHARA, &c.

It should be noted that while in Rāvaṇa-kā-khāī, Rāmêśvara, Dumār Lena, and other cave temples, there is a clear passage for *pradakṣhiṇā* or circumambulation of the shrine,

¹ The figure of Śiva from this panel was drawn by Capt. R. N. Grindlay for the Hon. Lady Hood in 1813, and afterwards published in 1828 in the *Trans. R. Asiat. Soc.*, vol. ii, p. 326, but like his other drawings made at Elurā, he gives the figure quite an artistic finish of a high order.

² A figure of Sūrya and his two wives appears in one of the tympana of the Ānanta Cave on the Khandagiri hill in Orissa, not represented in the photographs from the casts in *Cave Temples*, pl. i and p. 72. It is over the left door, and is specially interesting from its close resemblance to the sculpture in the small very early Vihāra at Bhājā (*Cave Temples*, pl. xviii and pp. 515, 522; *Reports*, vol. iv, p. 6 and pl. vi, fig. 1, and vol. ii, p. 215, and pl. lxxv; *Ind. Ant.*, vol. ix, p. 116). When not in his chariot, Sūrya is frequently attended by two armed males as well as by his wives.

³ Or *ariyaṅga*, from the Baktrian and Zend *airyoḍonhanem*, equivalent to the Pārsi *kusti*.—Haug's *Essays*, West's ed., pp. 286, 396.

⁴ *Bṛhat Saṁhitā*, lviii, 46.

in the Kailāsa this is provided for by the doors in the east wall leading on to the terrace on which are also five small shrines, with but little carving on their walls beyond the *dwārapālas* at the doors, which, in the case of the one on the north side, are females, with a pair of figures kissing on each side. In all of them, except that on the south side, there are altars for images; in that one there is a bench round the back and ends, and it was probably devoted to the Mātṛis, which would be arranged along the back of it as in the Yajña śālā on the south side of the court,¹ with Skanda or Śiva in the left end, and Gaṇeśa and the skeleton figure on the right. The two at the corners would probably be devoted to Chanda and Rudra or Bhairava—both terrific forms of Śiva—the former represented as nude, having Śiva's third eye in his forehead, with two or four arms holding the *triśula* and a jug or *damaru*, and his hair wound up in the *jaṭā* style. To him the refuse of the offerings were thrown. On the east side was the shrine of Pārvatī, the *śakti* of Śiva.² The *dwārapālas* of this shrine are armed with swords. It is doubtful to whom we ought to assign the fifth shrine on the north side opposite to the *Sōmasūtra* or outlet for the water from the *liṅga* inside the temple,—possibly it was dedicated to Sūrya or Nārāyaṇa.³ In an advanced recess in the corner of the temple facing this is an image of Gaṇapati or Vināyaka, the eldest son of Śiva; and on the façade above it is a figure in *alto-rilievo* with its face to the wall. The image in the corresponding recess on the south-west of the temple is perhaps meant for Viṣṇu.

The base of the *śikhara* itself is carved in panels, six on each side, and five on the back, containing various forms of Śiva, such as Chanda, Ardhanārīśvara, &c., Durgā and Viṣṇu, standing on fat dwarf figures (perhaps Asuras), and with other attendants. At the upper corners of the panels are conventionalised figures of peacocks with long tails; and above the panel is usually a Dēvi seated cross-legged. Two of these compartments are represented in figs. 1 and 2 of plate xxxi, the first being the second panel from the door of the maṇḍapa on the south side, and the other the sixth. The slightest examination of these two drawings will serve to convince any one of the exceeding richness and beauty of the foliage over the panels, and of the great variety of floral ornamentation on the side pilasters. And these are only two out of seventeen, all carved in similar style, and all varying in details.

Fig. 3 represents a similar panel on the south side of the basement of the Nandi porch, just in front of the great temple. It has contained a representation of Narasimha struggling with Hiranyakaśipu; but being more exposed, has been much injured. The compartment is surrounded by carved pilasters and a frieze, round which are numerous figures looking on at the struggle.

On the roofs of the Gōpuram in front, of the Nandi-maṇḍapa before the temple, and of the great hall itself, figures of lions and fat dwarfs are placed. Two of these lions from the roof of the great hall are represented on plate xxvi, figs. 3 and 4. They stand about 4 feet high, and are executed in the same bold style as the similar figures of lions and elephants round the base of the temple.

¹ Marked E' on the plan, *Cave Temples*, plate lxxxi A.

² See *Ind. Ant.*, vol. ix, p. 119 note, and p. 119.

³ The temple of Govindēśvara at Simar, twenty miles south from Nāsik, is arranged thus:—The great central temple dedicated to Śiva faces the east; in front of it is the Nandimaṇḍapa; in the S.E. corner of the surrounding court is the shrine of Viṣṇu; in the N.E. that of Sūrya; in the N.W. of Mahishamardini or Jagadambā; and in the S.W. of Gaṇapati.

Over the gôpuram were fat dwarf figures represented as blowing *śaṅkhs*. But as they had been carved separately, most of them have been thrown down and destroyed.

One is represented in the woodcut No. 15. Similar figures are also carved on the roof of the maṇḍapa in the court of the Das Avatâra cave, and on the roof of the second storey of the Undavalli cave near Bezvâḍâ.¹



No. 15.—Dwarf Figure from the roof of the gôpuram of Kailâsa.

SHRINE OF THE RIVER GODDESSES.

In the north side of the court, behind the elephant, is a shrine about 23½ feet long by 9 feet deep and 11 high, with two free-standing pillars in front (one of them broken) and two in antis (woodcut No. 16). They have moulded bases, 16-sided shafts, and massive capitals with a double bracket above. The floor is about 5 feet above the level of the court, and is approached by five steps, with an elephant's head and front feet on each side of them, and the rest of the front of the podium is divided into three panels on each side, containing small sculptures much abraded. At the ends also have been the heads, &c., of elephants,

and the façade was terminated by gigantic *dwârapâlas* with several arms, and wearing high *mukûṭas* or tiaras. The back wall of this shrine is divided by half pillars into three large panels, with slender colonnettes on each side carrying *makaras*, and richly carved *tôraṇas* above, each containing a tall figure of a goddess in almost entire relief, symmetrically arranged, and which have been carved with unusual care, and though anything but classical in their proportions, they are about the best here, but have been much abused. The central one, which is perfectly erect, stands on a *makara*, with lotus leaves and flowers behind her, and may therefore be supposed to repre-



No. 16.—Shrine of the River Goddesses, from a photograph.

sent Gaṅgâ; the other two lean slightly towards her,—the one on the left standing on a lotus flower, with creeping plants and birds among their leaves, and that to the right

¹ *Cave Temples*, p. 102.

on a tortoise (*kurma*), with creepers and water plants behind,—the two representing the river goddesses Sarasvatī and Yamī or Yamunā respectively.¹

The frieze of the façade of this chapel has been divided into seven panels; in the central one are three figures, and in each of the others a male and female seated together. These may have had some connection with the seven river goddesses of mythology, but they are too much abraded to make out who they are. Over these are some mouldings, and above, in front of a quite unfinished cave, is a low rail carved with water-jars, separated by two little colonnettes. A part of this rail, cut away in the centre, seems to indicate that it was approached by a ladder.

SCREEN IN FRONT OF THE COURT.

The screen and front of the *gopuram* or entrance gate to the court is also covered with mythological sculptures in recessed panels, and the outer side of the screen is crowned by a crenellated parapet. Each crenellation is carved with three bells, and below them is a string of small figures in high relief on foot, on horseback, in carts, fighting, &c.

Commencing from the north, the large panels in order are—(1) one never advanced beyond two slight incisions in the rock; (2) the next contained a large figure of some form of Śiva with ten arms, holding up what somewhat resembles a bowl, with flames rising out of it—all below the waist of the figure is destroyed; (3) a tall three-faced figure, probably Brahmā. Turning a corner, on a portion of the wall facing south, are three panels; (4) containing a tall *līṅga*, as in the Dās-avatāra Cave, with a triple Śiva looking out of it; Brahmā is represented ascending on the left side, and also standing lower down; Vishṇu is on the right side, and a four-armed figure over his head, with a gandharva still higher, but the Varāha below and the base of the *līṅga* have been destroyed; (5) a tall four-armed *dēva*, with something like a *chakra* in the left hand, and a bull's head to the left; (6) another tall four-armed figure, but all insignia are gone. The line of wall again turns to the south, and (7) the first compartment is a large deep recess over a drain from the court, but it is so rotted away that it is impossible to say whether it contained any sculpture; (8) the next seems to contain Kārttikēya or Skanda, the war-god, the Hindu Mars, and second son of Śiva, born to destroy Tāraka, an Asura who became dangerous to the gods.² He is represented two-armed, riding on his peacock Paravāṇi, with an arrow or sceptre in the right, and perhaps a bird in the left hand: the lower portion of the panel is destroyed. (9) A two-armed figure on a ram-headed animal with a mane—perhaps Agni, the god of fire and regent of the south-east; (10) a similar figure on a deer, and may therefore be Varuṇa, the Hindu Uranus, the regent of the west; (11) another on a *makara*, with a very large head. This may be Nirṛīti, the regent of the south-west.

Just behind the porch is (12) a Nāga figure with five hoods as a sort of *dvārapāla*,

¹ Like many other points in Hindu mythology, the number and names of the river goddesses is quite unsettled. In some of the classics they are called the *Sapta-Sindhava*, but for these even the *Mahābhārata* gives two different enumerations. In the Peninsula they are often reckoned as (1) Yamunā, (2) Sarasvatī, (3) Gaṅgā, (4) Narmadā, (5) Gōdāvarī, (6) Kāvērī, and (7) Kanyā; but in different districts one or more of the following—Sindhu, Satadri (Satiaj), Gomati, Krishnā, Tuṅgabhadrā, Tāmraparnī, and Mannēri—are added or substituted for others in this list. The first three—Yamunā, Gaṅgā, and Sarasvatī—however, seem to have been the favourites, and generally accepted.

² See Griffith's beautiful version of the first seven cantos of the *Kumāra-Sambhava* or *Birth of the War God* (Trübner, 1879).



having a lotus bud in the left hand. On the north side wall of the entrance is a Nāgañi with one hood and a dwarf female attendant, and a *gandharva* over her right shoulder. (13) On the jamb of the porch is a tall female—a river goddess—standing on a *makara* as Gaṅgā, and resting her arm on a smaller female. A fat *gandharva* figure with a large *chauri* is over her right shoulder; that over the left has been broken away, except the *chauri*; and below is another attendant figure. (14) On the other pilaster has been a similar sculpture. (15) On the south side of the pilaster and return of the wall are a Nāgañi and a Nāga figure as on the other side, with large *chauri*, and one *gandharva* over her head and two over his bearing garlands. (16) Indra, the god of the firmament and regent of the east, on his elephant Airāvati, with Indrāñi, Aindrī or Sachī behind, and above are *gandharvas*. This panel is much weatherworn. (17) Behind this a little, in a narrow compartment, is Yama the "Restrainer," the god of death, the Pluto or Minos of the Indian Pantheon and brother of Yamī, the regent of the south, mounted on a buffalo. (18) The next also contains a riding figure, but much abraded and indistinct—possibly Vāyu, the regent of the north-west, who should be mounted on a Bhūta or spirit. (19) Nothing is left in the next compartment, but it also was probably occupied by another of the eight Dikpālas or regents¹—Kuvēra or Īśāna.

Over the water drain is (20) a large figure of Varāha, with eight arms, and five *gandharvas* above; the figure of Prīthivī or Bhūmidēvi is destroyed. Then, on the return of the wall facing north are three panels—(21) Viṣṇu on Garuḍa; (22) an eight-armed Trivikrama as at Bādāmi, but destroyed below; and (23) a figure in violent action. On the west face again are (24) Narasiṃha, the man-lion avatāra of Viṣṇu, with long curls; and (25) an eight-armed figure in violent action, possibly Śiva in the Tāṇḍava dance, with Pārvatī at his right side.

To the south of this is a rock-cut cistern about 22 feet by 19.

On each side the entrance to the porch is a sitting figure with one foot up (*lalitāsana mudrā*)—perhaps they had beards; and on the front of the inner jamb on each side is a female with umbrella and *chauri* overhead, and a small attendant. Passing through the Gopuram,² in which the two pillars on each side dividing the passage from the guard-rooms have been neatly carved, we find the jambs at the east end have fat figures on the front, one holding a *saṅkh* and the other a bud, out of both which a long *torana* or roll extends over their heads. Above are two *gandharvas*, and their seats are supported by lions. On the east faces of these jambs are gigantic four-armed Rudras with clubs, as dwārapālas. In the inner porch of the gateway are two sculptures in panels with side pilasters and pediments; that on the south wall is the Mahishāsuri already referred to, and on the north side is a Gaṇeśa with female *chauri*-bearers.

On the outer side of the north wall of the porch is the large Mahishāsuri already described, and on the return wall of the court are—(1) A two-armed figure with high *mukuta*, and his right hand pressed against the upper corner of the compartment. (2) A male and female, supposed to be Kāma, Manmatha, or Makarakētu (Eros, Cupid), and his wife Ratī or Rêvā (Venus): these are represented on plate xxvi, fig. 2. (3) On the return of the wall is a single male figure. (4) A female with the hair gathered in a lump on her left shoulder. (5) A male and female with a slender palm-tree between them, the stem

¹ These figures appear in the roof of the verandah of the great cave of Bādāmi also. See *Int. Ant.*, vol. vi, p. 361 and plate.

² The apartment marked A on the plan, *Cave Temples*, pl. lxxxi.

notched. (6) Vishṇu mounted on Garuḍa. (7) Over the drain a figure sitting on a chair with another kneeling in front.

To the north of this is an unfinished cave in the screen, with four stout short pillars having thick compressed cushion-shaped capitals: one pillar is destroyed.

On the south side of the entrance porch, and partly on the west wall, is (1) a large sculpture of Śiva in the chariot of the sun, drawn by the four *Vedas* as horses, with Brahma as his charioteer, armed with the bow (Himālaya) which he draws against an enemy. This sculpture is also found in the Dâś-avatâra cave. In front of him in several panels are groups of small figures; in one in front of the horses his enemies seem falling in confusion. (2) Behind this is a four-armed figure with a peculiar turban, and holding a large fruit in his hand. The next figures (3 to 6) are apparently Rudras in various attitudes. (7) Over the drain are—a small figure bending a bow with his feet; a larger one, apparently about to strike or push away a female; and some others; and (8), to the left, a male and female seated on a *sinhâsana*. Next to this is an unfinished excavation in the south end of the screen, apparently intended for a small open room or shrine.

It is evident from the number of unfinished excavations, especially on the south side of the court, that for long after the great temple was finished, works were carried on at different points in the surrounding rock, adding shrines and images, until perhaps the inroads of the Muhammadans finally put a stop to them.

CHAPTER V.

ELURA BRAHMANICAL CAVES NORTH OF KAILĀSA.

CAVES XVII. - XX.

Of the caves to the north of Kailâsa, except in one or two cases, not much need be added to what has been said in the *Cave Temples* (pp. 438-448). Across a deep ravine and watercourse, we reach Caves XVII., XVIII., and XIX., of which the first two are in close contact. No. XVII. is locally known as the "Chhōta," or small "Dumar Lena," though it has no resemblance to the larger cave passing under that name. The ground-plans of it and of No. XVIII. are given in plate xxxii, fig. 1, from which it will be seen that it had a low court in front with a corridor round it, now fallen in and ruined. Eight steps rise up to the porch (now also fallen) on the level of the hall, the front of which is supported by four pillars (see plate xxxiii, fig. 2), and the roof inside by eight heavy square ones of various patterns, one of which, from the back row, is represented in plate xxxiii, fig. 1. It has never been finished above, but the drawing shows how it was probably intended to complete it. These pillars may be compared with the pilasters in Rāvapa-kā-Khāi (*Cave Temples*, plate lxxi, fig. 1). The front and back aisles are fully 2 feet longer than the middle one, being 64 feet, and the depth of the hall is 37 feet. In the back wall are three doors, two opening into the *pradakṣiṇā* passage which surrounds the shrine,¹ and the central one into the shrine itself, which contains a large square altar and a decayed *liṅga*. The only sculptures on the walls are Mahishamardini in the south end of the front

¹ Compare with this the plan of the temple of Pāpanātha at Pattadakal (*Arch. Sur. Rep.*, vol. i, plate xivii).

aisle, four-armed, with *trishula* and sword, and holding by the nose the buffalo, which represents the Asura; Gānapati, also four-armed, is carved in the north end.

On the rock on the left side of the court, at the end of the façade, is a figure of Brahmā with three faces, represented in plate xxxvi, fig. 1.

Cave XVIII., close to this, has an irregular-shaped court in front, in the middle of which is a shallow trough. The cave is raised above the level of the court, and has four unfinished pillars in front. The hall is 67 feet long by about $22\frac{1}{2}$ deep, having a slightly raised platform inside. At the back is an antechamber 30 feet by $10\frac{1}{2}$ feet, with two square pillars in front and corresponding pilasters, having low bases of two members. The shrine has no *pradakshinā* path round it, and contains a round structural *vēdi* or altar—a modern form—and a *linga*.

Cave XIX. (plate xxxii, fig. 2) is a very irregular and much-decayed cave, with a wide entrance. The hall inside is 43 feet wide by about 32 feet deep, and the shrine is surrounded by a *pradakshinā* passage.


Close to the next is a ruinous cave filled with earth and hidden by underwood. Cave XX. (fig. 3) is little more than a shrine, with a wide passage round it, or a hall 37 feet wide by 30 feet deep in the middle, of which a block has been left 20 feet by 16 hewn into a shrine, the front of which has been given in the *Cave Temples*, plate lxxviii, which shows the carving on the different members of the door-mouldings, and the figures on each side so very analogous, even in details, to what are found in similar positions in the Bauddha caves, as may be seen by comparing it with the front of the shrine in Cave VI. (*Cave Temples*, plate lxi), that one is almost forced to allow that the one sect may have copied from the other. On a platform outside is a square base, either of a *dhvajastambha* or the remains of a pedestal for a Nandi. Lower down by 6 or 8 feet, and farther back, is another small platform.

CAVE XXI.—RĀMĒŚVARA.

Close to the last is the cave No. XXI., known as Rāmēśvara, which has been described in considerable detail in *The Cave Temples* (pp. 438 f., and plate lxxvi, fig. 1, and lxxvii). The plan, it will be remarked, is similar to that of Cave XVII, but without the pillars in the floor of the hall, and more closely resembling that of Cave XXVI. It has two columns in front of the shrine, with corresponding pilasters; one of the columns is represented in plate xxxiii, fig. 3. They are somewhat of the Elephanta type, but in place of the bracket is a deep square abacus, carved on the front and sides with figures. The lower half of the shaft is square, the upper portions of it being covered with bands of rich tracery. Over these is a deep octagonal member, with dwarfs on the corners; and the upper portion of the shaft is circular, with forty-nine very shallow or flat flutes. The side chapels have each a similar pair of columns in front, but standing on a raised platform, and with only a thin square abacus above.

The façade of the cave is shown in plate v. It has a low screen wall in front, now much rotted away from the accumulation of earth that long lay against it. Below was a moulded base to about the level of the floor inside. Above this is a string-course of animals, chiefly elephants. The face of the rail over this is divided into narrow panels by broad vertical bands of arabesques, each panel containing a standing male and female figure, and over this runs a coping of festooned carving. From this wall rise the pillars which support the roof, of which the lower portions of the shafts, partly embraced in the





RĀMĒŚVARA CAVE-TEMPLE AT ELLURĀ.

wall, are square. Just above the screen is an octagonal member with dwarfs on the corners, then the shafts become circular, with flowered members and flutes. The capital has drooping ears and a square abacus, over which are long brackets, carved in front with human figures and animals, somewhat in the style of those in the later Ajantā caves; but here there are added massive struts supporting the brackets, each consisting, as shown in the accompanying woodcut (No. 17), of a tall female figure standing under foliage, and attended by two small figures. Similar figures on a larger scale are carved at the ends of the façade, and there they are at once identifiable with the river goddesses, the one at the left end standing on a *makara*, the symbol of Gangā.

Over a plain architrave is a frieze with sunk panels containing dwarf figures, divided by compartments carved in arabesque designs. On the whole, this has been the most richly carved façade of any of the Elurā caves, or indeed of any Brahmanical cave in India.

It is in fact the architectural arrangements of this façade that constitute the principal interest in this cave; for besides its intrinsic beauty, its strongly marked characteristics point it out as the style of a well-defined but limited architectural epoch. It is reproduced with some changes in Cave III. at Bādāmi, and to a certain extent in No. XX. at Ajantā, while, as the Bādāmi cave has a well-authenticated date of 579 A.D., we may feel certain that these Elurā and Ajantā caves were executed within a few years of that date—either before or after. Looking at the extreme elaboration of the Rāmēśvara façade, it would appear to be subsequent to the Bādāmi caves, but the difference can hardly be fifty years, and in the Ajantā example it may be even less. We have thus a thread of chronology running through the dates of the principal series of caves of the utmost value for determining the relative ages, at least of the later examples of cave architecture.

In the chapel in the right end of the hall of this cave is carved one of the large groups of Saptamātrīs found also in Rāvaṇa kā Khāi and in Cave XXII., in this case covering the three inner walls of the room, and of which the Mātrīs on the back and the group on the right end wall are represented on plate xxxiv, fig. 1. The vāhaṇas on vehicles of the different mother goddesses that were carved below each are now almost entirely destroyed, but there is no difficulty in recognising them by their positions and the symbols they have in their hands. Gaṇapati sits at their head, and then in order from right to left they are—(1) Chāmundā, (2) Indrāṇī or Aindrī (having a *vajra* in her hand), (3) Varāhī, (4) Lakshmi or Vaishṇavī (with the *śankha* and *chakra*), (5) Kaumārī or Sēnā, (6) Mahēśvarī, and (7) Brāhmī or Sarasvatī. Each of them had a child (except, perhaps, Sarasvatī), but they are all more or less defaced. At the end sits Mahādēva or Śiva, with Nandi below, and on the wall to the left is Śiva engaged in the *Tāṇḍava* dance, which he performs at the destruction of the world, with attendants. On the other end wall is the ghastly group represented to the right, in which Kālī and Kāla—the goddess of destruction and her partner—are probably represented. The panel is much injured below.



No. 17.—Pillar in front of Rāmēśvara, from a photograph.

A very similar group of the Mâtris is found in the south side of the next cave No. XXII., and is represented also on plate xxxiv, fig. 2. Here Châmuṇḍâ is represented in a ghastly skeleton form, while Varâhî, like her husband, has a boar's head, and Sarasvatî or Brâhmî has three heads and holds a bottle. On the right end wall are Kâla and Gaṇêśa, and on the left Śiva.

The high pedestal in front of the cave, on which a headless Nandî still couches, is carved on the sides with goddesses also and attendants.

CAVES XXII.-XXVII.

Close to Râmêśvara, and somewhat advanced in front of it, is Cave XXII., known as Nilakaṇṭha ("blue-throated"), a name of Śiva. The plan of this cave is given plate xxxii, fig. 4. It has a somewhat irregular court in front, about 42 feet each way, in the centre of which, on a high base, stands the Nandî maṇḍapa, now somewhat ruined. The plan somewhat resembles that of Cave XVIII., but with pillars introduced into the hall and in front of the side chapels. On the south side of the court is a low chapel containing the sculpture of the Mâtris referred to above, with a skeleton Bhringi or Kâla with two arms and outspread hair; Gaṇapati and the seven mothers—the last, Brâhmî, with three faces and holding a bottle; and, lastly, Śiva. All the Mâtris and Śiva have four arms each. Among other sculptures in the vestibule to the shrine is the figure of Gaṅgâ represented in plate xxv, fig. 5.

The next two caves (Nos. XXIII. and XXIV.) are close to the last, and are rather a series of small shrines than cave temples. They are probably of later date than any of the larger ones. The ground-plan is given on plate ii, drawn to the same scale as the others, from which it will be observed that they are huddled together and contain six round *vêdis*, and in one of the shrines in No. XXIII. is a *trimurti* on the back wall (figured in *Cave Temples*, plate lxxv, fig. 2). In Cave XXIV. is an injured figure of a River goddess represented on plate xxv, fig. 4.

From these last to Cave XXV., which is known by the names of Kumbârwaḍâ and Sûrêśvara, is about 70 yards. The plan is given on plate xxxv, fig. 3, which shows that, behind a hall about 90 feet long, of which the front has fallen away, is a smaller one, 57 feet wide by 23 feet deep and 13 feet 10 inches high, with four square free-standing pillars in front and two in antis. Inside are two others, with corresponding pilasters on the side walls; and in the back, separating it from the antechamber to the shrine, are two more free-standing pillars, with two in antis. These pillars have brackets, and on the front of each bracket a male and female flying figure. On plate xxxv, fig. 2, is a drawing of the side of one of these pillars, showing how the bracket is separated from the capital of the shaft by a neck narrower than the shaft itself, and illustrating at the same time the deterioration in style and taste which the proportions and details indicate.

On the roof of the antechamber is the figure of Sûrya, the sun-god, in his chariot (*Cave Temples*, pl. lxxxiii, fig. 2), from which the temple derives the name of Sûrêśvara. The shrine door has a Dravidian moulding on the frieze, and by the jambs are tall dwârapâlas standing on lotuses with very bushy locks and long swords.

The next cave, No. XXVI., is very like the Râmêśvara in plan (pl. xxxii, fig. 5). The hall is 74 feet wide by 25 feet deep and 16½ feet high, with four pillars in front. At each end is a large irregular-shaped room at a somewhat higher level, with two square pillars and pilasters in front, and at the back is a still larger one, about 40 feet square, also with two square pillars and pilasters in front. In the middle of this stands the shrine, about

16 feet square inside, and with a circumambulatory passage about $9\frac{1}{2}$ feet wide all round it. The entrance of the shrine is richly ornamented with sculptured figures, and female statues stand by the pilasters on each side the entrance to the side passages.¹

The next is a large cave, No. XXVII., known as the Milkmaid's Cave, the plan of which is given on plate xxxv, fig. 4. The front has been supported by six plain octagonal pillars with bracket capitals, but all of them have fallen away except one at the left end and a fragment of one at the right end. The verandah is about 69 feet long by 8 feet 4 inches wide, with several sculptures on the back wall and in the ends. In the walls of the hall three cells are rudely excavated. The carvings are mostly Vaishṇava in character, and the arrangement of separating the hall from the verandah by a wall pierced by three doors and two windows is more in keeping with the plan of a Buddha cave than any of the other Brahmanical caves at Elurā.

CAVE XXIX.—THE DUMAR LENA OR SĪTĀ'S CHĀVADĪ.

This is the most northern of the Brahmanical caves at Elurā, and certainly one of the finest of the class to be found anywhere. It is also interesting from its being as nearly as may be a duplicate of the celebrated cave at Elephanta, and also of the less known one at Jōgēśvari. All three are executed on the same plan, the light being introduced from three sides, which is no small difficulty in cave architecture, but was necessary to produce the effect of the structural buildings from which they were imitated.

This one is the best preserved and largest of the three, but not the earliest, though the Jōgēśvari one (plate xlvī) is certainly the most modern, and, except the Kailāsa which is exceptional, is probably the last of the great cave temples of India.

A ground-plan of this splendid cave was given in *Cave Temples*, plate lxxix, and we now add a section (plate xxxvii, fig. 1) through the middle of the cave from north to south, showing the front of the shrine, with the *dwārapālas* at its corners, and the pillars and sculptures on the east side. It is 148 feet wide by 149 feet deep, and 17 feet 8 inches high.

The description in *Cave Temples*, p. 446 f., gives a succinct account of the details and dimensions of this temple, but to give a full description of all its mythological representations and other sculptures, though these are much fewer in proportion to its size than any other cave temple here, would fill half this volume. Plate xxxviii, fig. 1, represents on a good scale the marriage scene on the east wall of the south portico. The two chief figures are Śiva and Pārvatī or Umā, each with a flower in the left hand; below, to the right, kneeling by the sacrificial fire, is Brahmā, with three heads, acting as priest; to the left are Menā and Hīmālaya, the mother and father of the bride, with a flower and a cocoa-nut. Above are the gods and goddesses; on the left are—Vishṇu mounted on Garuḍa, Yama on a buffalo, Vāyu or Sōma on a stag, Agni on a goat, and perhaps Varuṇa; on the right are Indra on Airāvati, and Nirṛiti on a *makara*. Among the goddesses are probably Gaṅgā—

"She in her goddess shape divinely fair,
And Yamunā, sweet river-nymph, were there,
Fanning their lord, that fancy still might deem
Swans waved their pinions round each Lady of the Stream."

¹ See *Cave Temples*, pp. 444, 445.



"High o'er their heads sweet Beauty's Queen¹ displayed
 Upon a stem of reed a cool green shade,
 While the young lotus-leaves of which 'twas made
 Seemed, as they glistened to the wondering view,
 All richly pearled with drops of beady dew.
 In twofold language on each glorious head
 The Queen of Speech² her richest blessings shed;
 In strong, pure, godlike utterance for his ear,
 To her in liquid tones, soft, beautifully clear."³

Fig. 2 of the same plate represents the left-hand corner of the shrine showing the *dwârapâlas* with their attendants. At each corner is a similar group, the *mukutas* of the guardian figures being very richly carved. At Elephanta these gigantic figures are attended by fat male dwarfs, whereas their companions here are females.

The other sculptures here are arranged as at Elephanta, in the ends of the aisles on the three open sides. But as the shrine occupies the central portion of the back area, there are no sculptures on the walls behind it; whereas at Elephanta, the shrine being in the west side of the cave, the back wall contains the three largest and finest sculptures, viz., the great Trimurti in the centre, Arddhanârî and attendants on the left, and Śiva and Pârvatî with numerous smaller figures on the right. These have no representatives here. In the north verandah, the sculptures correspond to those in the same position at Elephanta, but are greatly inferior in details. In the east end of it is Śiva as a Yogi or ascetic, with a club in his left hand, and seated on a lotus upheld by Nâga figures, with two females worshipping behind each,—an evident copy from the figures of Buddha. None of the accessory figures are represented here which render the Elephanta one so excellent a rendering of Kâlidâsa's poetical description. The panel in the west end is the *Tandava* dance, said to be performed by Śiva at eventide to the sound of musical instruments, with his hair loose, stamping with frantic energy, attended by his *gana* and *Pisâchas*, when the dust he raises is put on their heads by the other *Dêvatas*.⁴ The sculpture, however, is very inferior to that on the right of the entrance at Elephanta.

In the west aisle or front of the cave, the panel in the right end is the very frequent one of Râvaṇa under Kailâsa, the white mountain, which is the special abode or heaven of Śiva. The principal figures in this have not the larger proportions than the subordinate ones, which is usually given them in other representations of the same scene,—the finest example of which is to be found under the south porch of the Kailâsa temple, where it is really well represented. In the left or north end is an unfinished sculpture of Bhairava, the terrific form of Śiva, very effectively represented in the *Dâs Avatâra* (see pl. xxii, fig. 2), and also in the west aisle at Elephanta.

In the south aisle or portico, besides the marriage scene already referred to, is a very common sculpture of Siva and Pârvatî at play, with numerous *gandharvas*, &c., above; the bull Nandi and the rollicking dwarfs or *Gana* below; Vishṇu is represented to the right, and Brahmâ on the left. These two are the best executed of the six great panels.

Outside the cave, on each side, is a tall River goddess and attendants.

¹ Śrî or Lakshmi.

² Sarasvatî.

³ Griffith's *Birth of the War-God*, pp. 98 and 105.

⁴ See Wilson's *Hindu Theatre*, vol. i, p. xix, and vol. ii, pp. 53, 58, 59, 153; Colebrooke's *Essays*, vol. ii, p. 153.

CHAPTER VI.

THE JAINA CAVES AT ELURĀ.

It may help to illustrate the chronology of Jaina history¹ and its connection with Buddhism to remember that Mahāvīra, the last Tīrthaṅkara, was contemporary with Buddha.² The following table brings together the dates³ belonging to both sects:—

	B.C.
Gautama Buddha, born at Kapilavastu	About 560
Srēṇika Bimbisāra, king of Magadha ⁴	" 540-512
Vardhamāna, Mahāvīra, or Jātāputra, born at Chitrakoṭ in Bihār	" 540
Gautama became Buddha at Buddhagayā	" 525
Vardhamāna became a Digambara ascetic	" 509
Vardhamāna became an Arhat or Jina	" 496
Ajātasatru, called Kūṇika or Koṇikā by the Jains	" 488-461
Gautama Buddha's <i>Nirvāṇa</i>	" 480
Vardhamāna Mahāvīra's <i>Nirvāṇa</i> ⁵ at Pāva	" 467
Udayibhadra, Udayāśva, Udāyin, or Udāsin, ⁶ son of Ajātasatru	" 461-437
Nandivardhana, a new dynasty	" 407-
Alexander the Great's invasion of India	in 327
Chandragupta founded the Maurya dynasty	" 318-295
Bindusāra or Vārisāra, the Amitrokhates of the Greeks ⁷	" 295-267
Aśoka or Priyadarsi, son of Bindusāra	" 267-226
Samprati, grandson of Aśoka	about 225-217
Daśaratha, grandson of Aśoka, Saṅgata, Śāliśuka, Sōmasarman, and Satadhanvan	" 217-185
Bṛidhadratha, the last of the Mauryas	" 185-182
Pushyamitra, the first of the Śuṅga dynasty	" 182-152
Balamitra, Bhānumitra, and Nabovāhana ⁸	" 150-74
Gardabhilla in Ujjain	" 74-61

¹ For some notes on Jainism see *Cave Temples*, pp. 485 ff.

² See S. Hardy, *Man. Buddh.*, p. 274; *Ind. Ant.*, vol. ix, p. 258.

³ This is based on an extract from Merutuṅga's *Vichitraśrenī* in *Ind. Ant.*, vol. ii, p. 362, on Hemachandra's statement (*Parīśiṣṭapāraṇa*, viii, 341) that Chandragupta became king 155 years after Mahāvīra's *nirvāṇa*, and on the dates given in *The Cave Temples*, pp. 24-26.

⁴ The Ceylon chronicles assign to Bimbisāra the long reign of fifty-two years, and state that he was murdered by his son Ajātasatru, while both the *Vāyu* and *Matsya Purāṇas* agree in giving twenty-eight years to his rule, and after him the *Matsya* inserts the names of Kapvayana (with nine years) and Bhūmimītra or Bhūmiputra (with fourteen years), which fill up the interval. Bimbisāra's name is given as Vidhisāra in the *Vishṇu P.*, as Vidhisāra in the *Bhagavat*. Lassen, *Ind. Alterth.* (2d. ed.) vol. i, p. 859, and anh. p. xxxviii. For Srēṇika or Srēṇya, conf. *Asiat. Res.*, vol. xx, p. 46; Burnouf, *Introd. à l'Hist. Buddh. Ind.*, pp. 128, 147.

⁵ The Jaina chronicler gives only 108 years to the Maurya dynasty, and places Mahāvīra's *Nirvāṇa* 155 years before Chandragupta's accession, thus giving 312 a.c. (the Seleucid era) for the latter event. This drops about six years from our usual reckoning; but Merutuṅga and other writers add sixty for the reign of Pālaka: if we regard this as a mistake for six, the dates relating to Mahāvīra here will be thrown back six years—his death to 473 a.c., just 155 years before Chandragupta (318 a.c.), and add six to the 108 years of the Maurya dynasty, to which the *Purāṇas*, however, assign 137.

⁶ According to the *Vāyu Purāṇa* and the Jaina and Buddhist accounts, he founded Pāṭaliputra, and ruled, according to the *Purāṇas*, thirty-three years; but both place Dharbaka, Harshaka or Vansaka between Ajātasatru and him, with a reign of twenty-four or twenty-five years. The Buddhists assign to Ajātasatru, thirty-two years; to Udayibhadra, sixteen; to Munda, eight; and to Nāgadaśuka, twenty-four in succession.—Burnouf, *Introd. à l'Hist. Buddh. Ind.*, p. 319; *Mahāvamsa*, c. iv.; Lassen, *Ind. Alterth.*, vol. ii, pp. 222, 1207.

⁷ Athenæus, xiv, 67; Strabo, *Geog.* II, i, 9.

⁸ These were probably kings of Ujjain and not of Magadha.

The Jaina caves at Elurā form almost a group by themselves separated from the Dumar Lena, the most northerly of the Brahmanical caves, by about 400 yards. The group is a small one, consisting of only five caves, two of them unfinished, but the two principal ones are very extensive works.

The first of them, removed a short distance from the face of the scarp, which at the place is very low, is known as the Chhotā Kailāsa, from the circumstance that, like the great Brahmanical temple, it is not a cave, but a free-standing monolithic shrine, executed in the middle of a pit hewn out of the rock. It is very much smaller, however, than the great Kailāsa temple, being only one storey in height, with a very stunted and unfinished tower. The hall is only 36 feet 4 inches square, but, like its pattern, has sixteen pillars arranged in four groups; and the shrine at the back is small.

The second also stands in a pit, into which the porch projects, but the hall, quite unfinished, is under the rock. This temple is filled up with earth.¹

THE INDRA SABHĀ.

The two principal Jaina caves are very extensive works, superior both in extent and elaboration to any of the Brahmanical caves, excepting of course the Kailāsa, and the Viśvakarma among the Bauddha ones. Though two storeys in height and extremely rich in decoration, the Indra and Jagannāth Sabhās are entirely deficient in that purpose-like architectural expression which characterised the works of the two earlier religions. They have no cells, like the vihāras, and are nothing like the Chaitya halls of the Buddhists, nor do they suggest the Chāvaḍis, like the Dumar Lena, of the Hindus. Rich and elaborate though they certainly are, the plan is compressed, and all their arrangements seem to result more from accident than to have arisen from any well-conceived design, so that they lose half the effect that might have been produced with far less elaboration of detail.

Their age, too, is certainly considerably subsequent to that of the caves belonging to the two other sects, as if, after the decadence of the Rāṭhoḍ dynasty² in the ninth or tenth century, the Jainas had taken possession of the locality and determined to mark the superiority of their religion, which was then becoming so important, by attempting to rival the works of their predecessors. Had they had any real motive in what they did they might have succeeded in this, but the absence of purpose is so evident in all they did that their failure was inevitable.


The Indra Sabhā, as explained in the *Cave Temples*, is, like Kailāsa, rather a group of caves than a single one, consisting of a central two-storeyed cave with a court in front and smaller caves forming wings on each side. The plans of both floors have been given in *The Cave Temples* (plates lxxxvii and lxxxviii), and need not be repeated here. But on plate xxxvii, fig. 2, is given a longitudinal section of the cave, which, together with the plans, may enable the reader to form a tolerably accurate idea of its arrangements and architectural style.

The cave faces the south, and outside the court on the east side is a small hall 19 feet by 13 feet, with a low screen wall and two pillars in front, square below and octagonal above, including the capitals. In the ends of this are the favourite sculptures of Pārśva-nātha's temptation³ and the *tapas* or asceticism of Gautama Rishi or Gomatēśvara.

¹ For further details, see *Cave Temples*, pp. 495, 496.

² The Rāṣṭrakūṭa kingdom seems to have been divided in the time of Govinda III., when his younger brother, Indra, established a separate kingdom of Gujarkṭ, about the very end of the eighth century.

³ *Cave Temples*, pl. lxxxvi, and p. 496.



INDRA SABHĀ JAINA ROCK-TEMPLE AT ELLORĀ.

A screen wall, left in the rock, terminates the court on the south side, and is pierced by a doorway with a Dravidian roof. This court is about 56 feet inside from north to south and 48 feet across. In it stands an elephant on the right side, about 15 feet high, inclusive of the pedestal; a fine monolithic column¹ 27 feet 4 inches high, which fell over against the side rock about eight years ago; and a small *mandapa* analogous to the Nandī *mandapas* in front of Śaiva temples. This is about 8 feet 5 inches square inside, raised by eight steps above the level of the court, with a door on each side, but only with ascents from the north and south sides; each door has two advanced pillars. The roof, as may be seen from the section and the plan of it (plate xl, fig. 1), is Dravidian in style. Inside this room is left a square block of rock, on each side of which is carved a figure of Mahāvira, one of the Tirthaṅkaras, with the wheel in front of the seat supported by lions.

The accompanying autotype plate vi is a view taken in 1874, before the monolithic column in the west side of the court fell over, and shows the gateway, the *mandapa* in the court and the pillar, with portions of the façade behind them.

Exclusive of the verandah, the lower hall must have been intended to be about 72 feet wide by 56 feet deep, beyond which are two free-standing pillars and two in *antis* in front of the vestibule to the shrine, 40 feet wide and 15 deep, inclusive of the pillars. The shrine alone has been completed, and is 17½ feet wide by 13 feet deep, containing a Mahāvira seated cross-legged on a lion-throne, with the wheel or *chakra* in front, which is one of his emblems with the Digambara Jainas, to whom these cave temples have belonged.

The stair ascends in the verandah, and lands in the east end of the verandah of the great hall above. This upper hall, exclusive of the verandah, from which it is only separated by a low parapet wall, measures 55 feet deep by 78 feet wide. The verandah is about 54 feet long and 10 feet wide. In each end is a colossal image, the male (*Cave Temples*, plate xci, fig. 1) in the west, and the female in the east, usually known as Indra and Indrāṇī, the former being seated on an elephant and the latter on a lion, with a tree behind the head of each, and small figures of attendants beside them. These figures are perhaps the Yaksha and Yakshiṇī or Śāsanadēvi, the instructors of the Tirthaṅkara to whom the temple is dedicated. Each Jina or Tirthaṅkara, like each Buddha, has his sacred tree; but he has also his Śāsanadēva and Dēvi, his principal male disciple or follower, and chief of his female followers. These are very shadowy creations, and it would be difficult to find anywhere among the numerous temples of the sect, with all their exuberance of images, representations of the forty-eight male and female Śāsanas or Yakshas that could be distinguished from one another. Neminātha, the 22d Jina in their books, has the Vēṭasa for his tree; but at Mount Girnār the mango (*Ambā*) takes its place; his instructor or Yaksha is Gomēdha, and his Yakshiṇī Ambikā;² Pārśvanātha, the 23d, has the Dhātaki (*Grislea tomentosa*) for his tree, and Pārśvayaksha and Padmāvatī for his instructors; and Mahāvira, the 24th and last Jina, has the Śāla (*Shorea robusta*)³ as his consecration tree, and Mātāṅga⁴ and Siddhāyikā as his attendant divinities. But that the figures at the ends of this verandah, and so frequent in the other caves here and at Ankāi, Pātna, and elsewhere, represent a pair of these divinities is doubtful. They are always represented on the same

¹ For drawing, see *Cave Temples*, pl. lxxx, fig. 2.

² She is a form of Durgā, regarded in Gujārāt as a mother-goddess, and has a temple on the summit of Mount Girnār, which is sacred to Neminātha.

³ This is also the Dikshā tree of Ajitanātha and Sumatinātha, the 2d and 5th Tirthaṅkaras.

⁴ He figures also as the Yaksha to Supārśvanātha, the 7th Tirthaṅkara.

animals, and the male is probably meant for Indra, who plays as great a rôle in the Jaina as in Bauddha mythological literature, being an interested listener to the teaching of the Jinas;¹ and the female might be his consort, the voluptuous Śachî or Indrâñî,² but it is much more probably meant for Ambikâ, whose proper vehicle is a tiger or lion, and who is a special favourite among the Jains.

Behind each of these figures, but entered from the side aisles of the hall, is a small room about 9 feet by 11, by which access is obtained to the shrines on each side of the front area. A few steps lead down from each side room into a smaller one, carved all round with Jaina figures, at the ends of the verandahs of these side shrines. On the east the verandah has two pillars in front and two behind, rising from low parapet or screen walls, with Ambikâ in the south end facing the entrance, at the right side of which Indra is represented with a bag in his left hand and a cocoa-nut in his right, exactly like the figures we find in the shrines of the Bauddha caves facing the principal images. The hall is about 25 feet wide by 23½ feet deep, the roof supported by four square pillars with round capitals. On each side is a deep recess; in that on the right is a naked figure of Gomatêśvara, a favourite with the Digambara Jains, and of whom several gigantic figures exist in the Canarese country.³ He is always represented with creeping plants twining themselves round his limbs, snakes coming out of ant-hills at his feet, his hair falling over his shoulders, and attended by worshippers. In the corresponding recess on the left is Pârśvanâtha, also nude, and with attendant figures.⁴ In smaller recesses are figures of Mahâvîra seated cross-legged; on pilasters at each side the shrine door are nude Jaina dwârapâlas; the architraves are carved with numerous small figures; and on the throne inside is a cross-legged Mahâvîra.

Another door in the south-west corner of the great hall has a four-armed Dêvî on the right side, and below, on the left, a figure of Sarasvatî, eight-armed, with a peacock. Passing through a small room and down a few steps with sculptures on each side, we enter the verandah, a small hall similar to that just described. Ambikâ is seated at the right side of the steps, and a Dêvî opposite to her, four-armed, with two round discs or flowers in her uplifted hands, and something very like a *vajra* in her left upon the knee. Indra is seated in the west end of the verandah facing the entrance. A figure of Mahâvîra occupies the shrine and several compartments in the walls. In deep recesses again Pârśvanâtha is placed on the left, and Gomatêśvara on the right side of the hall, which is very similar in plan to the one on the east side, but the four central pillars are more elaborately and sharply carved after the pattern of those in the great hall. The two on the inner screen have sixteen sides, and also correspond to those on the screen in the great hall. One of these is represented on plate xxxix, fig. 3, and the carving on the members of the corresponding pilaster in fig. 4. Pairs of figures in dalliance fill the compartments of the low inner screen. On the ceiling are some fragments of painting in this room.

The façade of this side cave is shown in the accompanying plate vii, the greater part

¹ The *Satruñjaya Mahâtmya*, for example, is a relation made to Indra, at his own urgent desire, by Mahâvîra.

² Her name does not occur in the list of the twenty-four Śāsanadêvîs of the Jinas.

³ *Ind. Antiq.*, vol. ii, pp. 129, 353; vol. v, p. 37. An inscription on the Kârkajâ statue, however, calls it an image of Bâhubalin, who was the second son of Rishabhnanâtha, the first Tîrthanâkara. See also *Arch. Surv. W. Ind. Rep.*, vol. i, pl. xxxvii, and p. 25.

⁴ See a representation of one of these figures of Pârśvanâtha in *Cave Temples*, pl. lxxxvi.



LEFT WING OF THE INDRA SABHÂ AT ELURÂ

of it being covered with sculpture in an exceedingly good state of preservation. The right half of the rock below is excavated in two storeys and the left in one, and between the upper of the two on the right and the one on the left is a vertical belt of carving; at the bottom of it is represented a fight, in which over three prostrate bodies other three are contending with four. Over this is a smaller panel, in which two females kneel on the left and two males on the right of a sort of stool. And over this again is a figure of Pârśvanâtha seated cross-legged on a *siṃhāsana* or lion-throne, with the wheel in front, a small worshipper at the right corner, a *chauri*-bearer with high cap on each side, and the great seven-hooded snake behind him canopied his head. Above on the left is an object that may be intended to represent a structural chaitya or a dâgoba.

The lowest storey on the right has lately been cleaned of earth, and has two neat pillars in front (plate xxxviii, fig. 2). On the back wall are figures of Indra and Ambikâ, both particularly well cut, and in good preservation when excavated. Pârśvanâtha occupies the left end, and Gomaṭêśvara the right, with deer and dogs at his feet; farther back and seated cross-legged is a Tirthaṅkara. In the shrine is Mahāvira with *chauri*-bearers, a triple umbrella and foliage behind the head. Over this is another chapel with Pârśvanâtha on the left side, two small cross-legged Tirthaṅkaras on the upper half of the right side, Indra and Ambikâ in recesses on each side the shrine door, and a Jina inside with *chauri*-bearers seated cross-legged on a *siṃhāsana* with the wheel in front. In this chapel Gomaṭêśvara is carved at the front between it and the façade of the principal cave.

To the left (west) of these two, and nearly as high as both together, is a hall about 30 feet wide by 25 deep, having a screen wall in front, over which rises a pillar on each side the entrance. The upper part of this screen, which, as in temples of the tenth to twelfth centuries, forms the back of a seat inside, is carved with water-vases in small panels, each separated by two colonnettes, and the lower portion, like that of the upper storey, is carved with elephants' heads separated by slender pilasters, and each playing with or feeding on flowers: it differs only in height from the one above and in no *śardulas* being represented. Inside are four pillars with high square bases and cushion capitals, the front ones only having much carving. In the central compartment on the west wall is Pârśvanâtha,¹ with female *chhatri*-bearer, the snake behind him overshadowing his head with its hoods, and at his feet two Nâganis and two richly dressed worshippers, while round him are numerous demons trying to disturb his meditations, as the emissaries of Mâra attacked Buddha.² In the next compartment is a repetition of the same on a smaller scale, with a cross-legged Jina above.

On the east wall Gomaṭêśvara is represented in the central compartment with deer and perhaps a dog at his feet, and female attendants (plate xli, fig. 3). Above him are Gandharvas, one with a large drum just over the umbrella, and others with cymbals and garlands. In the compartment to the right of this is a smaller Pârśvanâtha, and in that to the left a standing figure half split off, with figures of deer, makara, elephant, rum, &c., by the sides. Above it is a small cross-legged Jina, and on the back wall were Indra and Ambikâ, now much defaced, with an ascetic bearing a *chhatri* and holding up one hand to her left. Two stiff Jaina dwârapâlas guard the shrine door, inside which is a Jina on a *siṃhāsana* with the wheel in front. He has two attendants and triple umbrella, with Gandharvas making music to him and bearing garlands.

¹ *Cave Temples*, pl. lxxxvi.

² *Cave Temples*, pp. 328, 345, and pl. li.



The façade over these rooms, forming a parapet in front of the hall above, has a compartment in the centre carved with a male and female, attended by two smaller females, each holding the stalk of a flower; at the sides are pilasters bearing *makaras* holding a *torana* (plate vii). On each side the wall is divided by small pilasters into panels, containing alternately an elephant's head playing with, or feeding on, flowers, and a rampant *śārdūla* trampling on a small elephant. Above this is a frieze of water-jars. Above the hall a drip projects covered with florid carving, flying figures in twos and threes, and curious little dwarfs hanging over with garlands. The next moulding is carved with numerous animals, but somewhat weatherworn; and over it is a broad frieze, broken vertically by pilasters into representations of little shrines, each containing a figure; Indra in the centre on the left and Ambikā on the right, with Gōmatēśvara, Pārśvanātha, and other Jinas in the remaining panels. The middle portion, representing the side of a building with an arched roof upheld by four kneeling figures, has a Jina seated cross-legged on the side, and another in a chaitya-window shaped recess just above him. Over this again the rock projects a little, and has served to preserve the sharpness of this sculpture.

Returning to the great hall, the section on plate xxxvii shows to some extent the variety in the patterns of the pillars supporting its roof, and of the arrangement of the sculptures on the walls. The pillars in the central hall are of five different patterns: two in the front and two in the back row are illustrated on plate xxxviii, fig. 3; the two middle columns on each side in fig. 1, with which is also shown the bracket above and the architrave; and the corner pillars are of the style represented in fig. 4. The four columns separating the verandah from the area of the hall are shown on plate xxxix, fig. 1, and those in the front of the verandah in fig. 2.

In the centre of each side wall, occupying a large compartment, is a Jina seated cross-legged on a throne, with the wheel, elephants' heads, and lions carved in front of it, and with two elephants below; like Buddha, he is attended by two *chauri*-bearers and a pair of Vidyā-dharas above, with aureole, triple umbrella, and sacred tree. On each of the other areas, between pilasters, are two smaller figures of Jinas on *siṃhāsanas*, and usually with small figures blowing conch-shells, between their trees. On the front of each pillar before the shrine, and also on the corresponding pilasters on each side, are tall nude male figures, some of them much injured. The ceiling has a large lotus in the centre, and still retains a good deal of painting, though somewhat smoked.¹ The door of the shrine is represented on plate lxxxix of *The Cave Temples*.

THE JAGANNĀTH SABHĀ.

The second large Jaina cave in this group is known as the Jagannāth Sabhā,² and is so close to the Indra Sabhā that the wall of the west wing of the upper floor of the latter has been broken through into a cell on the east side of the upper floor of the Jagannāth Sabhā. The court of this cave, however, is much smaller than that of the last, hardly 38 feet square, and has contained some structural erections now entirely destroyed. The plan of the ground-floor with the small cave to the west of it is given on plate xc, fig. 1, of the *Cave Temples*, and that of the upper floor, together with the west shrine of the Indra Sabhā, on fig. 2; and on plate xcii, fig. 3, is given a drawing of one of the pillars in the lower hall, while fig. 1 represents the style of those in the upper hall.

¹ For further details see *Cave Temples*, pp. 496-500.

² *Cave Temples*, pp. 500, 501, and plates xc and xcii, figs. 1 and 3.

The approach to the upper floor has been very clumsily planned—probably it was quite forgotten at first, and afterwards inserted—at the right corner of the court, where a rude stair leads up to the right corner of the great hall, which is 57 feet wide by 44 feet deep, and varying in height from 13 feet 4 inches in the front aisle to $14\frac{1}{2}$ feet in parts of the central area. Twelve massive pillars arranged round an oblong central area support the roof, and two in front with a low connecting parapet wall and corresponding pilasters, form three openings in 38 feet to light the interior. This arrangement, which is followed with slight modifications in all the Elurâ caves, renders them much lighter than the plan adopted in the Ajantâ, Nâsik, Kuḍâ, and other Bauddha caves. Outside, the parapet is sculptured with a large elephant head at each end and in front of each pillar, with smaller figures of human beings in the central division, and of animals in the two side divisions; and over them is a rail of small colonnettes and flower-jars, the body of each of the latter being carved with human and other figures. The front of the drip above has been carved with forty little *gaṇa*, and other sculptures above them, now much weatherworn. Over this, but removed back a few feet, are the decayed remains of a frieze richly sculptured with elephants, *makaras*, human figures, &c.

The lower floor of this is on the model of that of the Indra Sabhâ, but is much smaller, and has been finished, whereas in the latter case the pillars are little more than blocked out and the side aisles hardly commenced. This hall is only about 24 feet square and $13\frac{3}{4}$ feet high, with four pillars in the floor, and having in front a narrow verandah with two square pillars on the screen wall. This parapet has been finished only on the left of the entrance, with elephant heads below and water-jars above, while the carving on the portion to the right of the entrance has only been begun along the upper portion.

One of the front pillars to the left of the entrance, with a portion of the screen wall, is represented on plate xxxviii, fig. 3.

Two more pillars on a low partition separate the verandah from the hall, which has two recesses—one on the left side containing the usual standing figure of Pârśvanâtha with the snake-hoods over him and attendant figures, and another on the right side containing the corresponding figure of Gômatêśvara and attendants, all remarkably sharply cut. Figures of Jinas seated cross-legged fill the other six wall areas between the pilasters. In the verandah Indra occupies the left or west end, and Ambikâ the right or east end. The shrine is entered through a small antechamber with a fine *torana* arch over the entrance; it is about 9 feet by 7, and 10 feet 8-inches high, with a cross-legged figure of Mahâvira on the throne. The drip over the entrance has not been carved, and large pieces have fallen out of it.

The hall on the left side of the court is about 27 feet square and 12 feet high, with a shrine $9\frac{1}{2}$ feet by $8\frac{1}{2}$, and 9 feet $1\frac{1}{2}$ inches high, and on each side of it is a cell, the left one breaking into the next cave. This and the breaking into the cell at the left end of the upper storey of the recess on the right of this hall may perhaps indicate that it was forced in here after the others were completed.

On the other side of the court are two other small chapels, the walls of which are covered with Jaina sculpture.

CAVE XXXIV.,

The last of the series of caves, joins close on to the Jagannâth Sabbâ, and has been broken into by the hall on the west side of the court of the latter. The verandah in front

has been quite destroyed, except a small fragment of the left end. The back wall of it has two pilasters, and is pierced by a door and two windows. The hall is $20\frac{1}{2}$ feet wide by about 22 feet deep, and is 9 feet 8 inches high, with four pillars in it, and corresponding pilasters on the wall. One of the pillars is given in plate xl, fig. 4. All the spaces between the pilasters on the walls are covered with rich sculpture.¹

The colossal figure of Parśvanātha on the other side of the ridge is described in *The Cave Temples* (p. 502), where a translation of the inscription upon it, dated 3rd Phālguna sudi Ś. 1156, corresponding to Wednesday, Feb. 21, A.D. 1235, will also be found. It records the dedication of this image by one Chakrêśwara of (Va)rddhanāpura.

CHAPTER VII.

THE CAVES AT BÂDÂMI AND AIHOLE.

In *The Cave Temples* (pp. 404-416) and in the first volume of these *Reports*² the Brahmanical and Jaina caves at Bâdâmi and Aiholê, in the Kalâdgi district, were illustrated in considerable detail. The discovery of the date of the finest of them also supplied an important datum for the settlement of the chronology of these works. Little need here be added to the details there given, but, extensive as is the illustration in the first *Report*, it falls far short of representing the full sculptured wealth of these caves, and I now add a ground-plan showing the whole group of caves at Bâdâmi (plate xli, fig. 2). The ascent is from the Śaiva Cave No. I., at the west corner of the scarp, to Caves II. and III., which are Vaishṇava. Beyond them, and accessible from below, is the Jaina Cave No. IV.

Round the upper part of the walls, over the pillars in front and back of the verandah in Cave II., is a frieze containing a belt of sculpture only 10 inches broad, in which the figures are crowded together so as to represent a considerable chapter of mythology. This is given on plate viii, where figs. 1-3 represent the portion on the inside of the front wall, and figs. 4-8 that on the back. It would be needless describing these scenes in detail; those acquainted with Hindu mythology will make them out. They begin with Vishṇu sleeping on Śêsha, with the lotus springing from his navel bearing a very small Brahmâ; in the first half of fig. 2 is Śrî, his consort, bathed by elephants, &c., with Vishṇu mounted on Garuḍa, Indra on the elephant Airâvati, and other gods to the left; and well to the right Chandi destroying Mahishâsura. The next compartment is the churning of the ocean by the gods and Asuras, and the horse Uchchaiṣravas, one of the products of the operation.³ The end section (fig. 3) represents a battle. (Fig. 5, on the left end of the back wall, hardly seems connected with the others;⁴ figs. 5, 6, 7 apparently relate to the history of Kṛishṇa.⁵

On the rock outside Cave I., the Śaiva Cave, is sculptured a figure of Śiva performing

¹ See *Cave Temples*, pl. xci, fig. 2, for a drawing of one compartment.

² *Report on the Belgaum and Kalâdgi Districts* (1874), pp. 15-28, 37-40, and plates xvii to xxxvii and xlviii to I. In the *Ind. Ant.*, vol. vi, pp. 354-366, will also be found an account of the sculptures, illustrated by seven plates.



³ See *Reports*, vol. iii, *On Bedar and Aurangâbâd*, p. 17.

⁴ Portions of these sculptures are very similar to some of those on the pillars of the temple of Virûpâksha at Puṭṭalâkal. Unfortunately, they are not labelled with the names of the actors, as is the case on one pillar there, where the war of Râma with the Râkshasas is represented.—See *Reports*, vol. i, p. 32.

⁵ The principal sculptures, which are Vaishṇava, have been described in vol. i, *ut sup.*

see Bâdâmi
Memoirs by
Mr. Bawji

BADAMI.-FRIEZE IN THE VERANDAH OF CAVE II.




J. Burgess

Scale of 1 inch = 3 feet.

H. Griggs, Photographs.

AIHOLE:-CEILING OF THE BRAHMANICAL CAVE.



Scale of 1 2 3 4 5 6 7 8 9 10 feet.

J. Burgess,

H. Cousens, del.

the *Tāṇḍava* dance on a lotus, figured with the very unusual number of eighteen arms (plate xli, fig. 3), and attended by Nandī, Gaṇēśa, and Nārada.¹

In the great Cave No. III. is a frieze very similar in subject to that in Cave II., only the band is 14 inches high, and being of much greater length, the twenty compartments of varying lengths, extending to over 120 feet in all. Of this, about half is represented on plate xlii. In the central portion of fig. 1 is Śrī bathed by the heavenly elephants; to the right is Narasiṃha, the lion avatāra, tearing up Hiranyakaśipu, and on the left Viṣṇu on Garuḍa, engaged in combat with a *dēva* in a chariot. In No. 2 Viṣṇu again appears in the centre on Garuḍa, and to the right again contending with Indra in fight. A battle-scene occupies No. 3. In No. 4 Garuḍa appears carrying off the jar of *Amṛta*, the water of life, from the Asuras, and to the left protecting it. In No. 5 it is perhaps Rāhu who appears to the right of the jar; Śiva leans on Nandī, and Garuḍa is flying from the left. No. 6 represents the churning of the ocean, and Nos. 7 and 8 seem to be the scenes preparatory to that undertaking, the gods, mostly four-armed, figuring prominently as if in consultation. The other scenes² closely resemble those in Cave II. In one of them is Kṛishṇa upholding the mountain Govardhana over the flocks of Vraja, a scene also represented in the Kailāsa temple at Elurā and at Mahāvallipuram.³

The AIHOLE caves are only two—one Brahmanical and one Jaina, and have been described in the first of these *Reports*⁴ and in *The Cave Temples*.⁵ The Brahmanical shrine, though very small and much injured by Jogis living in it, is so rich in sculpture that a few specimens may be here added. Plate ix represents the roof of the small hall, and with the other examples from the neighbouring Jaina cave, figured on plate xlix of the *Report* on the Belgaum and Kalāḍgi districts, and that of the Jaina cave at Ankāi given in this volume (plate l, fig. 1) are almost the only examples yet found of an attempt to reproduce by carving in relief the forms we have become so familiar with in painting at Ajantā and elsewhere. These too may have been originally enriched by the addition of colour, though it was hardly required—the relief of the carving being quite sufficient for ornamental effect, and its greater permanency had much to recommend it. Barring a curious irregularity in the setting out, and which is owing to the shape of the room, the selection of the ornaments in this ceiling is judicious and elegant, and their arrangement is sufficiently varied, without confusion, to render it one of the most pleasing specimens of a Hindu ceiling we are acquainted with. It is so at least till we come to the elaborately constructed coffers of the temples at Baroli and Mount Abu,⁶ which belong to a later age and different style of architecture. This ceiling, however, is interesting as a first attempt at a style of decoration that afterwards gave rise to some of the most beautiful forms of Hindu architecture.

Plate xliii, fig. 2, represents Hara or Śiva with only two arms, the *paraśu*, *marhu*, or battle-axe by his left side, and the *triśūla* at his right, holding a snake in his hand, while another twines round the *paraśu*, and wearing the crescent moon on his *mukūṭa*.

¹ For a sketch of the sculpture of Ardhanārēśvara in this cave, see *Ind. Ant.*, vol. vi, p. 359, and plate.

² See *Ind. Ant.*, vol. vi, p. 365, and plates, where the figures should be arranged as follows: 2d plate, 4th, 5th, and 2d lines; 1st plate, 8th, 6th, 4th, and 2d lines.

³ *Cave Temples*, pp. 149, 460.

⁴ Vol. i, pp. 37–39, and plates xlviii to l.

⁵ Pp. 404, and 491, 492.

⁶ Tod's *Annals of Rajasthan*, vol. ii, pp. 708, 733, &c.

This is in the north or left corner at the back of the hall. In the right-hand corner is the group represented in fig. 1, of Śiva, four-armed, without symbols, but holding a triple lock of his hair on each side, with Pārvati at his left hand and Bhṛīngi, his Sannyāsī attendant, at his right. Below are four *gana*. But the peculiarity of this group is in the three goddesses that rise from a cloud in the shape of a large shell on the *mukuta*. The Gaṅgā river is fabled to flow from Śiva's hair, and the three heads perhaps represent the river goddesses of the three principal streams, which the Hindūs regard as forming their sacred river, viz., the Gaṅgā, the Yamunā, and the Sarasvatī,¹ the junction at Allahābād being called *Trivenī*—"triple braid." This triad of river goddesses was doubtless once painted—Gaṅgā, the daughter of Himālaya, would be white; Yamunā, the daughter of Sūrya, on her left, blue; and Sarasvatī, on Gaṅgā's right, would be red.

In the ends of the antechamber leading into the shrine are two sculptures, one (fig. 3) of Varāha, the boar form of Viṣṇu bearing Pṛithivī or Bhūmidēvi, the earth, on his left hands, holding the *chakra* or discus in one of the right hands, and with the *śaṅkh* figured in the upper right corner, while a Nāga and Nāginī are shown below, perhaps representing Hiranyāksha,² who had dragged off the earth, and his consort. On the opposite side is a pretty entire figure of Durgā as Mahishamardini (fig. 4), which may be compared with other figures of the same goddess elsewhere. In the left chapel, off the hall, is the Tāṇḍava dance represented in fig. 5, where Śiva has ten arms.

CHAPTER VIII.

JÔGÊŚVARI OR AMBOLI AND LONAD.

THE large cave known as Jôgêśvari, near Amboli, in Salsette, was described in the *Cave Temples* (pp. 475-477), but without any illustration. The ground-plan is now given on plate xlv, showing its general resemblance to the Dumar Lena at Elurā and the great Elephanta cave,³ while there are also marked differences perhaps indicative of the later date of this example. The great hall, which is about 94 feet each way, has twenty columns arranged in a square as in the Buddhist vihāras, and in the centre of this stands the shrine, scarcely 17 feet square inside. Being constructed under a low rocky knoll, and lighted only by what comes in through three doors and two windows in the back wall of the front verandah, with some slight addition from the side doors, it is much darker inside than any of the Elurā caves, and the drainage running into it from the sides, it must always have been a very damp temple during the rains. Now it stands deep in water for months after they cease.

There is no sculpture on the inner walls, as at Elephanta and the Dumar Lena, though the pillars are of the Elephanta type. The doors and windows in the verandah have mouldings round them, and panels above filled with small groups. The verandah in front is 117 feet long by 15 wide, and an irregular open court has been excavated before it, with two water cisterns, on the plan of the neighbouring caves at Kanheri, and also a small shrine and another room. Two narrow passages have also been cut through the rock into the east end



¹ Ante, p. 34. A similar way of representing this triad is to be found at Elephanta. See my *Elephanta*, § 44.

² See *Haricandīśa*, cccxiv.

³ *Cave Temples*, plates lxxix and lxxxv.



JOGESVARI.
SHRINE DOOR.



of this court, by the side of one of which is another small shrine. The left or west side of the hall is entered by a sloping passage, with a cistern by the side of it, which enters first into a sort of guard-room with unfinished rooms on each side, on the plan of the gateway at Elurâ, and with decayed remains of sculpture round the door. From the opposite or east side a more elaborate entrance is formed. First a stair descends or slopes down to a wide door that gives entrance to a large room over 30 feet deep, with a wide passage through it, separated from the side areas by a screen of four pillars on each side. This leads into an open court nearly 60 feet wide by 40 deep, with two irregular upright blocks of rock, apparently intended to be hewn into *dhvaja-stambhas* or ensign pillars, similar to those on each side of the court of the Kailâsa temple at Elurâ.

This court has three doors into another hall 59 feet wide by about $31\frac{1}{2}$ deep and 16 $\frac{1}{2}$ feet high, and which is divided into three areas by two rows of four pillars each—each division having its own entrance into the great hall of the cave. The central door has been carefully sculptured, and though now somewhat decayed, it is the best preserved piece of sculpture here, and is represented on plate xlv, fig. 2. Over the door, under a *torâna*, Śiva is seated—apparently receiving worship. Above the *makaras* on either side are female figures and cherubs. To the left is the marriage scene so often represented. On the right are Śiva, Nandi, and Pârvatî, and attendants; and the tall *dwârapâlas* and attendant dwarfs by the jambs are in keeping with those found in other Śaiva caves. Over the outer door of the first hall on this side is also left a portion of the sculpture representing Râvaṇa in the well-known scene under Kailâsa. Gaṇeśa figures to the left of Śiva, and among the *ganas* below expressing their scorn of Râvaṇa are some with animal heads. Over the *makaras* at the sides are figures on clouds, and above them again are clouds.

The shrine doors are also moulded, and the principal one, represented on the accompanying plate x, will fully illustrate their style, and presents a close analogy to those in the cave on the eastern hill of Elephanta called Sîtâ's *dêvala*,¹ and which is apparently more modern than the great cave there. The whole style is indicative of a later date for this hall than either the Elephanta one or the Dumar Lena; in fact, as stated in *The Cave Temples*, it may be regarded as one of the very latest of the larger cave temples in India, and may be ascribed to the end of the eighth century A.D.

LONÂD.

Lonâd is a small village about $3\frac{1}{2}$ miles N.N.E. from Kalyân, and about 30 miles from Bombay. In a hill which forms one side of a glen above this village Mr. W. F. Sinclair, of the Bombay Civil Service, discovered a rock temple in January 1875.² It faces S. by W., and consists of a verandah 48 feet long by 10 feet wide, of a hall 45 feet long by 19 deep, entered by three doors, and of an unfinished shrine at the back (see plan on pl. xlv, fig. 3). The verandah has four square pillars in front, with a carved frieze above about a foot deep; the left-end portion, or fully one-third of it, is represented on pl. xlv, fig. 1. It will be observed that there is nothing specially distinctive of any religious sect in these groups, but when compared with those in the Bâdâmi caves (plates viii and xlii), they appear to belong to the same general class. In a recess at the left end of the front of the verandah is a larger group, represented in fig. 3. It is a good deal destroyed on the right or outer

¹ See my *Elephanta*, §§ 103, 104. and drawings x and xi.

² See *Ind. Ant.*, vol. iv, pp. 68, 165.



side, but measures about 8 feet by 6 feet. A pilaster on the left side of the sculpture supports a *makara* from whose mouth a *torapa* issues, and it is probable the other side was similar. In the centre sits a male figure, as in the fourth compartment of the frieze; a small female chafes his left foot, and a taller one by his side holds up a sword, as in many of the Ajantā wall paintings.¹ On his right are three females, one with a *chauri*, and another with a dish or other round object. Two males with curled hair sit on his right, and other two on his left, each pair being engaged in conversation, while numerous other figures fill up the background. The scanty clothing of all the figures reminds one of the ✓ Amarāvati sculptures; but there is nothing distinctively sectarian in this sculpture any more than in those of the frieze.

The side doors are surrounded by plain facias, and have small standing figures at each side, and the central one has slender pilasters and a leaf moulding outside with chaitya arches on the lintel. At each side is a sort of horizontal disc, borne by a small curly-headed dwarf, both much injured (see fig. 2). Besides the unfinished shrine, there are incisions made in the back wall of the hall, as if for the beginning of two cells. There can be no doubt that this was intended as a Brahmanical shrine, but whether Śaiva or Vaishnava, it would be difficult to decide. The cave is now dedicated to a Grāmadēvi or village goddess, known as Khand-ēśvari, or the goddess with the sword (*khaṇḍa*)—possibly from the figure in the sculpture described above. In the left end of the front, opposite the sculpture, is a rough square isolated block of stone left in a recess.

✓ The style of the sculpture and of the mouldings on the pilaster, pillars, and door, indicate a much later date for this cave than for even the last described. A little to the left of this and higher up are two or three unfinished cells.

¹ e.g. in *Cave Temples*, pl. xliii, where two may be seen.

CHAPTER IX.

ELEPHANTA CAVES.

THE great cave at Elephanta, in the Bombay harbour, has been so long known to Europeans, and has been consequently so often described and so fully illustrated by Daniell and others,¹ that it is hardly necessary to say anything about it in the present work.

The cushion-shaped capitals which crown all its pillars, as represented in the accompanying woodcut (No. 18), seems to have reached its greatest development and beauty of form in this cave, but is found in greater or less perfection in so many caves dating from before and after this one, that it has come to be considered the typical capital of Indian architecture. It may be compared with the Doric style of classical art in the same manner as the vase with the leaf falling over it, as exemplified in the Râmésvara and elsewhere,² may be considered as a richer Ionic order. The two are the principal forms or "orders" of Indian art, and though they may be compared³ with the classic orders, they are thoroughly original in their form and indigenous in their inception.

The Elephanta cushion capital is also of interest, as being the same form that constitutes the *amalâ śīla* or *amalāka* crown to Hindu temples of the same age; and though we are still unable to guess from what it may have been derived, we can hardly escape the conviction that their origin was the same.



No. 18.—Pillars and Corner of the Shrine in Elephanta. From a photograph.

In some respects the Dumar Lena at Elura may be said to be a finer cave than this, as it is a larger one, but it wants that perfection of finish both in architectural and sculptural details which make this temple so remarkable and so justly admired. The third of the group—the Jôgêśvari one—both as regards its architecture and sculpture, is greatly inferior, and probably may be considered as the last of the class.

This cave may belong to the middle of the eighth century, and is the most complete of its class, which consists of the three great halls of Dumar Lena, Jôgêśvari, and Elephanta.

¹ See *Cave Temples*, pp. 465–475, and plate lxxxv for the ground plan. For some of these accounts, see Niebuhr's *Voyage en Arabie*, &c., tome ii, p. 25–33; Dr. W. Hunter in *Archæologia*, vol. vii, pp. 286–295; H. Macneil in *ibid.* vol. viii, pp. 270–277; *Asiat. Res.*, vol. iv, pp. 409–417; Forbes, *Oriental Memoirs*, vol. i, pp. 423, 432, 435, 441–448; W. Erskine, *Trans. Bomb. Lit. Soc.*, vol. i, pp. 198–250; Fergusson, *Rock-Cut Temples*, pp. 54, 55; Dr. J. Wilson, *Calcutta Review*, vol. xlii (1866), pp. 1–25; and my *Rock Temples of Elephanta or Gharapuri* (Bombay, 1871). || ✓

² Compare also the capital from cave XXIV at Ajantâ figured in *Report*, vol. iv, p. 57, woodcut No. 17; *Cave Temples*, pl. xlix, fig. 1; in the Tin Thâl, *ib.* pl. lviii, fig. 2; in the Viśvakarma, pl. lxiii, fig. 2; in Râvaṇa kâ Khâi, pl. lxxi, fig. 2; in Kailâsa, pl. lxxxiv, figs. 1, 2, 3; and at Aurangâbâd, pl. lxvi, fig. 2.

³ We might similarly compare the pillars in the Kârle Chaitya, and in several of the Nâsik Caves, with the Tuscan order.

The accompanying autotype plate xi presents two of the compartments on the back wall of this cave; that to the left being the Trimūrti or large three-headed bust of Śiva, representing him in the three characters of Rudra, Brahmā, and Viṣṇu. The central face is that of Brahmā, or Śiva as the Creator, that to the spectator's right is the same god as the preserver or Viṣṇu, and that to the left holding the snake in his hand and with the tusks is Rudra, the destructive form of Śiva. The other compartment to the left represents Śiva in the androgynous form of Ardhanārī, the right side being male, and leaning on Nandi, the favourite vehicle of Śiva, and the left female representative of Pārvatī. The gods are represented on the clouds on either side of this group doing them reverence.


But, besides the great cave, there are several others on the island, which seems to have been a very early sacred place; for, on the north-east of it, on its highest point, is a large ruined brick Baddha stūpa, which I had opened in May 1882, but found no relic chamber in it.

Not far from this, in a south-westerly direction, and north-east from the great cave, is a neat cave (plate xlv, fig. 2) with a large court in front, and having a hall or portico 73½ feet long by 26½ feet deep and 11 feet high, with four pillars in front and two pilasters. Each pillar is 3 feet square to a height of 4½ feet from the plinth on which it stands, and the neck and compressed-cushion capital, 3 feet 9 inches high, is sixteen-sided. In the back of the hall are three shrines, the side ones empty, and the central one, 15 feet 7 inches square, contains only a moulded altar.

This cave appears to be the one mentioned by De Couto (1603), who says that "in the other hill of this small island, to the east and nearly in the centre, beyond the great temple, is another temple, to which the entrance was formerly by a beautiful gate which had a porch of marble most exquisitely wrought. This temple has a large hall and three chambers; in the first, to the right hand, there is nothing left now; the second has two idols seated on a large square seat. One of these idols was called Vithalā Chendai, had six arms and only one head, and was supported by two small idols that were on each side of it."¹ This probably referred to Viṭṭhala and Chandī, or possibly only to Chandī or Durgā in one of her terrific forms—the Mahishēśvarī with the Asura and her attendants. The cave is now known as Sītābāī's Dēvala.

Quite near to the great cave, a little to the south-east of it, are two others, much ruined in front, but otherwise not without interest, and probably older than the large one. The fronts of both have entirely fallen, but they have been on the general plan of the last described, a long hall or deep verandah, with three cells at the back, and other apartments in the ends. The portico of the first (Cave II. on plate xlv, fig. 1) is 85 feet long by about 35 feet deep, with a shrine and two cells behind, and a large room in the left end, about 39 feet by 20 feet, screened off by four octagonal pillars. The shrine door is moulded, and has dwātapālas by the jambs. In the other (Cave III.) the portico has been 49 feet long, with a liṅga shrine and two cells at the back, and a room at the left end about 21 feet by 16 feet, with slender square pillars in front and a cell at the back, and at the right end is another small room leading into two more cells.

¹ *Da Asia*, dec. vii, liv. iii, cap. 11; see also Niebulr, *Voyage*, tome ii, p. 33.



TRIMURTI AND ARDDHANÂRI SCULPTURES IN ELEPHANTA CAVE TEMPLE

CHAPTER X.

HARISCHANDRAGAD AND PATNA CAVES.

THE Hariśchandrāgād Caves admit of but little illustration, as they are exceedingly plain, and what sculpture there is has been repeated elsewhere, and they have been fully described already.¹ The plans (plate xlvii) may help, however, to make the description more intelligible. Fig. 1 is the ground plan of Cave II., the most complete of the group, and whilst there is a figure of Gaṇeśa on the lintel of the central door, it will be seen from the arrangements that there is no shrine or place for worship; the plan is that of a dwelling-house, not of a shrine. There seems no reason to suppose that it was ever meant for ought else, and was probably the dwelling of the priest in charge of the neighbouring temple.

Cave I. also (see plan, fig. 2) is only a smaller place of the same sort, with a well in front. In a small room on the right side of the court of Cave III. is an altar, and inside the cave is a large figure of a nude Gaṇeśa in a panel about 6 feet square. Cave IV. consists of an outer oblong cell with an inner one rough and unfinished. Cave V. is lower, and in a water-course; the front has fallen away and a structural one is substituted. The plan is irregular and unfinished, with broad high benches along the three inner sides, and a cell on the right. Close to it is a water-cistern. Cave VI. is at a slightly higher level, and is similar to No. IV., the front room being 16 feet by $8\frac{1}{2}$ feet, but a bed of *muram* or soft clay has destroyed the walls. In Cave VII. the outer room is deeper, with an open front, and in the inner one is a long *vēdi* or altar, as if for three images, and with some small figures and lozenge-shaped ornaments carved on the front of it. At the right end is a basin to receive the water, &c., from the images. The *muram* bed has also damaged its left and back walls of this cave. Cave VIII. is similar to No. IV., with a larger cell.

To the N.N.W. of these small caves and at a lower level stands an old temple of perhaps the tenth century, consisting only of a neat Vimāna, with four small porches on the sides, standing in the middle of a court, the west side of which consists of a rocky face, in which are excavated three caves (see plan, fig 3),² one of them with a cell in the corner of it. In the south side is a shrine and two cells, and on the right is a wall with a small shrine near the entrance; the wall that once bounded the north side has fallen. This temple spire is much like that of the temple of Pāpanātha at Paṭṭadakal, and is probably as old as the rock excavations, which seem to have been meant for the accommodation of the attendants. The pillars and roofs of the small porches are elegantly carved.

Farther down the stream a little is a rock-cut hall about 55 feet square, with a large *līṅga* altar in the middle of it.

PATNA CAVES.

The caves of Pātna or Kanhar, on the south border of Khandēsh, near to the Pitalkhorā Bauddha cave, consist of three excavations, one Brahmanical and two Jaina.³

¹ *Cave Temples*, pp. 477-479; *Ind. Ant.*, vol. v, pp. 10, 11.

² The structural parts are indicated on the plan by the hatched lines being vertical.

³ *Cave Temples*, pp. 428 and 492.

The Brahmanical cave is locally known as Śringār Chāvadi, of which the ground-plan is given plate xlviii, fig. 2, and a section to double the scale (fig. 1), showing the return of the façade along the side of the court, and the carving on the screen wall and pillars, the style of which indicates a comparatively late date, as does also that of the entrance door, shown in plate xlvii, fig. 5, with its very high step and mediæval style of ornamentation.

The Jaina caves are known as Nāgārjuna's Koṭri and Śitā's Nāhni, the latter a very irregular unfinished cave, and the other, strangely enough, bearing the name of one of the greatest Bauddha teachers, if not the founder of the Mahāyāna schools.¹ The plan of the first is given plate xlviii, fig. 4, the longitudinal section in fig. 3, and a transverse section in plate xlvii, fig. 4, which shows Indra and Ambikā seated in front of the two very rude pillars, and the Jina on a low throne against the back wall. These, with the details given in the *Cave Temples*, are sufficient to give a correct idea of this very late Digambara Jaina excavation.

CHAPTER XI.

ANKAI CAVES.

LITTLE need be added to the account of the Brahmanical Caves at Ankāi-Tankāi given in *The Cave Temples*, p. 480. The sketch plate I, fig. 3 represents the sculpture at the right side of the entrance to the first cave, and fig. 2 is a drawing of the door of the shrine to the scale of 1 inch to 3 feet. The sculptures represented in these drawings indicate pretty clearly that these caves belong to about the same date as the latest Elurā Brahmanical caves, about the tenth century. There are no sculptures whatever in the other three excavations. On plate xlix, fig. 6, is a plan of the very irregular Cave No. II.

The Jaina Caves on the ascent to the hill fort are a much more interesting series,² and have been elaborately carved. The accompanying autotype plate xii presents the appearance of the first two caves, which are two-storeyed, and on plate xlix, figs 1-3, are the section and plans of both floors of No. II. On the outside wall at each end of the façade are lions in full relief, and the front wall is perforated in small square holes to admit light. In the lower storey the front apartment, about 26 feet wide by 12 deep and 9½ feet high, has the usual Jaina figures of Indra and Ambikā in the ends, and an elaborately carved door (pl. xlvii, fig. 6) from it into the hall, which is about 25½ feet square. A small lobby leads into the shrine by a door also carefully sculptured. In the shrine is a throne with an arched back and a high step to it, but no image.

The plans of Caves III. and IV. are given in figs. 5 and 6 of plate xlix, and will render the account in *The Cave Temples* more intelligible. The roof of the central area of Cave III., between the four pillars, as there mentioned, is carved with a large lotus, having four concentric

¹ Nāgārjuna is said to have lived as a hermit in Western India, but was converted to Buddhism by Kapimāla of Patnā, the 13th Patriarch. Can this story have anything to do with this locality? The cave, however, is of much later date than the time of the 14th Bauddha Patriarch, who must be placed before the Christian era.

² See *Cave Temples*, pp. 505-508, and plates xciv and xcv for plans and section of Cave No. I., also the door and image of the Jina.



TWO JAINA CAVE-TEMPLES AT ANKĀI.

rows of petals, two of which are sculptured with figures: the inner with sixteen single figures dancing or playing on musical instruments, and the outer with twenty-four, mostly mounted on different animals, and perhaps representing the gods of the Hindu Pantheon. This ceiling is represented on fig. 1, plate 1, and may be compared with the examples at Aihole already noticed (pl. ix), but to which it is much inferior.

CHAPTER XII.

INSCRIPTIONS.

By PROFESSOR G. BÜHLER, C.I.E., VIENNA.

I. THE NĀNĀGHĀT INSCRIPTIONS.

THE Nānāghāt inscriptions, which belong to the oldest historical documents of Western India, and in some respects are more interesting and important than all the other cave inscriptions taken together, have not received hitherto much attention from Orientalists, though Colonel Sykes' imperfect copies have been available for many years, and excellent photolithographs were printed by Dr. Burgess some time ago. Probably the fragmentary preservation of the large inscription has deterred epigraphists from undertaking its explanation. Paṇḍit Bhagvānlāl in his article on the coins of the Andhrabhṛityas¹ discusses, however, the general sense and bearing of Nos. I. and II., and gives particularly valuable hints regarding their connection with the six smaller coeval inscriptions. He has also given a list of the numeral signs which occur in I. and II., *ibidem* vol. xii, pp. 404-6.² His readings, however, do not always agree with the photolithographs. Before him Dr. Stevenson made some remarks on these documents,³ which, as usual, speak more for his courage as a scientific pioneer than for his knowledge of the subject.

For the attempt at a translation and explanation of the Nānāghāt inscriptions, which I now offer, I have used, besides the photolithographs taken for Dr. Burgess by Paṇḍit Bhagvānlāl, a photograph of the first half of the large inscription, also furnished to me by Dr. Burgess. As will appear in the sequel, this additional aid has proved to be very important for the beginning of line 3, and has enabled me to find what I think will be admitted to be the real connection of that fragment with those preserved in the following lines.

These inscriptions are found in a large cave at the top of the Nānāghāt, a pass which leads from the Koṅkan to the ancient town of Juunnar. Nos. I. and II. occupy the left and right side walls, while Nos. III.-VIII. are incised, as labels, above the heads of what have once been a number of portrait figures carved on the back wall.

¹ *Jour. Bo. B. R. As. Soc.*, vol. xiii, pp. 303-316. Paṇḍit Bhagvānlāl had engaged to supply translations of this and indeed of all the Cave Inscriptions, which were to have been ready nearly two years ago, but has failed to supply them in time even for this volume.—J. B.

² Also in *Ind. Ant.*, vol. vi, pp. 44, 45.

³ *Jour. Bo. B. R. As. Soc.*, vol. v, p. 174.

Transcripts.

No. I.—A. Left Wall.

- (1.) [Om̐ namo prajāpati]no Dhammasa namo Idasa namo Samkamsana-Vāsudevānam Chanda-sūtānam
[mahī]mā[v]atānam chaturānam chandī lokapālānam Yama-Varuna-Kubera-Vāsavā namo namo kumāra-
varasa Vedisirisa ra[n]o¹
- (2.) [v]īrasa sūrasa apratihatāchakasa Dakhi[nāpa]tha[patino]²
- (3.) mā [bā]lāya mahārathino Ambgiya-kulavadhanasa sagaragiriavaravala[yā]ya pathaviya patha-
mavīrasa vasa . . ya va alaha (?) salasu . ya mahato maha . .³
- (4.) sirisa bhāriyā devasa putradasa varadasa kāmadasa dhanadasa Vedisiri-mātu
Satino sirimatasa cha mātuya sīma pathamaya . . .
- (5.) variya ā[n]āgavaradayiniya māsupavāsiniya gahatāpasāya charitabrahmachariyāya
dikhavratayamāsasundāya yañā hutā dhūpanasugandhā yaniya
- (6.) rāyasa [ya]ñehi yītham vana | Agādheya-yamño dakhinā dinā gāvo bārasa
12 aso cha | Anārabhaniyo yamño dakhinā dhenu
- (7.) dakhināyo dinā gāvo 1700 hathi 10
- (8.) sa . . sasataraya [v]āsalaṭhi 289 kub-
biyo rupāmayiyo 17 bhi⁴
- (9.) riko yamño dakhināyo dinā gāvo 11,000 asā 1,000
pasapako
- (10.) 12 gamavaro 1 dakhinā kāhāpanā 24,400 pasapako kāhāpanā 6,001 Rāja
[sū]ya-yamño sakatam

No. II.—B. Right Wall.

- (1.) dhammāgiritadāsapayutam sapato 1 aso 1 asaratho 1 gāvīnam 100 Asamedho bitiyo [yi]tho dakhināyo
[di]nā aso rupāla[mkā]ro 1 suvarāna . . si 12 dakhinā dinā kāhāpanā [1]4,000 gāmo 1 ha[thi]
. [dakhī]nā dinā⁵
- (2.) gāvo . sakatam dhammāgiritā[n]sapayutam ovāyo yamño
. 17 dh[enu]! . . vāya . satara sa⁶
- (3.) 17 acha na . la ya
. . . pasapako din[o] [dakhī]nā dinā su . . . ptni 12 tesa rup[ālan]kāro
1 dakhinā kāhāpa[nā] 10,000 . . . 2⁷

¹ L. 1. In the beginning six or seven syllables have been lost. It is certain from the construction that the word *namo* must have stood before an adjective or noun qualifying *dhammasa*, and it may be inferred from the usual practice observed in inscriptions that the first word was *Om̐* or *Sūtham̐*. The restoration [*prajāpati*]no rests on the fact that in the *Purāṇas* Dharma is one of the *Prajāpatis*. In *mahimāvatānam* the top of the *ma* is visible, as well as the vowel *i* and the top of the *ra*. For *cham̐* read *cha*.

² L. 2. The restoration *Dakhināpātha* seems to be certain, because the inscription was written in the Dekhan. The second part of the compound may have been *īsarasa*, *patino*, or *sāmīno*.

³ L. 3. The restoration *bālāya* is based on the photograph, where the letter *la* is faintly, but still distinctly readable before *ya*.

⁴ L. 8. Possibly *Asaḍaṭhi*, which, however, gives no sense. The last figure in 289 is not certain. Pandit Bhagvānlāl reads 189, but the 200 is plain on the facsimile and on the photograph. It is just possible that the sign read as 9 is a mutilated *da*, and belongs to *kubbiyo*. *Dakubbiyo* might mean *ulakubhiyo*, "water-vessels." Read *rupimayigo*. See Childers, *Pali Dict.* s. v. rūpi. L. 10. Read *gāmavaro*.

⁵ L. 1. Possibly *kāhāpanā* 24,000 may have been the original reading, for before 4,000 only 7 1000 appears, and the determinative sign, which must have been 10 or 20, has been effaced.

⁶ L. 2. The figure after *gāvo* is blurred on the facsimile. Pandit Bhagvānlāl reads it 60,000.

⁷ L. 3. Probably *pasapako dīno* is to be read. Probably some more figures followed after 10,000.

- (4) gāvo 20,000 [Bhaga]la-*Dasarato* yañño y[i]tho dakhinā di[nā]gāvo 10,001 Gargatirato yañño
y[i]tho dakhinā pasapako paṭā 301 Gavāmayanañ yañño y[i]tho[dakhinā dinā]gāvo 1101
gāvo 1100(?) pasapako kāhāpanā . paṭā 100 Atuyāmo yañño¹
- (5) [Ga]vāmayanañ yañ[o] dakhinā dinā gāvo 1,101 Aṃgiras[ā]mayanañ yañño y[i]tho
dakhinā gāvo 1,101 ta [dakhinā d]inā gāvo 1101(?) Satātiratam yañño
100 [ya]ñño dakhinā g[ā]vo 1100 Aṃgirasa[ti]rato yañño y[i]tho[dakhi]-
nā gāvo
- (6) gāvo 1,002 Chhamdomapa[va]mā[natirato] dakhinā gāvo 1,001 Aṃg[i]ra[satira]to yañ
[ño-yi]tho da[khinā] rato y[i]tho yañño dakhinā dinā to
yañño y[i]tho dakhinā yañño y[i]tho dakhinā dinā gāvo 1001
- (7) na . sayam dakhinā dinā gāvo
ta [Aṃ]gi[rasā]mayanañ chhavaśa [dakhi]nā
dinā gāvo 1,000 dakhinā dinā gāvo 1,001 teraśa a
- (8) Terasarat[sa] āga dakhinā dinā gāvo
Dasarato ma [di]nā gāvo 1,001 u
1,001 da
- (9) [ya]ñño dakhinā di[nā]
- (10) [da]khiṇā dinā²

Translation.

A.—Left Wall.

1. "[*Om adoration*] to Dharma [*the Lord of created beings*]; adoration to Indra, adoration to Saṃkarshaṇa and Vāsudeva, the descendants of the Moon,¹ (*who are*) endowed with majesty, and to the four guardians of the world, Yama, Varuṇa, Kubera and Vāsava; praise to Vedisīri, the best of royal princes! Of the king

2. " of the brave hero, whose rule is unopposed, (*of the lord of*) the Dekhan

3. "By the daughter of the Mahārāṭhi, the increaser of the Aṃgiya race, the first hero of the earth that is girdled by the ocean and the best of mountains³

¹ L. 4. The top, the sign for 1000 in 20,000, has been lost. The two letters *Bhaga* are not certain. The *r* in *garga* is not certain. The sign for 100 in 1101 is blurred, but the amount paid for the Gavāmayana mentioned in the next line is 1101.

² L. 10. It seems doubtful if the tenth line was the last.

³ L. 1. Krishna and his elder brother Balarāma are remotely descended from the Moon, and the expression *sātānam*, literally "sons," must be taken in this sense. The form *sāta* for *suta* may be owing to a clerical mistake, or to a fissure in the rock, but in some of the modern Prakṛits, e.g. in Gujarātī, *sāta* is frequently used for *suta*. Among the guardians of the quarters Yama is named first, apparently because the inscription was written in the South. In my opinion the *mangalācharaṇa* ends with the word *Vedisirisa*, "to Vedisīri." It is hardly likely that that individual who is called "the best of royal princes" should immediately afterwards be mentioned as a king. It seems to me more probable that the word *raño*, "of the king," applies to another person, whose name is lost. To the same person apply the epithets also which are contained in the fragment of L. 2. It is impossible to say with certainty in what connection his name may have been introduced, but see the remarks below.

⁴ L. 3. The fragments in line 3-5 form, it would seem, one sentence, the subject of which is *yaññā dhāpamasugamdhā* (l. 5), "sacrifices odoriferous with incense," while the verb is *huta*, "were offered." The adjectives ending in the fem. instr. abl. gen. which precede the word *yaññā* qualified the queen who caused the sacrifices to be offered. The same person, it seems to me, is referred to by the words . . . *sirisa dhāriṣā*, "the wife of . . . sri," *Vedisirimātu*, "the mother of Vedisīri," *Satino sirimatasa mātuya* in line 4, and *bdāya*, "the daughter of," in line 3. It is not uncommon in inscriptions that queens and other females are described by giving

4. "(Who is the) wife of . . . śrī,¹ the lord who gives sons, boons, (the fulfilment of) desires and wealth, (who is the) mother of Vedisrī and the mother of the illustrious Śakti

5. "Who gave a . . . most excellent (image of) a snake (deity),² who fasted during a whole month, who (even) in her house (lived like) an ascetic, who remained chaste, who is well acquainted with initiatory ceremonies, vows and offerings,—sacrifices, odoriferous with incense, were offered

6. "of the king sacrifices were offered. Description—An Agnyādheya sacrifice (was offered), a sacrificial fee was given (consisting of) twelve, 12, cows and 1 horse;—an Anvārambhaniya sacrifice (was offered), the sacrificial fee (consisted of) . . .³ milch-cows

7. " sacrificial fees were given (consisting of) 1700 cows, 10 elephants

8. " 289 (?) . . 17 silver waterpots⁴

9. " a rika-sacrifice, sacrificial fees were given (consisting of) 11,000 cows, 1000 horses

10. " 12 . . . , 1 excellent village, an (other) sacrificial fee (consisted of) 24,400 Kārshāpanas, (the gifts to) the spectators and menials (consisted of) 6,001 Kārshāpanas; a Rāja[sūya-sacrifice] the cart⁵

first their descent, next their position as married women, then the names of their sons, and last an enumeration of their virtues. If this conjecture as to the connexion of the three fragments is correct, it will, however, be necessary to alter *bhāriyā* in line 4, which stands in the nominative case, to *bhāriyāya*, the instrumental, and *Vedisirimātu*, a genitive, to *Vedisirimātuya*, the instrumental. The name of the pious queen has been lost. Regarding the meaning of the word *Mahārāṭhi* see my remarks on Kārle No. 20, *Reports*, vol. iv, p. 107. "The best of mountains" is either the Himālaya or the Vindhya.

¹ L. 4. The name of the king whose queen is here described is, unfortunately, mutilated. As the remnant *'sirisa* shows, it ended, like the names of some other Andhra kings, in *śrī*. *Satino* undoubtedly corresponds to Sanskrit *Śakti*, and we have here the proof that the Śaktikumāra who is frequently mentioned in the legends regarding Vikramāditya and Sātavāhana as a son of the latter, really was a historical person; compare also Prof. Jacobi on the *Viracharita*, in Weber's *Indische Studien*, ch. xiv, pp. 108 *seqq.*

² L. 5. The translation of *nāgavaradāyiniya*, "who gave a most excellent image of a snake deity," is of course uncertain, because the word may be mutilated in the beginning, and because *nāga* means also "elephant" and *vara* "a boon."

³ L. 6. [*Ya*] *ñehi yīṭhaṁ* corresponds to Sanskrit *yajñair iṣṭam*, and is the impersonal passive construction. In the original there is a larger blank space left after *yīṭhaṁ*, which indicates that one part of the inscription is finished. The word *vano*, which opens the second part, corresponds to Sanskrit *varṇa* (*prāśasti*), and has to be taken as an equivalent of the common Jaina *vaṇṇao*, which is used in order to imply that the conventional description of a person or thing mentioned has been left out, and must be supplied by the reader. It may be translated by "description" or "details." The horizontal stroke which follows *vano* is a stop, and used frequently in ancient inscriptions for the single or double vertical stroke | or ||, which latter occur both on ancient monuments and in modern MSS. The Agnyādheya, "the kindling of the sacred fires," precedes all Śrauta sacrifices. It is followed by the Anvārambhaniyeshṭi, called in the text Anārambhaniyo yamño.

⁴ L. 8. I leave *vāsulaṭhi* untranslated. The corresponding Sanskrit word *vāsayaṣṭi* means "a perch" for peacocks and other birds. It seems hardly likely that the same object is meant here. Regarding the figure compare the note to the transcript. The text has plainly *rupāmāyigo*, but *rūpāmāyigo* is required (see Childers, *Pali Dict.* s. v. *rūpi*).

⁵ L. 10. In several cases the word *dakṣiṇā*, "sacrificial fee," occurs more than once in connection with the same sacrifice. Probably the several sets of officiating priests received in these cases separate gifts. *Pasapako*, "the presents to the spectators and menials," corresponds to Sanskrit *prasarpaka*, literally "one who approaches." The latter word is used as a technical term for the spectators and menials who assisted at the sacrifices (see the *Pet. Dict.* s. voce). It is evident from the context and from the phrase *pasapako dīn[o]* in L. 3 that in this inscription "the presents given to" such persons are intended, and that *pasapako* stands for *prasarpaka*.

B.—Right Wall.

1. "Used for conveying a mountain of grain, 1 excellent dress, 1 horse, 1 horse-chariot, 100 kine. A second horse-sacrifice was offered; sacrificial fees were given (*consisting of*) 1 horse with silver trappings, 12 golden . . ., an(*other*) sacrificial fee was given (*consisting of*) 14,000 (?) Kārshāpanas, 1 village . . elephant . . ., a sacrificial fee was given¹

2. . . . cows, the cart used for conveying a mountain of grain an . . . OVĀYA sacrifice 17 milch cows (?) . .

3. 17 presents to the spectators were given a sacrificial fee was given (*consisting of*) 12 1 (*set of*) silver ornaments for them, an(*other*) sacrificial fee was given consisting of 10,000 Kārshāpanas

4. 20,000(?) cows; a Bhagala-Daśarātra sacrifice was offered, a sacrificial fee was given (*consisting of*) 10,001 cows; a Gargatrirātra sacrifice was offered the presents to the spectators and menials (*consisted of*) 301 dresses; a Gavāmayana was offered, a sacrificial fee was given (*consisting of*) 1,101 cows, a . . sacrifice, the sacrificial fee (*consisted of*) 1,100 (?) cows, the presents to the spectators and menials (*consisted of*) . . Kārshāpanas, 100 dresses; an Āptoryāma sacrifice (was offered)²

5.; a Gavāmayana sacrifice was offered, a sacrificial fee was given (*consisting of*) 1,101 cows; an Angirasāmayana sacrifice was offered, a sacrificial fee was given (*of*) 1,101 cows; (a sacrificial fee) was given (*consisting of*) 1,101 cows; a Satātirata sacrifice 100; . . . sacrifice was offered, the sacrificial fee (*consisted of*) 1,100 cows; an Āngirasatrirātra sacrifice was offered; the sacrificial fee (*consisted of*) . . . cows³

6. 1,002 cows; a Chhandomapavamānatrirātra sacrifice was offered, the sacrificial fee; a rātra sacrifice was offered, a sacrificial fee was given; a tra sacrifice was offered, a sacrificial fee; a sacrifice was offered, a sacrificial fee was given (*consisting of*) 1,001 cows⁴

7.); a sacrificial fee was given (*consisting of*) . . . cows; an Angirasāmayana, of six years (*duration*), a sacrificial fee was given, (*consisting of*) 1,000 cows (a sacrificial fee) was given (*consisting of*) 1,001 cows, thirteen

¹ L. 1. The grain used for the sacrifices is brought to the sacrificial enclosure in a bullock-cart, which afterwards is made over to the priests. Hence a cart is twice enumerated among the fees. The sense of *taṁsa*, "conveying," seems to be clear from the context, but its etymology is not certain. The Prakrit dictionaries and grammars give *taṁsa* as an equivalent of *tirichha* (*tiryak*) and *tryasra*, which do not answer in this case. Possibly *taṁsa* may be here a noun of action, derived from the root *taṁs*, "to move, to shake." *Sapaṭo* stands for Sanskrit *satpatta*, "an excellent dress or piece of cloth" (see also below, line 4). I take *gāṛiṇaṁ* for the gen. pl. of *gāṛi*, "a cow," governed by *satam*, "one hundred," which is expressed by a figure only. The expression "a second horse-sacrifice" shows that the last sacrifice mentioned, the name of which has been lost, must also have been a horse-sacrifice.

² L. 4. I am not able to find the *Bhagala-daśarātra* in the Śrauta-sūtras. But as Bhagala is the name of an ancient Brahmanical teacher, it is not improbable that a rite, called after him, existed. Regarding the *Gargatrirātra*, see *Āśvalāyana Śrauta-sūtra*, x. 2, 6. The Gavāmayana is one of the Sattras, or sacrificial sessions. The Āptoryāma is a well-known Soma sacrifice.

³ L. 5. The Angirasāmayana is also a Sattra. I leave the name *Satātirata* in its Prakrit form, because I am unable to identify it in the Śrauta-sūtras. Regarding the Āngirasatrirātra, see *Āśv. Śrauta sūtra*, ii, 2, 1.

⁴ L. 6. Regarding the *Chhandomapavamānatrirātra*, see *Pet. Dict.*, s. v. *Chhandoma*.

- 8.) a Trayodaśarātra a sacrificial fee was given,
 (consisting of) . . . cows a Daśarātra
 . . . a . . . sacrifice, a sacrificial fee was given (consisting of) 1001 cows¹
 9-10.²

No. 3—

This and the following five inscriptions are incised on the back-wall of the Nānāghāt Cave, above the positions of the heads of what were relieve figures now entirely destroyed.

Rāyā Simuka—Sātavāhana sirimāto.

—“King Simuka Sātavāhana, the illustrious one.”³

No. 4—

Devi-Nāyanikāya raño cha
 Sīri-Sātakanino.

—“(The images) of the Queen, Nāganikā, and the King, the illustrious Sātakarṇi.”⁴

No. 5—

Kumāro Bhāya⁵

—“The Royal prince Bhāya”

No. 6—

Mahārāṭhi Tranakayiro.⁶

—“The Mahārāṭhi (feudal baron) Tranakayira.”

No. 7—

Kumaro Hakusiri.

—“The Royal prince Hakusiri.”⁷

No. 8—

Kumāro Sātavāhana.

—“The Royal prince Sātavāhana.”

No. 9—Over a cistern near the large cave. This inscription is much later than the preceding ones, and belongs to the times of Gautamīputra Sātakarṇi I. or Puṣumāyi.

Sopārāyakasa Govindadāsasa
 deyadhama poḍhi.

—“A cistern, the meritorious gift of Govindadāsa, an inhabitant Śorpāraka (Sūpārā).”⁸

¹ L. 8. Regarding the Trayodaśarātra sacrifice, *Āśv. Śr. sū. xi, 2, 1.*

² L. 9-10. The only fragments remaining are not worth translating. It is, however, very uncertain if the inscription ended with line 10.

³ Paṇḍit Bhagvānlāl takes the word *Simuka* as an equivalent of Sanskrit *śṛimukha*, and attributes to it the same sense as to *bhāḍramukha* in the Jastan pillar inscription. The objection to this exceedingly ingenious explanation is, that *śri* in all the Prākṛits invariably becomes *sirī*, or *siri*, and *mukha* either remains *mukha*, or becomes *mugha* or *muka*. It seems to me, also, that the adjective *sirimāto*, i.e., *sirimanto*, *śrīmāto*, which follows the name, makes a *śṛimukha* superfluous, and its employment improbable. A different solution of the difficulty is suggested by the fact that Indian kings often have double names, the first being the real name, and the second either a family name, or a so-called *Biruda*. To the first kind belongs, e.g., the familiar instance Prithvirāj Chohan, and to the second the equally well-known Jasingh Sidhrāj. In the same manner it might be that *Simuka* was the proper name of this king, and Sātavāhana his family name or *Biruda*. That there are good reasons for considering this view to be the correct one will be shown below in the remarks on these inscriptions.

⁴ Nāyanikā, in S. Nāganikā, is a double diminutive from S. nāga, “a snake.”

⁵ The name was probably Bhāyala, as a female name Bhayilā occurs at Kudā, inscription No. 12.

⁶ The first letter of the name is not certain. It may be also read as *va* or *bha*. I cannot give a transliteration of the whole into Sanskrit, but think that the syllables *ayiro* correspond to Sanskrit *ārya*. Regarding the meaning of the title *Mahārāṭhi*, see Kārle, inscription No. 20.

⁷ Hakusiri, which, according to the method of spelling used in the ancient inscriptions, may stand for Hakusiri, would correspond exactly to Sanskrit Saktuśrī, “he whose glory is the (sacrificial) barley-flour.” But it will be shown below in the remarks that it is probably a corruption of *Saktiśrī*.

⁸ See *Ind. Ant.*, vol. xi, p. 236.

Remarks.

Owing to the mutilation of Nos. I. and II. the inquiry into the bearing of the Nānāghāt inscriptions on the early history of the Dekhan presents very considerable difficulties, and its results must always remain open to adverse criticism, in a higher degree even than those deduced from other documents of the same class, because more conjectures and speculative combinations are necessarily required in order to obtain them. But it seems to me that a complete and minute analysis of the contents of these documents, and a careful utilisation of the information available in other inscriptions and in the Purāṇik accounts of the Southern dynasties, permits a combination of the fragments into a self-consistent story and a fuller solution of the riddles which they offer than might be expected at a first glance.

The fundamental principles on which the inquiry must be based are those three, the importance of which Paṇḍit Bhagvānlāl has already recognised, and which he has in part, at least, correctly applied in his article on the coins of the Andhrabhṛityas. First, it must be assumed that the royal personages mentioned in the large inscriptions (Nos. I. and II.) are identical with or intimately connected with those represented in the broken relievos on the back wall of the cave, and named in the six small inscriptions accompanying them. Secondly, it must be acknowledged that they refer to the same dynasty, which has left records of its deeds and its liberality towards the Bauddha monks in the caves of Kārle, Nāsik, and Kaṇheri, and on the Amarāvati stūpa, and which the *Purāṇas* call Andhras or Andhrabhṛityas. Thirdly, it must be conceded that the characters of the Nānāghāt inscriptions belong to a period anterior by about 100 years to that of the edicts of Gautamīputra Śātakarṇi I. and his son Vāsishṭhīputra Puṣumāyi.

As regards the first proposition, its probability is very great on account of the fact that the same cave contains the two sets of inscriptions, and that, as the characters show, both belong to the same period. What can be more natural than the assumption that the relievos are intended as illustrations of the large inscription, especially as the most superficial comparison of the labels over the heads of the figures with the large inscription shows that the former represent two kings, a queen, a Mahārāṭhī, and three royal princes, while the fragments of the latter certainly mention a queen, one or possibly two kings, a Mahārāṭhī, and at least two princes? This probability gains considerably by the analogous custom pointed out by Paṇḍit Bhagvānlāl, according to which both Bauddha and Jaina founders, restorers, and benefactors of temples, set up so-called Śālikās, i.e., their own and their relatives' statues in the sacred precincts, grouping the images according to the various generations.¹ The occurrence of this practice in such widely distant countries as Gujarāt and Nepāl, permits us to infer that once it was universal all over India. Traces of it, I think, are also found in other Western caves, e.g., at Kārle and Kuḍā, where figures of kings and queens are introduced, which look very much as if they were intended for portraits. But in order to make the connection between the two sets of inscriptions and the figures really convincing, it is necessary to show that at least the number and the characters of the persons named in them actually correspond. To prove the identity or correspondence of all the names is, of course, impossible, because the majority of those in Nos. I. and II. have been lost or mutilated. Paṇḍit Bhagvānlāl, who has partly attempted this task in the article quoted above, arrives at the conclusion that the male figures with the short

¹ Examples are found in some of Vastupāla's temples, e.g., at Âbū.

inscriptions represent three generations of the Andhra dynasty. 1. King Sātavāhana. 2. King Sātakarṇi. 3. The sons of the latter, the Kumāras or royal princes Bhāya[la] Hakusiri and Sātavāhana. He further identifies King Sātakarṇi with the royal prince (*kumāra*) Vedisiri, and believes that the latter is referred to also by the word *raño* "of the king" (at the end of line 1), and is described as a Mahārāṭhi and "increaser of the Aṅgiya race" (line 3). The latter name he is inclined to correct to Andhiya, and to take as an equivalent of a Sanskrit adjective Andhriya,¹ derived from Andhra. Finally, he assumes that Vedisiri-Sātakani was the person who caused the inscriptions to be incised.

I regret that I am unable to agree with a portion of my learned friend's remarks, and must differ from him on all his deductions, except that the relieves and their headings refer to three generations. In favour of the latter point particularly is the circumstance that the first king and the last Kumāra bear the same name, and that it is usual among the Hindūs to name the grandson after his grandfather. The distribution of the persons named in these three generations, on the other hand, cannot be correct, for Paṇḍit Bhagvānlāl entirely forgets No. VI., the Mahārāṭhi Tranakayiro, and neglects to notice the circumstance that this individual is placed between the Kumāra Bhāya[la] (No. V.) and the Kumāras Hakusiri and Sātavāhana. The latter circumstance makes it highly improbable that the three Kumāras belong to one and the same generation. As a stranger is introduced after Kumāra Bhāya[la], it is more likely that this prince belonged to the second generation, and, in fact, was a brother of king Sātakani. This conjecture would become almost a certainty if it could be shown that the Mahārāṭhi was not a son of Sātakani, but closely connected with him in some other way. An analysis of the contents of the first part of the large inscription will, I think, show in what relation the Mahārāṭhi Tranakayiro stood to Sātakani, and furnish further proof that the third generation consisted of two members only. It will also make evident that Paṇḍit Bhagvānlāl makes too much of Kumāra Vedisiri, and errs in identifying him with King Sātakani.


In considering the contents of the large inscription the first question is, Who is the chief person in it? Now, the central figure is a queen, whose name has been lost. Line 3 gives her parentage, deriving it from a Mahārāṭhi, "the increaser of the Aṅgiya race," whose name is also lost. Line 4 states that she was the wife of a king, whose name ended in . . . siri, and that her two sons were Vedisiri and Sati. Line 5, finally, gives a catalogue of her virtues, asserts that she was "well acquainted with initiatory ceremonies (*dikhā*), vows (*vrata*), and sacrifices (*yañā*), and contains the very important information that "sacrifices were offered by her (*yañā hutā*)." Thus, she and her affairs occupy three out of the five lines and a half over which the first part of the document extends, and it is said of her that she performed, or caused to be performed, those very acts, with the enumeration of which the second part of the inscription is filled. As another sentence ending in *yañehi gīṭham*, "sacrifices were offered," followed the phrase *yañā hutā* and immediately preceded the word *vano*, "description" or "details," it is of course possible to demur to the conclusion that the queen caused the particular sacrifices named in the description to be offered, and to contend that some other male agent was named in the last portion. Though it might, further, be urged in favour of such a conjecture that, according to the *Sāstras*, women are not allowed to offer Śrauta sacrifices, and that Brāhmanas who perform such sacrifices for them (*striyājaka*)

¹ An adjective *Andhriya*, is, however, not traceable in Sanskrit, where *andhra*, *andhra*, and *andhraka* alone occur.

are severely blamed, yet that seems hardly probable, for in the sentence which ends with *yañehi yitham*, "sacrifices were offered," we have the impersonal passive construction and the genitive *rāyasa* "of the king" (l. 6, first word). It is for this reason not likely that the clause contained any personal agent. Further, though in general Brahmans are forbidden to act as priests for women, that prohibition does not apply to queens who may be conducting the government of a state, either independently or for minor sons. In that case the disabilities attaching to the sex are removed by the position which the female occupies.¹ Now, it seems to me that the queen described in the large inscription must have been ruling as guardian of her son, the prince Vedisiri. For though, as has been shown, she is the chief person in the inscription, "the best of royal princes," Vedisiri is addressed in line 1 with *namo*, "adoration to" or "praise to," and treated with the same reverence as the gods invoked in the beginning of the *mangalācharana*. That fact points to his occupying a privileged and particularly high position. Further, in the enumeration of the queen's virtues (line 5), it is asserted that she "lived (even) in her home like an ascetic" (*gahatāpasā*), and "remained chaste" (*charitabramhachariyā*). Such behaviour befits a widow only, not a wife whose husband is living. A widow must, as is well known, never violate the duty which she owed to her husband, and it is particularly prescribed that she shall emaciate herself by fasts and other austerities. A married wife, on the other hand, has no business with such practices, and the duty of conjugal intercourse is incumbent on her. Hence, it seems that the two epithets *gahatāpasā* and *charitabramhachariyā* clearly indicate that the king was dead. If that was the case, the conclusion that the widowed queen ruled during the minority of her son, and that that son was Vedisiri, follows from the *namaskāra* addressed to him. If these combinations are admitted, the large inscription mentions—1. A defunct king whose name ended in . . . siri. 2. His widowed queen (name lost). 3. The father of the queen, a Mahārathi (name lost) of the Aṅgiya race; 4, 5, two sons of 1 and 2, the prince Vedisiri and the illustrious Sati. But there is still one line (2) which has not been taken into account. The fragment remaining speaks of a "brave heroic lord of the Dekhan whose rule was undisputed," and if the last word *raño* in line 1 is,—as in my opinion must be,—connected with the words in line 2, it appears that he was a king. The individual referred to cannot have been the Mahārathi mentioned in line 2. The construction forbids this, because the word *bālāya* stands before *mahārathino*. Moreover, as stated above, *Mahārathi* was a title belonging to a feudal baron, and had a meaning similar to the title *Mahāsāmanta*. This follows clearly from the fact that in Kārle No. 20 the Mahārathi of the Okhalakiyas dates according to the regnal years of Puṣumāyi. Again, the word *raño* and the fragment of line 2 cannot be connected with the preceding genitive *Vedisirisa*, because it is clearly impossible that a person who is called a royal prince, can at the same time receive the title "king" and be said to be the lord paramount of the Dekhan. Thus the only course is to assume that the words in question refer to a sixth individual, a second king, who, as his name stands before that of the consort of the pious sacrificer, either was his father or remoter ancestor.

If we now turn to the persons mentioned in the small inscriptions, it is clear that the number and the character attributed to each correspond almost exactly with those in the larger. They may be arranged as follows :—

¹ For the fact that queens ruled in India, compare *Rājataranginī*, i, 70; vi, 313 *seqq.* and the grants of Queen Vijayabhāṭṭārikā of the Chalukya race, *Jour. Bo. Br. As. Soc.*, vol. iii, p. 203; *Ind. Ant.*, vol. vii, p. 163.



The only difficulties which remain are (1) the discrepancy between the name Sātakani (No. IV.) and that ending in . . . siri (No. I.), (2) the discrepancy between the names of the two princes in Nos. VII. and VIII. and in No. I. Now, it must be noted that Sātakani is not a proper name, but a *Biruda* or title, and that we have, at least, one certain case where a king who was called Sātakani had a second name containing the word—SIRI, in that of the second Gautamiputra of the Nāsik and Kanheri inscriptions, whose complete name is in Prakrit Gotamiputa Siri-Yañña Sātakaṃpi. The fact that the name of the second king in No. II. ends in . . . siri, and in No. IV. is Sātakani, is, therefore, no obstacle to their identification. As regards the names of the Kumāras the case is somewhat different. The Sanskrit form of the name of the prince called in No. I. “the illustrious Sati” is undoubtedly Śakti. The Prakrit word is the regular representative of Śakti, and we know, from the legendary history of Sātavāhana,¹ that a Śaktikumāra belonged to his line. Though in general I do not attribute any historical value to those legends, yet I think it cannot be denied that they have correctly preserved some of the names of the persons whose lives they pretend to describe. Now, if Śakti is the Sanskrit etymon of Sati, it is quite possible that *Haku*, which, according to the method of spelling adopted in the old inscriptions, may stand for *Hakku*, is another stronger Prakrit corruption of Śakti.² It ought not to be objected that, even admitting the philological possibility of the identification of Sati and Hakku, it is improbable that two such different forms should be used to designate the same individual in two closely allied inscriptions. For, to judge from the examples furnished by other ancient Prakrit inscriptions, the Hindus did not hesitate to vary the forms of names even in one and the same inscription. Thus we find in Nasik No. 14 the forms Puḷumāyi, and in the postscript No. 15 Puḷumavi, and Bhadāvaniya in No. 14 against Bhadāyaniya in No. 15. Similarly in the Jaggagyapettā inscriptions (*Ind. Ant.*, vol. xi, p. 256), where a number of names occur formed with the word *nāga*, “snake,” we find sometimes *nāga* and sometimes *nāka* employed. Under these circumstances I not only take Sati and Haku to denote the same person, but to be two different forms of the same name. If the illustrious Sati and Prince Hakuṣiri are one, it follows that Vedisiri is another name of Sātavāhana, and it must be noted that Sātavāhana is just as little a proper name as Sātakani, but either a family name or a *Biruda*. It will be observed that the order in which the two

¹ See e.g. Jacobi on the *Vivacharita*, Weber, *Ind. Stud.*, vol. xiv, p. 103.

² The change of *sa* to *ha* is not at all uncommon; see Kuln, *Pāligrammatik*, p. 45, 53 (where Pāli *suṇṇā*, *suṇṇā*, and *hauṇ* for Sanskrit *mushā* ought to be compared), and the common name *Haṇḍha* in the Amarāvati inscriptions for *Saṇḍha*; that of *kta* to *kka* is just as usual as that of *kta* to *tta*. And there are at least some instances where final *u* appears for *i*; e.g. in *Teraṇhu* (Nāsik inscriptions, Nos. 11 B, 15, 18) for *Triraṇmi*. See also Kuln, *ibidem*, p. 25.

princes are named differs in the two sets of inscriptions. In the large one Vedisiri stands first and Sati second, while in the short one Hakusiri appears before Sātavāhana. The cause of this discrepancy probably is that Sati-Haku was the elder by birth, but that the succession to the throne devolved on Vedisiri-Sātavāhana, either for unknown political reasons, or because the elder brother was dead at the time when the inscription was incised.

In turning now to the second point—the question as to which Andhra kings of the Purāṇik lists, the princes named in the Nānāghāt inscriptions have to be identified with,—I must premise that the link which connects the latter with the Andhra dynasty consists in the names Sātavāhana and Sātakani. From the Nasik inscriptions Nos. 1 and 14 we learn that Kṛishṇa, Puṣṭamāyī, and Gautamīputra Sātakani I. call themselves members of the “race of Sātavāhana,” and these same kings belong, according to the *Purāṇas*, to the dynasty of the Andhras or Andhrabhṛityas. Again, the title or *Biruda* Sātakani is given in the cave inscriptions to several members of the Sātavāhana family, and in the Purāṇik lists, its Sanskrit original, Sātakarṇi or Śātakarṇi, appears repeatedly as the name of Andhra kings. Moreover, it has not hitherto been found applied to any other princes but those of the Sātavāhana-Andhra family, and its use seems to be confined to them. Under these circumstances we may safely infer that wherever we find kings or royal princes bearing the appellation Sātavāhana or Sātakani they presumably belong to the Andhra dynasty of the *Purāṇas*, and may be looked for in the lists of those works. Paṇḍit Bhagvānlāl, acting on this principle, identifies the first king of the Nānāghāt inscriptions with the thirteenth king of the *Matsya Purāṇa*, called Kuntalasvāti, and the second with the fourteenth of the same list, Svātikarṇa. In favour of the first conjecture he adduces the fact that Vātsyāyana's *Kāmasūtra* speaks of a Kuntalasvāmin-Śātakarṇi-Sātavāhana, and he thinks that probably Kuntalasvāmin was a second name of Sātavāhana. The name Svātikarṇa is, in his opinion, a corruption of Sātakarṇi. The basis of this identification is obviously very unsafe, and the Paṇḍit's conjecture becomes very improbable if it is borne in mind that the Nānāghāt inscription gives not merely Sātavāhana, but Simuka Sātavāhana as the name of the first king. I have already stated why I cannot accept Paṇḍit Bhagvānlāl's explanation of Simuka by *śṛtmukha*, “of glorious face,” and that Simuka probably is a part of the king's name, because the adjective *sirimāto*, “the illustrious one,” stands at the end of the inscription, and hence no other adjective of the same or similar import is required. But if Simuka is the proper name, it is not difficult to find in the lists of the *Purāṇas* the person named in the Nānāghāt inscription. Simuka-Sātavāhana is in all probability the first king of the list of the Andhra monarchs, whose name is never given alike in any two works, but according to three *Purāṇas* begins with a *si* or *śi*; according to two, contains in the second syllable the vowel *u*; and according to all, ends in *ka*. The *Vāyu Purāṇa* calls the founder of the Andhra dynasty Sindhuka, the *Matsya Purāṇa* Śisuka, the *Vishṇu Purāṇa* Śipraka and the *Brahmāṇḍa Purāṇa* Chhismaka.¹ Now this divergence of the authorities clearly proves that the name was one

¹ Wilson, *Vishṇup.* (ed. Hall, vol. iv, p. 194). Prof. Wilson's assertion that the *Bhāgavata* calls the founder of the Andhra dynasty *Balin* is a mistake. For the word *balī*, which occurs in the verse quoted, must be taken as an adjective, not as a proper name. The real name of the “powerful Sūdra servant of the Andhra race” has been left out. Wilford's assertion that the first Andhra is called Sūdraka in the *Kumārīkā Khanda* I doubt, for I have not found it in the copy which I have examined. But even if Wilford were right, the authority of the

which did not readily give any sense if taken as a Sanskrit name, but had a strange, un-Sanskritic form. Hence the copyists blundered badly, and correctors tried to make a Sanskrit word of the unmeaning syllables. To this desire we owe the form Kshipraka (lit., "the swift one"), which, according to Dr. F. E. Hall, occurs in some copies of the *Vishṇu Purāṇa*, the form Śīśuka (lit., "the infant"), and Sindhuka (lit., "born on the Indus." But patent as the fact is that the name of the first Andhra king is badly corrupted in all the *Purāṇas* which give it, there is not one form among those given which might be safely regarded as the original of the others, while it is not too much to say all that can be easily traced to misspellings of *Simuka* or *Śimuka*. The reading of the Vāyu, Sindhuka or Simdhuka goes back to Simuka, Śipraka, and Śīśuka to Śimuka, while Chhismaka, the reading of the *Brahmāṇḍa*, which still preserves the *ma*, owes its initial *chha* to a bad pronunciation of *śa*. Everybody who is conversant with Devanāgarī MSS. will know how common the graphical mistakes which I here impute to the scribes really are. As regards the two forms Śimuka and Simuka, they are for a Hindu, who, if he is not a grammarian, constantly exchanges these two sibilants, and especially before *i* and *e* in many districts always pronounces *ś* for *s*, perfectly identical. Similarly the forms Śātavāhana and Sātavāhana, Śātakarṇi and Sātakarṇi, Vaśiṣṭha and Vasishṭha, Śāṅkhāyana and Sāṅkhāyana frequently occur in the same work, and it is difficult to decide in such cases, except where the etymology is perfectly certain, which form is the original one. In the case of Simuka it is possible that the form with *s* is the older one, as the word might be derived by the affix *uka* (like *prithuka*, *ṛidhuka*, *kramuka*, &c.) from the rare root *syam*, which according to the grammarians means "to go," "to make a noise," and "to examine" or "consider." *Simuka* might thus mean like the familiar name *Rudra*, "the roarer." But it is also possible that the Prakrit Simuka is a strongly corrupted Apabhraṁśa or Deśī word. Be that as it may be, the identification of Simuka Śātavāhana with the Sindhuka, Śipraka, &c., of the *Purāṇas*, is not affected by the etymological question. But there are other facts connected with the statements of the inscriptions and of the *Purāṇas* which support the identification. First, if Simuka is the founder of the Andhra dynasty, the fact that he bears the second name Śātavāhana, agrees well with the fact that the inscriptions give Śātavāhana-kula "the race of Śātavāhana" as the family name of the Andhra kings. Secondly, according to the *Purāṇas*, the founder of the Andhra dynasty was succeeded by his brother Kṛishṇa (who appears in the Nāsik inscription No. 1 as Kaṇha), and the latter by his son Śātakarṇi or Śātakarṇi. The second king of our short inscriptions is the illustrious Śātakani. Now it happens not unfrequently in Indian inscriptions that the genealogy is not given completely, and even important members are left out.¹ Even supposing, therefore, that the Purāṇik account of the order in which the first three Andhras followed one another is correct, there is no obstacle in the usages observed in Hindu inscriptions that prevents us from taking Simuka Śātavāhana as the paternal uncle of Śātakani.

The third argument in favour of the view that these inscriptions belong to the earliest times of the Andhras is furnished by the alphabet. If we compare the characters of the

Kumdhrikā Khayḍa, which appears to be a compilation of the 14th or 15th century A.D. (see my notes, *Bombay Gazetteer*, "Cambay"), would be of no value. Elsewhere (see, e.g., *Ind. Stud.*, vol. xiv, p. 105) Śūdraka is called a minister of Śātavāhana.

¹ See *Ind. Ant.*, vol. vi, pp. 60, 184; and vii, 66, where in a grant of Guhasena of Valabhi the name of his father Dharapatta has been left out.

Nānāghāt inscriptions with those used by the later Andhra kings, Gautamīputra, Śātakarṇi I., and Puṣumāyi, at Nāsik and Kārle, the former show the following constant peculiarities, which consist in—(1) the absence of a thickening or small horizontal line or serif at the top of letters which begin with or consist of a vertical stroke, like *ka*, *pa*, *ra*, *va*, &c.; (2) the absence of curves in the lower portions of the letters *ka* and *ra*; (3) the roundness of the letters *pa*, *ya*, *la*, and *ha*, which in the later inscriptions are angular; (4) the form of the letter *da*, which consists of a small vertical top stroke, a deep irregular curve open to the left, and a small vertical stroke at the bottom, which latter, in the later inscriptions, has been changed to a horizontal stroke turned to the right; (5) the form of the letter *chha*, which consists of a circle divided by a long vertical line, while the later inscriptions show two small circles joined together, with a very short vertical over the junction or over the first circle; (6) the use of the symbol *su* for 100 instead of the symbol *śu*. All these peculiarities are archaic, because they agree with the oldest form of the Southern Indian alphabet, i.e., that which the Mauryas use. A number of other letters vary in their forms and sometimes agree with the Maurya characters, and sometimes with those of the later Andhras. In some cases we find other variations which are not traceable elsewhere; thus the initial *a* has the Maurya form in *apratihatachakasa* (No. I. l. 2), and in *aṃgiya* (No. I. l. 4), the later Andhra form in *aso* (No. I. l. 6) and *aso* (No. II. l. 1), and an unusual shape in *asaratho* (No. II. l. 1), *aṃgirasām* (No. II. l. 5), &c., where the two left hand strokes are curved upwards and downwards. Again, *va*, *cha*, and *ma* usually show the round Maurya forms, but the first is angular, e.g. in *devānam* (No. I. l. 1), in *variya* (beginning of No. I. l. 5), and in *devi* (No. IV.), the second has the later shape in *cha* (No. IV.), and the third is angular, e.g. in *dhammasa* (No. I. l. 1). Finally, the letters *ga* and *ta* usually agree with those of Puṣumāyi's inscriptions. But in *sagara* (No. I. l. 3), and still more in *aṃgira[tira]to* (No. II. l. 6), the *ga* has the angular form used by the Mauryas. The same remark applies to the *ta* of *satino* (No. I. l. 4), *dhamnāgiritāmsa* (No. II. l. 2), and a few other cases.

The inferences as to age drawn from these facts will be considered further on. For the present it will suffice to point out that, according to the epigraphical evidence, these documents may be placed a little but not much later than Aśoka's and Daśaratha's edicts. But what, in my opinion, most clearly proves that they belong to one of the first Andhras is that their graphic peculiarities fully agree with those of the Nāsik inscription (No. 1) of Kāṇha or Kṛishṇa's reign. In the latter we have the same forms of *da*, *ka*, *ja*, *ra*, *la*, *va* and *ha*, the same absence of the thickening or serifs at the top of the vertical strokes, and the same vacillation as to the form of *ta* and *ma*. This complete identity of the characters very strongly corroborates my view that the Śātakarṇi whose wife caused the Nānāghāt inscriptions to be incised is the Śātakarṇi whom the *Purāṇas* call the son of Kṛishṇa and the third Andhra king. In conclusion, I have to add two more remarks. First, I must repeat that I do not feel justified in trusting the assertion of the *Purāṇas* that the third king (Śātakarṇi) was the son of the second (Kṛishṇa). He may have been the son of the first and have come to rule only after the death of his uncle, for it is a very common occurrence in Indian history that an uncle assumes the government instead of a nephew who is a minor at his father's death. The fact that Kṛishṇa's name does not occur in the Nānāghāt inscriptions is not absolutely irreconcilable with the Purāṇik account, but it is more easily explained on the supposition that Śātakarṇi was Simuka Śātavāhana's son. A usurper would, of course, not be noticed. The Purāṇik accounts of the Andhras, moreover, as is

well known, are not very accurate, and their being mistaken on such a detail as the exact relationship of the rulers is very probable. Nevertheless, I prefer to leave the question open. Secondly, it might be objected to my theory that the name of the fourth Purāṇik king, Pūrṇotsanga, does not agree with that of Śātakani's son, who is called Vedisiri-Śātavāhana. One answer to this objection would be that the name Pūrṇotsanga is clearly a *Biruda*, and its bearer certainly had one or perhaps more other names. He may, therefore, be identical with our Vedisiri-Śātavāhana. The difficulty admits, however, of a very different solution. It is not impossible that, though Vedisiri-Śātavāhana was heir-apparent, he may never have come to rule at all. It must not be forgotten that the Purāṇik lists contain neither a Vedisiri nor a Śātavāhana, and the question if our "best of royal princes" ever ruled, or if he is hidden under the name Pūrṇotsanga, must for the present be left undecided.

As regards the third point,—the age of the Nānāghāt inscription and the chronological position of Simuka, Kapha, and Śātakani, I can here only indicate shortly my views,¹ which differ considerably from the chronological theories of Professor Wilson, as well as from those of Mr. Bhāu Dhājī and Paṇḍit Bhagvānlāl. I find it impossible to trust with Wilson to the statements of the *Purāṇas* regarding the order and duration of the Maurya, Śunga, Kāpāyana, and Andhra dynasties, and to fix the accession of Simuka-Śipraka, in 21 B.C., by the simple proceeding of adding the years of the first-named three dynasties, and deducting the total from 312, the year B.C. in which Chandraguptas' coronation is supposed to have taken place. This method is charmingly simple, but hardly in accordance with the canons of historical research. Its incorrectness is proved by the fact that it throws the reign of Puṣumāyi, whom Ptolemy in 150 A.D. mentions as a ruler of Baithana or Paithān, into the fourth century A.D. On the other hand, I am unable to agree with Mr. Bhāu Dhājī and Paṇḍit Bhagvānlāl that Gautamīputra Śātakarṇi I., who overthrew the Kshatrapa Nahapāna, must have done so between 124–135 A.D., because Nahapāna's latest date is Saṃvat 46, and this Saṃvat is the Śaka era. Nor can I assume with them that Ptolemy's dictum, "Baithana, the royal residence of Siri-Polemaios," must mean that Siri-Polemaios, whom they, following Lassen, rightly identify with Gautamīputra Śātakarṇi's son, Siri-Puṣumāyi, ruled at Paithān-Pratishthāna, at or shortly before the time when Ptolemy wrote, i.e., in 150 B.C. Least of all can I concede to Paṇḍit Bhagvānlāl that it is permissible, after upsetting the chronological system of the *Purāṇas*, to invoke their help for chronological purposes, and assume that the years which some of them allot to the various reigns have been correctly given, and to fix the dates of kings with the help of the Purāṇik figures. As regards Ptolemy's statement, it gives nothing else but an extreme limit beyond which the reign of Puṣumāyi-Polemaios cannot be placed. There are good reasons for believing that the two names denote the same person. But as we do not know from what source Ptolemy drew his information, and as a note like that which he gives would be equally correct both if Puṣumāyi lived a long time before the geographer, and if he were his contemporary,² it is not possible to make Ptolemy's assertion the starting-point of a chronological calculation. Further, as regards the *Purāṇas*, their

¹ I trust that I shall soon be able to treat the question more fully in a treatise "On the Royal Inscriptions of the Western Caves."

² Similarly a geographer of the present day describing Germany would be quite correct appending to the name *Berlin*, the note, "the capital of Frederic the Great," and a historian of future ages who would infer from this statement that Frederic the Great ruled in 1882, would make, as we all know, a serious blunder.

aim is to bring the history of India into the frame of the Yuga theory. For this purpose their authors have to pile dynasty on dynasty in order to fill a space of many thousand years. Historical research has shown that they possessed *some* reliable information not only as to names, but even as to years. In the case of the Andhra dynasty, the coins and inscriptions prove that the order in which the corrupt forms of the names Gautamīputra Sātakarṇi, Puṣumāyi, Sakasena (*Sirisena*) Mātharīputra, and Gautamīputra Yajñaśrī Sātakarṇi are given, is perfectly correct, as well as that Simuka, Kṛishṇa, and Sātakani reigned a considerable time before the former princes, and followed each other closely. But it by no means follows that all the other names or the order in which they are given are reliable. Nor is there any guarantee that the dynasty of Simuka-Śipraka ruled during about 450 years, much less that Simuka-Śipraka reigned 350 or 360 years before Gautamīputra Sātakarṇi I. All these points have to be proved. Though I think it right and necessary, therefore, to look to the *Purāṇas* for the kings mentioned in the inscriptions, I deny the possibility of making up a chronological account of the Andhras with their help. It seems to me that the only means for approximatively fixing the age of the group of kings—1. Simuka, 2. Kṛishṇa, 3. Sātakani—and of that containing 1. Gotamīputa Sātakarṇi, 2. Puṣumāyi, 3. Sakasena Mātharīputa, 4. Gotamīputa Siriyāṇa Sātakarṇi and 5. Chandasiri, are epigraphic evidence, and the synchronisms with the Western Kshatrapas, who date according to an era, not according to regnal years. The synchronisms which the inscriptions and ruins allow us to establish are: 1. Gotamīputa Sātakarṇi was a contemporary of Nahapāna. 2. Puṣumāyi was a contemporary of Chashtana. 3. Gotamīputa Siriyāṇa Sātakarṇi was a contemporary of Rudradāman,¹ whose reign fell between 72 and 101 of the era used by the Western Kshatrapas. The initial point of the latter era can be determined approximatively by the following process. The Kshatrapas ruled over Mālava, Eastern Rājputānā, and Gujārāt. Their power was destroyed by their immediate successors the Guptas, whose first date in Mālavā is the Gupta year 83, while the latest date on the coins of the Kshatrapas is Sam 310.² These two dates must, therefore, nearly correspond. The Gupta era began about 190 A.D.,³ and the Gupta year 83 to circiter 273 A.D. Hence the beginning of the Kshatrapa era falls about the middle of the first century B.C., and the reign of Gotamīputa Sātakarṇi I, who destroyed Nahapāna's power, a little earlier. In order to determine the date of the group Simuka, Kaṇha, Sātakani, nothing but the epigraphic evidence is available. It seems to me that a comparison of the characters of Kaṇha's and of the Nānāghāt inscriptions with those on the coins of the earlier Śunga kings, as well as of Dhanabhūti's inscription on the Bharahut gateway, which, owing to its beginning *suganam raje*, i.e. *Śungānām rājye*, "In the reign of the Śungas," must be counted among the documents of Pushyamitra's successors, incontestably proves that the Nānāghāt and Kaṇha's Nāsik inscriptions belong to the first half of the second century B.C., i.e. were incised between 200–150 B.C. It agrees with this estimate that the differences between the characters of Gotamīputa Sātakarṇi's and those of the Nānāghāt documents are such that it is not possible to place them, as Paṇḍit Bhagvānlāl has also seen, at a distance of more than about 100 years.

¹ The latter assertion becomes particularly probable by Campbell and Bhagvānlāl's discovery of a coin of Sātakarṇi designed on the model of the Kshatrapa coins.

² General Cunningham's unpublished coin.

³ This date is now substantiated by Sir E. C. Bayley's discoveries of Gupta dates on the Kabul coins and other epigraphic evidence.

It now remains to notice the importance of the large inscription for the history of religion and civilisation in India. First, it proves more clearly what indeed may be inferred from the names of some Andhra kings, *e.g.* from Siriyaña or Yajñaśrī and from the Nāsik inscription No. 14, that this family from the beginning to the end adhered to the Brahmanical faith, and, though willing to support Bauddha mendicants by liberal gifts, did not follow their heretical teachings. This fact, to which I have pointed already in my introduction to *Āpastamba (Sacred Books of the East, vol. ii, p. xxxvi)*, taken together with the other fact that Southern India produced a number of ancient schools of the *Taittiriya Veda* and of the *Sāmaveda*, some of which seem to have had their home in the Andhra country, disposes of the view frequently advanced that the non-Aryan races of Southern India owe their civilisation to Buddhism and Jainism, and that Brahmanism is, in Southern India, a modern interloper. Secondly, the second part of the large inscription shows that the assertion made in the school-books of the Brāhmans regarding the costliness of the great Vedic or Śrauta sacrifices are not exaggerated, and that the so-called *Dānastutis*, occurring in the *Rigveda*, name comparatively speaking small largesses which the Rishis received from their royal patrons. Thirdly, the invocation *namo Saṁkarsana-Vāsudevānam Chāṁdasūtānam mahimāvatānam*, "adoration to the two descendants of the Moon, Saṁkarshana and Vāsudeva, who are endowed with majesty," furnishes an important addition to the materials proving the early prevalence of the worship of Kṛishṇa and his family in other countries than the Doab, where the Greeks already found the club-bearing Kṛishṇa-Vishṇu installed as the tutelary deity.

II. KAṆHERI INSCRIPTIONS.

32
-15
17

The first fifteen inscriptions, given below, have been read according to the facsimiles on pl. li. For the following ones I have used Dr. West's *eye-copies* (*Jour. Bo. Br. Roy. As. Soc.*, vol. vi, pp. 1-14) and some unpublished materials. A portion of the Kaṇheri inscriptions has been translated by Dr. Stevenson in his usual style (*loc. cit.* vol. v, p. 1 *seqq.*)

No. 1 (West's No. 1) beneath a standing figure of Buddha, in a recess behind the dāgobā Cave No. II.—

1. Nannavaidya-
2. rāṇo
3. Bhāskarah ,
4. Bhāraviḥ
5. Chelladeva
6. Boppai
7. Bhaṭṭa Khasu avvai po-
8. hoī []

The inscription, which shows some Sanskrit nominatives, and ends with two Prakrit words, seems to record merely the names of some Brahmins who visited the cave, viz., *Nanna*, *i.e.*, *Nānā*, a physician; *Bhāskar*, *Bhāravi*, *Chelladeva*, *Boppai*, *i.e.*, *Vopadeva*, and a priest or Bhaṭṭji, whose name may be read *Khasu* or *Besu*. The concluding two Prakrit words are not quite clear to me, but it seems likely that their meaning is equivalent to the Jaina phrase *nityam praṇamati*, which is often read on votive statues. *Arva-i* might stand for Sanskrit *avyayam*, or *avyaye*. Alphabet, Western type of the fourth or fifth century.

(West's No. 2)

No. 2, on the back wall of Cave II.¹ above a bench—

1. Nāsikakasa Nāka-
2. nakasa sata deyadhama [||]

—"A seat, the meritorious gift of Nāganaka (Nākanaka), (*an inhabitant*), of Nāsik."

The word *sata* is probably a corruption of Sanskrit *sadaḥ*. Language, Pālī; characters, Andhra type of the time of Puṣumāyi, or a little earlier.

(West's No. 3)

No. 3, in the same cave, near a tank—

1. Kaliyana[nā] suvaṇako[kā]rasa Samida-
2. tasa saha sagha[gha]na paṇi[ya]ka deyadhama [||]

—"A cistern (?), the meritorious gift of the goldsmith Samidata (Svāmidatta), of Kalyāṇa (*associated*) with the community (*of ascetics and lay-brethren*)."

Dr. West's facsimile reads plainly *Kalimyanā* (ablat.) which is required, and *saghāne*, i.e. *saghena* or *saghenā*. Language, Pālī; Letters, Andhra; Date, about or shortly after Puṣumāyi's time.

(West's No. 4)

No. 4, on the right-hand gate-post of the Chaitya cave (No. III.)—

1. Raño Gotam[i]putasa Sāmi-Siriyaṇasa]
2. Sotakamissa [sathavachare gi]²
3. mahapakhe patichame [5 divase]
4. vāṇijakehi utā(?)]³
5. naya upaṇnehi gā[.]
6. khātiyehi bhātū[hi]
7. Gajasenena Gajami[tena]
8. kapathāyi cheti[ya]
9. āchariyānaṁ nikā[yasa Bhādāya]
10. nīyānaṁ parigahe pa[tiṭṭhāpitaṁ mā]
11. tapitānaṁ abhatitā[naṁ]]
12. pūjāya kuṭumbini[na bāla]kānaṁ bāli[kānaṁ]
13. savatasa⁴ bhāgineyāna nikā[ā]yasa nāti]
14. vagasa cha aga paṭiasiya savvasa[tānaṁ]
15. hitasukhāya hetu [|] etha cha nava . .]
16. kā pavajito therā bhadata-Achalā bhādara[ta-]
17. Gahalā bhadata-Vijayamitā bhadata-Bo[dhiko]
18. bhadata-Dhamapālā upāsako cha negamo A[nada-]
19. puto Aparesuko samāpitā[|] āchari[y]āna therānaṁ
20. bhadata-Soumlānaṁ sisena uparakhitana bha⁵
21. data Bodhikena kata selavaḍhakhihi [nāya]kami-
22. sehi kadhichak[e]hi mahākata[e]hi khadara-
23. kinā cha mīthikenā [||]

("On the . . . day) of the fifth fortnight of the hot season (*of the . . . year*) of the king, the son of the Gautamī queen (*the lord Siriyaṇa*) Sātakarṇi. By the merchants, born of . . nu, the *khātiya* brothers Gajasena, Gajamitra (*was erected*) a *chaitya* which will endure until the end of the *kalpa*,

¹ See *ante*, vol. iv, p. 63.² Read *Sātakamissa*.³ Possibly *mha* is to be read.⁴ Possibly *seva* . *tasa* to be read.⁵ Read *uparakhitana*; *bha* looks like *su*.

in honour of their deceased parents and, after securing a most excellent share (of the merit) for their wives, sons, daughters, stepbrother, the crowd of their sister's sons, and the multitude (of their blood relations, also) for the well-being and happiness of all sentient creatures. And an ascetic, the *Thera*, the reverend Achala, the reverend Gahala, the reverend Vijayamitra, the reverend Bodhika, the reverend Dharmapāla and the lay worshipper, the merchant Aparenuka, the son of Ānanda, have completed (this) new (?) . . . here. (The work has been) executed by the reverend Bodhika, the pupil of the teacher (and) *Thera*, the reverend *Seṣmīla*, (who acted as) overseer, together with the stonemasons and with the polisher *Skandarakī* (Khadaraki)."

Regarding the state of the inscription and the causes of its mutilation, see Dr. West, *loc. cit.* The restoration [*Bhādāya*]nityānam (l. 9) is supported by No. 37, (West) l. 2. The wording of the latter inscription must be compared for the next phrases of our inscription (l. 10-15). At the end of line 13 *mīta* or *bandhu* may also be thought of. It is difficult to offer a plausible conjecture for the restoration of the end of line 15. I think of *nava-karmamān*, which must have been followed by the name of the *pavajito*, the last syllable of whose name *kā* (read *ko*) is preserved in l. 16. It seems to me that the Kanheri Chaitya was begun by the merchants Gajasena, Gajamita, &c., and finished by the persons named in l. 15-19. The name *Anada* (l. 18) may be restored according to No. 15 (West, 44—l. 3, 4), where the names of Aparenuka's relatives are given in full. For the active meaning of *samāpitā* "have completed," compare *paṭiṭhāpita* "has erected" in the Jaggayyapetta inscriptions (*Ind. Ant.*, vol. xi, p. 256). *Seṣmīla* is a curious name, but may stand for *Śaivala*. Ll. 22, 23 contain several difficult words which apparently denote various artisans. The modern Gujarāṭi *kaḍḍiyo*, "bricklayer," may be compared with *kadhichaka*.

(West No. 5)

No. 5, on the left-hand gate-post of the Chaitya cave (No. III.)—

1. khabhālakaresu adha-
2. a[ka .]ch[e]tiasa bha-
3. lakārasa . [pa]vayitāna ya
4. . . akhaya nivī [da]tā Soparakāhāre hā-
5. . . [ti]ni 3 Kāliya Abālikāvihāre cheti-
6. . . upathānasāl[ā] ovarakāni Paṭiṭhāne vihā
7. . . ṭigupasadari[ya] chetiaghara ovarakā terasa
8. . sa-akhayanivikā [R]ājatalāka-Paṭhānapathe
9. . saṇa chulika . ya kuṭi koṭhi cha choṇitā sada-
10. sevājuya [vihā]re saghārāmo sa-akhayaniviko k[ā]
11. rāpito pu[ṣa]ṭha deyadhamāni cha anāni pi [kāri]tāni []

This inscription appears to record, besides a benefaction at Kanheri, various meritorious gifts which the donor bestowed at other places on the Bauddha monks. The fragments permit us to recognise the following details:—1. Some addition seems to have been made to the Chaitya at Kanheri (l. 2). 2. A perpetual endowment, the purpose and nature of which have been lost, was given (l. 3). 3. In the Zilla of Sūpārā (Soparakāhāre) three (possibly cells) were added to some building (l. 4, 5). 4. In the Ambālikāvihāra situated at Kalyāṇa (Kalliene in the Konkan), a *Chaitya*, a hall of reception (*upathānasālā*) and cells for the monks (*ovaraka*) were built (l. 5, 6). 5. At Paṭhān (Paṭiṭhāne) a *Chaitya-griha* and thirteen cells for the monks (*ovarakā terasa*) together with a perpetual endowment (*sa-akhayanivikā*) were given (l. 6, 8). 6. In the *pargana* or *tāluka* of Paṭhān,

called Rājatalāka (?), a small temple (*kuṭī*) and a hall (*koḍhī*) were erected¹ at the vilāra of Sevāju (?), (l. 8-10). 7. A monastery (saghārāmo) was built (*kārāpito*) and endowed with a perpetual grant (*sa-akhayaniviko*). These and other meritorious gifts were made, as the donor adds, for his own benefit (*pu[ṇa]ṭha*). Alphabet, Andhra type of the time after Puṣumāyi.

(wests no. 6)
No. 6, under a figure of Buddha in the verandah of the Chaitya Cave (No. III).—

1. Buddhasya bhagavataś śāsanānukāritraipitakopāddhyāya-
2. bhādanta-Dharmavatsa-śiṣhyasya bhikṣhor Buddhaghoshasya
3. mahāgandhakuṭivārikasya Bhagavat-pratimeyam deyadharmmaḥ []

Sākya

—“This image of Bhagavat, (*Buddha*, is) the meritorious gift of the ascetic Buddhaghosha, the guardian of the great *gandhakuṭī*, and pupil of the reverend Dharmavatsa, a teacher of the three *Pitakas*, who follows the religion of divine Buddha.”

The reading *vārikasya* (see, however, the *Pet. Dict.*, sub. voce *nāgavārika*) is not absolutely certain. It may be *chārika*, and be translated “who undertook a pilgrimage to the great *gandhakuṭī*.” By the latter term, as the position of the inscription shows, the great Chaitya is meant. Language, Sanskrit; letters, Western alphabet of the fourth or fifth century A.D.

(wests no. 7)
No. 7, under another figure of Buddha² in the verandah of Cave No. III.—

Deyadharmmayam Sākya-bhikṣho[r] Dharmmaguptasya []

—“This (*is*) the meritorious gift of the Buddha ascetic Dharmagupta.”

Letters and language as those of the preceding.

(wests no. 8)
No. 8, on a small bas-relief dāgoba in the verandah of Cave No. III.—

Ye dharmmaḥ hetuprabhavā teshā[. . .].

The beginning of the Buddhist creed. Language and letters as those of No. 6.

(wests no. 9)
No. 9, inside a small chamber to the left of the entrance of the Chaitya Cave (No. III).—

1. Deyadha-
2. rmmoyam ā-
3. chāryya-
4. Buddhara-
5. kṣhitasya []
6. anena
7. sarvvasa-
8. tvā Buddhā
- bhavantu []

—“This (*is*) the meritorious gift of the teacher Buddharakshita. May all living beings thereby become Buddhas.”

Letters and language as those of No. 6.

¹ *Chōpitā*, compare Gujarātī *chāyavāṇ*, “to build.”

² See vol. iv, p. 61.

(West's No. 10)
No. 10, in the small chamber, No IV. (West), just north of the Chaitya Cave¹—

1. Sidham heranikasa Dhamanakasa bhayā-a
2. Sivapālitanikāya deyadharmā
3. therāna bhayata-Dhammapālāna
4. thuba [||]

—“Success! The stûpa of the Thera, the reverend Dhammapāla (Dharmapāla), the meritorious gift of Śivapālitanikā, the wife of the goldsmith Dhamanaka (Dharma).”

West's No. 10. Mr. West's facsimile reads plainly *bhayāa*, i.e., *bhayāya*, while Pandit Bhagvānlāl's omits the final *a*. Date of the inscription, the interval between Puṣumāyi and Gotamiputa Siri-Yaśa Sātakaṁni II.

(West's No. 11)
No. 11, in a recess over the tank, No. V. (West) on the path up the hill—

1. [Vā]śiṣṭh[i]putrasya śrī-Sāta[karp]i[s]ya devyā[h] Kārdamakarājavanisāpra[bha]v[ā]y[ā] mahā-
kshatra[pa] Ru . [p]utry[āh] . . .
2. śya . . . v[i]śvasyasya amātyasya Saterakasya pāniyabhājanam deyadharm[m]a[h] ||

—“Of the queen . . . of the illustrious Sātakaṁni Vāśiṣṭhīputra, descended from the race of Kārdamaka kings, (and) daughter of the Mahākshatrapa Ru(*dra*) . . . of the confidential minister Sateraka, a water-cistern, the meritorious gift.”

As the connection between the royal lady, mentioned in l. 1, and the minister in l. 2, is not clear, I can do no more than translate the remaining words literally. It seems, however, probable that the minister executed the work at the command of the queen. Language, Sanskrit; alphabet, Western Kshatrapa type of the times of Rudradāman I. *Kārdamaka* probably means “of (the town or country of) *Kardama*.” A locality called *Kardamila* is mentioned in the *Mahābhārata*, see the *Petb. Dict.*, s. voce. For further historical combinations see *Ind. Ant.* xii, “On the relationship between the *Andhras* and the *Kshatrapas*.”

(West's No. 12)
No. 12, above a tank with two openings to the left of Cave No. VII.—

1. Sopāragā negama-
2. sa Samikupāsaka-
3. sa poḍhi deyadhama [||]

—“A cistern, the meritorious gift of the lay-worshipper Samika [Śramika?, Svāmika?], a merchant of Supārā [Sopāraka].”

Language, Pālī; letters, Andhra type of the time of Gotamiputa Sātakaṁni I. or Puṣumāyi.

(West's No. 13)
No. 13, close to the preceding—

1. Chemulakasa heranikasa
2. Rohiṇimitasa putasa
3. Sulasadatasa poḍhi
4. deyadharmā [||]

—“A cistern, the meritorious gift of Sulasadatta, son of the goldsmith Rohiṇi-mitra of Chemula” (Simylla, Cheṇval, or Chaul).

¹ See vol. iv, p. 63.

⁴ Language, Pali. Letters, Andhra. Date, the period between Sātakani of the Nānāghāt and Gotamiputa Sātakani I., as is shown by the archaic form of the letter *da* and the prevalence of round strokes in *sa*, *pa*, *ha*, and *ya*.

No. 14 (West's No. 19), outside the verandah of Cave No. XXXVI.—

1. Sidham raño Ma[Mā]dhariputasa Svāmi-Sakasena
2. savachhare 8 gi pa 5 diva 10 etāya puvāya ka-
3. liyānakasa nekamasa Venhunandisa pātasa nega-
4. masa gahapatisa . . . tisa l[e]ṇa pa[tī]thāpi-
5. ta sahā āyyak[e]ṇa . . . sena sahā pitu[nā] Venhuna-
6. dinā sahā mātuye Bodhisamāya sahā bhā-
7. [tunā . . .] hathinā sahā [sa]vena [n]i[kāyenetī]

—"Success! On the tenth day of the fifth fortnight of the hot season, in the eighth year of the king, the lord Śakasena, the son of the queen of the Māṭhara (Mādhara) race. On the above (day) the merchant and householder . . . ti, the son of the merchant Viṣṇunandin (Venhunandi), an inhabitant of Kalyāṇa, made a cave, (*he being associated*) with the venerable . . . , with his father Viṣṇunandin, with his mother Bhadhisamā, with his brother . . . hastin (hathi), and with the whole multitude (*of his relatives*)."

Sakasena appears plainly on Mr. West's eye copy, while on Dr. Burgess's facsimile it looks like *Sikasena*. Bhagvānlāl's emendation (*Jour. Bom. Br. R. As. Soc.*, vol. xii, p. 408) *Sirisena* requires confirmation. According to Bhagvānlāl's facsimile the name of the donor ends in *ta*, according to Dr. Burgess's in *ti* (*Śivabhāti*?). Regarding the place which Mādhariputa Sakasena holds among the Andhra kings, see Bhagvānlāl's remarks, *loc. cit.*, and vol. xiii, pp. 306, 307.

No. 15 (West's No. 44), on the left-hand side wall outside the verandah of Cave No. LXXXI.¹—

1. Sidham ||
2. Raño Gotamiputasa Sāmi-Siriyaña-Sātakaniṣa sata[va]chhare 16 gi.²
3. mh[ā]ṇa pakha 1(?) divase 5 Kālayāṇavāthavasa negamasa Aṇa-
4. dāputasa usā[pā]sakasa Apareṇusa sa[pa]rivārasa sahā
5. kuḍubiniya Ānadamātu Ju(?)vāriṇik[ā]ya sahā bālakena Aṇadeṇa
6. saha cha suṇh[ā]hi Aṇa . . . la . . . sipecha(?) dhāmadev[i]ya
7. saha [cha] . . . veṇa Ahavi(?) aṇa āmāpitāro udisa.³
8. pāva[te] Kāphasele leṇam koḍhi cha deyadhāma[n] chātudise
9. bhikkhusaghe paṭiṭhāpita sāvasat[ā]ṇam hitasughatha [||]
10. etasa cha akhayanivi datā kāhāpāṇ[i] satāni be 200
11. saghasa yeva haṭhe paṭike sate eṭha cha āhapaṇa-
12. khetiyasa kheta gāme Magalathāne bhojā kapati eto
13. saṅgheṇa dātavaṇ chivarika soḷasaka paḷiko cha māse utukāle [||]

—"Success! On the 5th day of the 1st (?) fortnight of the hot season, in the year 16 of the king, the son of the queen of the Gautama (*race*), the lord Siriyaña Sātakani. The lay-worshipper Apareṇu, the son of Ānanda (Aṇada), a merchant residing in Kalyāṇa,

¹ See *Arch. Report*, vol. iv, p. 70.

² L. 2. Possibly Siriyaña; the last *sa* of Sātakaniṣa stands below the line.

³ L. 7. The letters in the middle of the line are very indistinct and uncertain; perhaps *puhaviṇeṇa* or *aleṇa* to be read.

has excavated, together with (*his*) family, (*viz.*) together with (*his*) wife Juvārinikā (?), the mother of Ānanda (Anāḍa), together with his son Ānanda (Anāda) and together with his daughters-in-law, (*the wives of*) Ānanda Dharmadevī (Dhāmadevī) and together with a cave and a hall, in the mountain, the hill of Kṛṣṇa (Kaṇhasela) for the community of the ascetics from the four quarters of the horizon (*to be*) a meritorious gift for the benefit of his own parents, and for the welfare and happiness of all living beings.

"And he has given a permanent endowment (*of*) two hundred *kārshāpaṇas*, 200, even into the hand of the community, two hundred bearing (*a monthly interest of*) one *kārshāpaṇa*. And here the field of the *half-paṇa*-owner, in the village of Maṅgalasthāna (*Maḡalasthāna*) may be enjoyed. Out of (*the interest and the revenue of*) that the community shall give 'a piece of sixteen' for clothing and in the season the value of one *kārshāpaṇa* a month."

The date of the inscription proves that the figure 19 or 20, which some copies of the Purāṇas give for the duration of Yajñaśrī's reign, comes nearer the truth than Professor Wilson's statement that he ruled nine years only. The endowments appear to be two—(1) a principal of two hundred *kārshāpaṇas*, bearing one per cent a month (see *Arch. Rep.*, vol. iv, p. 102, No. 9), and (2) half a share of the produce of a field at Maṅgalasthāna, the modern Maḡthān, which lies in the neighbourhood of the caves (*Jour. Bom. Br. R. As. Soc.*, vol. vi, p. 13). I take *ādhapaṇa-khetiyasa*, which, as this inscription invariably lengthens a short *a* after which an *r* has been elided, stands for *ardhapāṇakshetṛiyasya*, in the same sense as the modern Indian an eight-Āṇā or half-rūpī, owner. These phrases are used to denote a person who possesses a right to half a share in a property. I assume that Apareṇu possessed the field in question, together with an unnamed co-partner, and made over his share of the produce for religious purposes. I intentionally translate *saṅgha* by "the community," and understand thereby the whole Bauddha community of Kalyāṇa, not the ascetics alone. *Saṅgha* seems to have in this case the same meaning in which the Jainas invariably used and still use it, *viz.* the community of the faithful, both lay and cleric.

No. 16 (West's No. 16) on the left-hand side-wall outside the verandah of Cave No. XII.—

1. S[i]dha[m] Kāliya[nā] . . sa . . . ṇa S[i]vāmitasa putasa nega-
2. masa Dhama Budhakema saha cha saveṇa parivā-
3. rena bavā (?) . . . la[ya]nām pāpiyapoḍhi āṣaṇapeḍhikā-
4. yo piḍho a . . . cha kamo cha deyaḍhama chātudise bhikkhusaghe pa-
5. tiṭhāpita mā[tā]pitara udisa savasatuhitasughatha []
6. eṭha cha akhayanivī cha datā []
7. eto cha vāsārate vasatasa bhikkhuo chivarikakāhāpaṇā solasa pāte l[e]¹
8. sa upāhāṇa² cha kāhāpaṇo utukāle [cha] paḍiko māse vasatasa dā-
9. tavo sesena leṇa paḍiagitava [] Kāliyaṇe cha viḥāre Gaṇḍhārikābhami-
10. ya[m] bagabham bhojanachātusāla cha deyaḍhamma [] etesi pi akhā³ nivī datā Mukuḍasiva-
11. yi [vā]yam nivesanaṃ [] eto be bhāka bigabhasa bhāka chātusāla viḥāra dasakāni chivari⁴
12. kāni chātusāla cha [bhāka]⁵

¹ L. 7. For the last sign, *le*, the vowel is indistinct.

² L. 8. The *ṇa* of *upāhāṇa* stands below the line.

³ L. 10. *I.e.* *akhayā*.

⁴ L. 11. Possibly *yithāyam*. Read *viḥāre*.

⁵ L. 12. The last two signs are indistinct, and one might read *chataka* [*chatushka*].

—“Success! . . . a cave, a water-cistern, benches for sitting on, a chair, a and a flight of stairs (?), have been erected for the community of monks from the four quarters of the horizon (as) the meritorious gift of the merchant Dharma . . . , the son of Sivamitra an inhabitant of Kalyāṇa (he being associated with) Buddhaka and with his whole family, in honour of his parents, and for the welfare and happiness of all living beings. And a permanent endowment has been given there. And out of (the interest of) that, sixteen *kārshāpaṇas* are to be given (to defray the expense) for clothes to the ascetic who resides (in the cave) during the rainy season, some trifle for (his) almsbowl, and one *kārshāpaṇa* for (his) shoes, and in the season (the value) of one *kārshāpaṇa* a month to him who dwells (there). With the remainder the cave is to be kept in repair. And in the monastery at Kalyāṇa, in the Gandhārikā-bhamī, a (house) with two apartments and a quadrangular dining-hall (have been built as) a meritorious gift. A perpetual endowment has been given for these also (viz.), a dwelling-house in the *Mukūḍasivayivā*. Out of (the rent of) that two shares (are to be spent) on the house with two apartments, (three) shares on the quadrangular hall, ten (shares) are (to be given to the ascetics) in the monastery for clothes, and one share (to those) in the quadrangular hall.”

The exact meaning of *utukāle paḍiko māse vasatasa dātavo* is not quite clear to me. Possibly food of the value of one *kārshāpaṇa* is meant. *Paḍiagītava* is the fut. part. pass. of a denominative, derived from Sanskrit *pratyāṅga*, Pali *pachchaṅga*. *Gandhārikā-bhamī* is apparently the name of a ward or street of Kalyāṇa (Kalliene in the Konkana), and *bhamī* is probably derived from the Sanskrit *bhrami*, “circle, arrangement of troops in a circle,” &c. In the present day the Anglo-Indian equivalent would be “the *Kābūli Bazar*.” *Mukūḍasivayivā* or *yīthā* is, of course, likewise the name of a ward of the town. No numeral is appended to the second *bhākā* (*bhāgāḥ*); hence the plural has to be taken in its original sense of “three.” The total of the shares amounts to sixteen, and this shows that the now usual division according to *Āṇa*-shares (16 *Āṇas*=1 *Rūpi*) is exceedingly old.

The alphabet of the inscription is of the Andhra type, of the times of Gotamiputa Siri-Yaśa-Sātakaṇiṇi.

After *datā* (l. 6) a large blank space of one and a half lines has been left. Probably it was intended to insert the nature of the first-mentioned perpetual endowment.

No. 17 (West's No. 17) on the left-hand side-wall of the porch of Cave No. XIX.—

1. Sidham āchariā[na] bhayātā[rāna] bhātuno pavajitasa Āṇadasa
2. lepa deyadhamam saghe [] akhayanivi dīnā [] eto chivarikam dāta-
3. va chhaka . nam saha savehi nātihi []

—“Success! A cave, the meritorious gift of the ascetic Ānanda (Āṇada), the brother of the teacher, the reverend (Antara?), for the community of ascetics. A permanent endowment has been given. Out of (the interest of) that (the expense) for clothes is to be given to (the ascetics). (The giver is associated) with all his blood-relations.”

Letters, Andhra type, about the time of Gotamiputa Siri-Yaśa-Sātakaṇiṇi. The name of the reverend teacher has been given according to Dr. West's copy.

No. 18 (West's No. 18) on the inner wall of the verandah of Cave No. XXIX.—

1. Sidham Kalyāṇakasa negamasa Golāṇakaputasa negamasa Isipālaka
2. saparivārasa mātāpīṭunam

3. puyatha leṇa poḍhi cha deyaḍhaṇṭhi-
4. ma || akhayanivi cha dinā gāme
5. Saphāsu kheta thapati [] eto
6. cha vasa-uthasa chivarika bārasaka
7. gimhāsu paḍiko māse sesaṇa
8. maṭape pavāḍe cha paḍiagitava []

—“Success! A cave and a cistern, the meritorious gifts of the merchant Rishipāla (Isipāla) (*who is associated*) with his family, the son of the merchant Golanaka, an inhabitant of Kalyāṇa, in honour of his parents.—A perpetual endowment has been given (*viz.*) a field in the village of Saphāu And out of (*the rent of*) that ‘a piece of twelve’ (*shall be given to the ascetic*) who keeps the *vasso* (*to defray the expense*) for clothes, in the hot season the value of one *kārshāpaṇa* (*each*) month; with the remainder the minor repairs shall be done in the Maṇḍapa and the Pravāḍa.”

Alphabet, Andhra type of, or shortly after the time of Gotamiputa Siri-Yaṇa-Sātakaṃṇi.—The feminine plural *gimhāsu*, *i.e.*, *grīshmāsu*, probably caused by the analogy of *varshāsu*, is unusual. *Maṭapa*, *i.e.*, *maṇḍapa*, seems to denote the cave. *Pavāḍa*, *i.e.*, *S. pravāḍa* or *prabāla*, “a young sprout, or a coral,” must have here a technical meaning. A line of small letters, incised under the first ten *aksharas* of line 1, which seems to have been a postscript, is illegible in the facsimiles.

No. 19 (West's No. 20) outside the verandah of Cave No. XXXVI.—

1. Sadha ra . Ma[dhariputasa Svāmi-Sakase-
2. [nasa [di]vā 10 etāyi (?)
3. vāṭhaveya Veṇhunadiputra-
4. [sa] sa bhajāya Hālanikā le-
5. [ṇa patiṭhāpita sa]hā āyyakena Lā . . . sa
6. Dhāmāye
7. Buddhakayena sahā vi

This inscription, which is found in the same cave as No. 14, apparently records the gift of the second room attached to the larger one, by the wife of the donor mentioned in the preceding inscription, the son of Veṇhunamdi or Viṣṇunandin. It seems to have been incised on the same day as No. 14, as the remaining letters show that the king was the same Mādhariputa Sakasena. Though Dr. West has *Sara*, I think the last three signs of line 1 of the facsimile point to *Sakase*. In line 3, Dr. West has *vāṭhaveya*; the correct reading is probably *vāṭhavasa*, “an inhabitant” (*of Kalyāṇa*), as in No. 14.

No. 20 (West's No. 23) on the back wall of the open gallery No. XXXIX.—

[Siddhant Sop]ārayakasa manikarasa Nāgapālita saparivārasa leṇa deyaḍhama []

—“Success! A cave, the meritorious gift of Nāgapālita, a jeweller from Śorpāraka (*who is associated*) with his family.”

For the form *Sopārayakasa* compare Nānāghāt, inscription No. IX. The transcript has been made with the help of Dr. West's facsimile. Alphabet, Andhra type, about the time of Puṣumāyi.

1. Sidha therāṇa bhayaṇṭa-Ghos[ā]ṇa atevāsiniye
2. pavattikā P[o]ṇaklasaṇā theriya leṇa
3. . . . pāṇiyapodhi cha deyaḍhama saha bhagi-
4. niya saha cha . . . samaṇapapaakehi chātu-
5. diṣe bhikhusaghe patithāpitā mā[tāpitare udi]
6. sa [] akhaya nivi cha saghaṣa diṇā kāhāṇa satāni be []
7. eto chīarika solasaka paḍiko māse cha utukāle sava-
8. l[o]kahitasughatha []

No. 22 (West's No. 25) on the left-hand side-wall outside the verandah of Cave No. XLVIII.¹—

1. . . . thoṇakā[na] [therā]ṇa[bha]yata-Hā[la]kāpa ma
2. . . . tisa Kāṇhasa deydhaman leṇam p[o]dh[i] k[o]dhi [cha]
3. [pa]tiñhāpitā [] akhya nivi cha dinā kāhūpanāṇa
4. . . . satā sa[ghe] eto cha bhikkhusagho chevarika dātava bārasa-
5. [ka] sa savalokahitasukkhāya ti []

The importance of the inscription consists in the name Kaṇha, Kṛṣṇa, which furnishes another proof for the worship of Kṛṣṇa in the Koṇkan,² and in the form *che-varika* (Sanskrit, *chavirika*), which proves more clearly than the usual *chivarika* that "for clothes," not "cloth," is the meaning of the word. Alphabet as in the preceding inscription.

1. Sīdhaṃ theṛānaṃ bhayata-Mitabhūtinam
2 leṇaṃ sāgarapaloganānaṃ devadhamaṃ []

² See vol. iv, p. 9.

Dr. West's copy shows only *nam* in the difficult word *sāgarapaloganānam*, while the unpublished one has above the line *nā* and below the line *na* and an *anusvāra* above the line. It is possible that the mason wished to remove the *nā* and to substitute *nam*. If that is the case, and the whole has to be read *sāgarapaloganam*, the latter might be taken as a genitive plural, and the whole be translated "of the people who protect the ocean," i.e. either "of a community of traders by sea," or "of an admiralty-board." The reading *sāgarapaloganānam* would be equivalent to Sanskrit for *sāgarapralokanānam* "of those looking after the ocean." Alphabet, Andhra type of Puṣumāyi's time or a little later. The *t* shows the form which is constantly used in the Kuṭā inscriptions.

No. 24 (West's No. 32), in a recess over the tank in Cave No. LIX.¹

1. [Siddham Kālījanikāya Bhoḡgiyā A-
2. [pa]rāntikāya Dāmīlāya leṇa
3. [po]dhi cha Kaṇhasele deyaḍhamam [||]

—"Success! A cave and a cistern on the hill of Kṛishṇa, the meritorious gift of Dāmīlā, Bhojiki of the Koṇkaṇ (Aparānta), an inhabitant of Kalyāṇa.

This inscription has been restored according to Dr. Stevenson's transcript, whose Paṇḍit, as Dr. West states, destroyed the beginning of the lines. The epithets *Bhoḡgiyā*, *Āparāntikāya*, of course, mean that the husband of Dāmīlā was Bhojaka, i.e. the ruler, of the Koṇkaṇ. Alphabet, Andhra type, earlier than the inscriptions of Gotamiputa Sātakaṃṇi I.

No. 25 (West's No. 33), on the inner wall of the verandah of Cave No. LIX.—

1. Siddham Kālīyiniṇikiya bhikhuṇiṇi Dāmīlāya leṇa deyaḍhamam
2. poḍhi cha [||]

—"Success! A cave and a cistern, the meritorious gift of the female ascetic Dāmīlā, an inhabitant of Kalyāṇa."

It would seem that the small letters *poḍhi cha* in the second line are intended as a correction, and to be inserted after *leṇa* as the sense requires. [Alphabet, Andhra type, of the time of Puṣumāyi.

No. 26 (West's No. 35), on the left-hand side-wall outside the verandah of Cave No. LXVIII.—

1. pālā[ṇam] [amteṇā] sīsa
2. ṇayasa . . . [m]itanakasa pavajitasa
3. leṇa (?) . . . pāṇiya-poḍhi cha
4. [deya]dhama [chātu]dise bhikhusaghe pati-
5. thāpitaṃ mātāpitara udisa savasatāna
6. hitasukhaṭṭha apaṇo cha nivāṇāsabharatṭha [] etasa cha akhayanivī di[nā ||]

—"By the pupil of pāla, the ascetic . . . mitanaka, a cave (?) and . . . a water-cistern have been excavated for the community of ascetics from the four quarters of the horizon; for the benefit of (his) parents, for the welfare of all living beings, and for the fulfilment of the hope of final liberation for himself. And a perpetual endowment has been given by him."

Alphabet, Andhra type, about the time of Puṣumāyi.—*Nivāṇāsabharatṭha* would be in Sanskrit *nirvāṇāśābharanārtham*, but the idiom is Gujarātī or Marāṭhī.

¹ See *Arch. Report*, vol. iv, p. 69.

No. 27 (West's No. 37), on the left-hand side-wall, outside the verandah of Cave No. LXX.—

1. lepaṃ pāṇiyya[poḍhi cha] . . .
2. ṇa Bhādrājanījāpaṃ pratigrahe [] etta¹ pūṇaṃ
3. mātua cha Nandīnikā bhājāya gharīṇiṇi Dāmi-
4. [lāya] ya ekka ovarako deyyadharmma etto cha punabbhāgo puttāṇa je-
5. bhātuputrasya cha Āryaghoshasya dhutua cha Saṃghadevanikāya
6. natukapaṃ nātipaṃ² panatukapaṃ panatīpaṃ sūnāpaṃ savvaseva kulasya
7. [a]tītaṇaṃ tthitāṇaṃ anagatāṇaṃ³ cha sārvaśatvāṇaṃ cha hitasukhārthāya bhavatu tti []

—“ a cave and a water cistern for the acceptance of the Bhadrāyanīyas. The merit (*gained*) thereby (*shall belong*) to and to (*my*) mother Nandīnikā. One cell (*is*) the meritorious gift of (*my*) wife (*and*) lady Dāmilā. A share of the merit (*gained*) thereby (*shall belong*) to (*my*) sons Je, to (*my*) nephew Āryaghosha, and to (*my*) daughter Saṃghadevanikā . . . to (*my*) grandsons, grand-daughters, great-grandsons, great-grand-daughters, and daughters-in-law, and to (*my*) whole race, the deceased, the living, and the unborn; may it be for the welfare and happiness of all living beings.”

I am unable to make out the whole of the postscript, which narrates how a perpetual endowment of 1600 *kārshāpaṇas* was given, and contains details into whose hands it was placed, and for whose benefit the interest was to be expended. The portion transcribed is interesting on account of its language, which presents a most remarkable mixture of Sanskrit and Prakrit forms, and for the occurrence of the name of the Bhadrāyanīya school, which is frequently mentioned in the Nāsik inscriptions. The alphabet shows the Andhra type, with an admixture of younger forms, *e.g.*, in *ṇa* and *śa*.

No. 28 (West's No. 39), on the right-hand side-wall outside the verandah of Cave No. LXXVI.—

1. Sīdha[m] upāsakasa Dheṇukākata[i]yasa [Kulapiyasa]
2. [Dha]maṇakasa dh[u]tuya pavaṭtik[ā]ya Sā[pāya the]
3. r[ā]ṇa bhadata-Bodhikāṇa ātevasini[ya]
4. leṇa deyadhama p[ā]ṇiypoḍhi cha saha bhagī[niṇi]
5. Ratīnikāya saha cha saveṇa nātisabaddhi[vage]
6. ṇa ch[ā]tudi[s]e bhikkhusagha[s]e aṭhasu puris[esu]
7. lesu (?) patīthāpita mātupitara udisa sava[satāṇa]
8. hitasughatha[] bhikkhusaghasa akhayanivi cha dipā eto cha [bhikhu]-
9. sagha[ā]ṇa chivarika dātava solasaka utukāle cha . . .

—“Success! By the female ascetic Sāpā (Sarpā), the daughter of the lay-worshipper and inhabitant of Dheṇukākata, Kulapiya (Kulapriya) Dhamaṇaka (Dharma), (*and*) the pupil of the Thera, the reverend Bodhika (*she being associated*) with her sister Ratīnikā and with the whole number of her relations and connections, a cave and a water-cistern have been excavated (*as*) a meritorious gift, for the community of ascetics from the four quarters of the horizon (*viz.*) for eight persons (?) . . .—for the benefit of her parents and for the welfare and happiness of all living beings. And a permanent endowment has

¹ L. 2. Read *etto*.

² L. 6. Read *natīpaṃ*.

³ L. 7. Read *anagatāṇaṃ*.

been given to the community of ascetics; and out of (*the interest of*) that (*a piece of*) sixteen shall be given to the community of ascetics for clothes, and in the season. . . ."

Dhenukākata is doubtless the same place which is frequently mentioned in the Kārle inscriptions and elsewhere. It is most probably different from Dhanakataka or Dhañakataka, the Andhra capital, in the south-east. Etymologically the name means "the residence of Dhenukā," and the word looks like a synonym of Dhenukāśrama, or Dhenukā, which is mentioned in the *Mahābhārata*. The alphabet shows the Andhra type of the times of Gotamiputa Siri-Yaśa Sātakaṁni II.

No. 29 (West's No. 40), on the right-hand side-wall outside the verandah of Cave No. LXXVII.—

1. . . sa ipula sava . . ma
2. . . sa dasamiya etā[ya] puvāya mahārā[ja]bālikāya ma[hābhoji]ya
3. bā[likā]ya mahārāṭhīniya *Khaṁdanāgasātaka*-mātuya mahā[bho]jasa [Ahi]-
4. [jasa](?) cha Dhepasasasa(?) bhagīniya Nāgamulanī[kā]ya leṇa deyadhama
5. bhikusaghe patīthāpita(m) mā[tup]i[ta]rā [udi]sa kā . eṇa a . . .

—" on the tenth (*lunar day*). On the above (*date*) Nāgamulanikā (Nāgamūla), daughter of the great king and daughter of the Mahābhoji, wife of the Mahārāṭhi, mother of Khaṁdanāgasātaka (Skandanāgasātaka), and sister of the Mahābhoja Ahija (?) Dhepasasa (Dhanasena?) excavated a cave (*as*) a meritorious gift for the community of the ascetics . . . for the benefit of her parents"

Letters, Andhra. Both *ta* and *na* have a loop, and are for that reason not to be distinguished; *na* has the later form, which occurs also on the Jagayyapettā inscriptions. As, however, an *i*, a *pu*, and a *la*, or rather traces of these letters, are faintly visible in the first line before the first break, it is not impossible that the inscription was dated according to the regnal years of Siri-Puṣumāyi.

No. 30 (West's No. 53), on a detached rock between Caves No. XIV. and XV.—

Kaliya[ṇa]to
Nadasa kamā-
rasa patho de-
yadhama []

—"Success! A path, the meritorious gift of Nanda (*Nada*), a blacksmith from Kalyāṇa."

This inscription seems to be one of the oldest found at *Kaṇheri*, for the letter *da* has the old form and opens towards the left.

Postscript.—The word *Āṇadamātu*—Kaṇheri No. 44, West (Burgess, No. 15), l. 5—affords a certain instance in which the genitive *mātu* is used in the sense of the instrumental. It is, therefore, not necessary to change, as proposed above, *Vedisirimātu* (Nānāghāt I. p. 61) to *Vedisirimātuya*. As regards the word *bhāriyā* (*Ibidem*), which evidently has the sense of *bhāriyāya*, it may also be a vicarious form for the latter instead of a misspelling, for the Kaṇheri and other old Prakrit inscriptions repeatedly show *a* instead of *ya* as the termination of the third case. It is, therefore, imaginable that this *a* may have coalesced with

the preceding long vowel, and that thus *bhāriyā* (loc. cit.) may be really intended for an instrumental case.

No. 31.—

On the architrave of Cave X—the Darbār Cave¹—is an inscription in eight lines from 11 to 11½ feet long, with two additional ones of 5½ feet long, but very indistinctly engraved. The opening sentences have been translated by Pandit Bhagwānlāl Indrajī.² It is dated in the Śaka Samvat 775 in the reign of the Rāshtrakūṭa king Amoghavarsha Jagattuṅga, and of his feudatory Kapardi, the Śilāhāra, chief of the Konkan.

✓ No. 32.—

On the architrave of the small cave No. LXXVIII., just opposite to the Darbar Cave, is a similar inscription (West's No. 43) dated in Śaka 799 during the reign of the same two kings.

In Cave LXVI. are three Pahlavi inscriptions, one on the left side of the recess of the water cistern in the right side of the court, and consists of thirteen lines; the other two are on the pilasters of the verandah, and are also written vertically. Dr. E. W. West also discovered two fragments of similar inscriptions at the structural stūpa or dāgaba which he examined.³ These inscriptions have been translated by Dr. West,⁴ and consist of lists of names, two companies of Pārsās who visited the place: the first having engraved two of the inscriptions on 10th October and 24th November 1009 A.D., and the second perhaps also two—the one dated 30th October 1021 A.D. The fifth fragment is too small and indistinct to yield any information.

The copperplate inscription found by Dr. Bird at Kanheri has also been published elsewhere.⁵

III. DAŚA AVATĀRA INSCRIPTION AT ELURĀ.

On the west side of the maṇḍapa in front of the Daśa Avatāra cave temple at Elurā is a long inscription in fourteen lines in Dēvanāgarī characters, of the forms used in the first half of the eighth century; but they are faintly cut and much chipped, few of the letters being uninjured, and long portions of many of the lines quite illegible. Pandit Bhagwānlāl Indrajī studied it carefully on the spot, and made a transcript of all the letters he could make out, of which the following is a transliteration. It is in Sanskrit verse, and contains 29½ śloka in different metres.

Transcript.

- (1.) Om namaḥ | Sivāya | Arddhakṛiṣṭe garishṭhe dhanushi śiśutayā jānulagnāḥ kumārāḥ vāmārdhenāpanetum
jhaṭiti vighaṭite gāḍhabandhepi muṣṭau yātaḥ pāyā sannādapī[dahati pure]
(1.)

¹ See *Cave Temples*, p. 355. This inscription is Dr. West's No. 15.

² *Jour. Bom. B. R. As. Soc.*, vol. xiii, p. 11; and *Cave-Temple Inscriptions*, p. 61.

³ *Jour. Bom. Br. R. A. Soc.*, vol. vi, pp. 116 ff.

⁴ Published in the separate memoranda of the Archaeological Survey of Western India, No. X.—*Cave-Temple Inscriptions*, pp. 62–66; and *Ind. Ant.*, vol. ix, pp. 265–268.

⁵ *Cave-Temple Inscriptions*, pp. 57–60.



- (2) bhasantushṭā viyuktānyā setyetyuktavati haraṁ rahasi vaḥ pāyānagendrātmaḥ (2) [sva]lambhīkṛitāṁ
yatna pi nirmamalaṁ pareṇa jāpyanalini karotyalaṁ prakṛiṣṭamākṛiṣṭa
payobindurivāyudhaṅkaraḥ (3) sthīrātmakaḥ [sadguṇa]
ka sya nāṁ sajano (4)
- (3) ye kīrtitāḥ kṣhītibhujāḥ kavibhiḥ purāṇāḥ tāneva saṁsamarati vetyadhunāpi lokastasyānvayasya kavireṣha
tanoti kīrtiṁ (5) samagrajagattīlāvikalapālanaikochitaṁ pra[kāmachatu]rārṇavapramathanājītaḥ śrīpatir
na vetti khalu kaḥ kṣhītai prakṛāśhtrakūṭānvayaṁ (6) tapatha
ddhairyaṁvantaḥ karttāraḥ prārthitārthaḥ prapayijana
- (4) pra[thita]prithuechamāvīkramāpamarīṇāṁ bhaktārāḥ kauṇjarīṇāṁ samadakaṭatataślāghinīnāṁ ghaṭānāṁ (7)
tasmīṁ dugdhāmbu[vichī]dyu[ti]dhavalayaśācandrikodbhāsītāśo yoshichakrasya
raṇadadbanmattamātaṁgagāṁ svāmi varṇāśramāpāṁ prasamītasakalavyāpadānandadā[nā]
bhāsva tapaśāṁ vidvishāṁ Dantivarīmā (8) sudustyaḥ yena satāpi
bhūbhṛtā sa tra vīvekināścharya
- (5) masajjanāya yaṁ dayālunā sajjanavṛittasālinā (9) ālekhyārpitamūrtitayaḥ svabhavaneshvadyāpi yasya
dvishāḥ paśyantaḥ kimu yuddhamuddhatarushāśchitrasaṁ[māna]ntaśch tannāmasamarāṅgata
mātvanyopī nashṭaśrīyaḥ² prekshyante pathikāḥ śuśheva vividhāstenaiva nirmūlitāḥ (10)
tasyātmaḥ devarāja kamalaḥ kamalāyatākṣaḥ kṣhūṇārī-
pakṣhavanitā nayanāntavāntatoyānvitakṣhītarakṣhayadindrārājaḥ (11) yasmīnkshepi
- (6) makhaṇḍāṁ kṛitabhayaśunnatāṁ rakṣati kṣhūṇadusṭe saṁpannāḥ sārddhasiṣṭāḥ pravarakṣitayū[ga]ḥ
kṣhmāpatinyāyayuktyā yajūai [bhaktā]ḥ vibudhāṁjire
kaśchinnābhūtsaśokāṁ kalikalushamatirnaiva nāpyalpavittāḥ (12) vikāśi yasya kṣhaṇadāsvavikṣhatāṁ
śāśāṅkadhāmavyapade[śakā]rī karo[ti] saṁpratyapi nirmamalaṁ jagatprasannadigmaṇḍalamandanaṁ yaśaḥ
(13) durvārodārachakraḥ prithutarakṭakāḥ kṣhmābhṛidunmūlanena khyātāḥ śaṁkhāṅkapāni
- (7) rbbalivijayamahāvīkramāvāptalakṣmīḥ kṣhōḇibhārāvātārī viṣhamamahipateṣṭasya sūnurnripobhūt mānyo
Govindarājo haririva harīrākṣhījanaprārthanīyaḥ || (14) yasyāmala[h] prapatabhūpativachehhalasya³ rāmā-
bhīrāmācharitasya sahasrasaṁkhyāḥ ānandabhirguṇaśatai[h] prasṛitairddigāntāṁ vyāptāḥ ja[ga]ṭkaraśatairiva
śītarasmeḥ (15) tasmā janmā ripujanatimirākāṇḍachandāmśu meshaḥ puṇyaib
prajānāṁ sūgatasamakṛipaḥ kalpavṛikṣhānukārī bhītāpannārttīhārī
- (8) kalikalushajushā makārī rājāśrī Karkkarājaḥ khara ra[khurākṣhepa]ḥ nīḥśeshitārīḥ
(16) yasyārūḍhasya naktāṁ nīyatanripujanāsthānadānāyukāntāṁ ramyaṁ harṁyasya prīṣṭaṁ pravatatara-
maṇi śreṇīśiṅghāsanāṁkām vāraṣṭribhātātādyutitaralamahāratanarocheśśikhābhīḥ kāmāṁ dhvastendhakāre
na sitakarakarai yaḥ (17) duḥprāpavāṁchhitamanorathasamvidhāna nīrnāsītārthibud-
hasārthamanobhītāpāḥ yaḥ kalpāpādapamapīndusitorukṛtī
- (9) rānandibhirguṇaśatairadharīchakāra || (18) tasyābhūdbhūvanaprakāmamahimā bhagnārvīronnatīḥ kṣhīptāḥ
kṣhudrārājaḥ prajāparibhāvavyāpattivichchhīttikṛit mādyaddīkkarikumbhabhittivilasatkīrtipratitāyatan . .
dvājirupājirajītajayaḥ śhrīndrārājaḥ sutaḥ || (19) yo māchchharyamanār⁴yakāryavimukhaḥ proch-
chhārya⁵dhairyaśodhīḥ dhṛitvā sajjanavṛittameṣha sukṛitāḥ . . dhīrograhīt yasyādyāpi guṇaiḥ
śāśāṅkaśuchibhīrdhāmāparāṁ tatsamaṁ bhṛāmyadbhirna bhavekhile
- (10) māsaradāṁ hāṁsachchhalenāpyate || (20) varṇāśramāśaśhāṁ tanayastasya svavartmasuyasitūḥ śrī
Dantidurggarājassakalamahīpālānāthobhūt (21) yasya hareriva charitaṁ nātīkrāntairna bhāvibhiḥ kaiśchit
śakyamanukarttumamalaṁ napatibhirnāpi sāmpratīkaiḥ (22) dandenaiva jīgāya Vallabhabalaṁ yaḥ
Sandhubhūpādhipaṁ Kāñchīśaṁ sa Kalīṅga-Kośalapai Śrīśailadeśeśvaraṁ śeśhānMālavaLāṭaTamkanṛi-
patinanyāścha nītvā vaśaṁ yaḥ ŚrīVallaba
- (11) tāmavāpa charaṇaṁ nyasya dvishāṁ mastake || (23) śauryeṇātyaśayishṭa yaḥ prathanakaṁ tejasvinā mārutīṁ
tyāgenāśumadātmaḥ rājanayairdronaḥ gururṁ prajāyā rūpeṇāpratimena manmathamatha sthemaṁ
suvarṇpūchalam lāvayena śāśāṅkamujvalayaśch śubhrikṛito [yaḥ] pathaḥ (24) devaḥ
savaraparikaraṁ bhīmasenānyātāṁ prahvairbhūpendravṛindaiḥ parivṛitamabhayairugraseno jītārīḥ
vyāpadyuddharttumekaṁ prasabhaparakarīdhvamsasamśkāradakṣho Bibhachchh⁶urduṣhaṇḍaṅgo

¹ Read *tasmīnāṁ*.² Read *mātsarya*.³ Read *śrīyaḥ*.⁴ Read *protśarya*.⁵ Read *śalasya*.⁶ Read *bibhatsa*.

- (12.) Jayinamiva param śrīmahārāja-Śarvāḥ || (25) dattam yenojjayinyāmapī nripatimahādānamāścharyabhūtam
nyāyāṇa sañchintyadīptadyutibhukanakam ratnamuktāvataṁsam māṇikyākīrṇamanyam divasamavira-
tatīptadinārthīsārtham karttum kṛdāmapūrvvāmaparaṇipatibhiḥ svapmakālepyanāpyām || (26) dhaureyaṁ tu
prakṣiṣṭam sakalavasumatibhāradhārī[ṭva]yogyaṁ dṛiṣṭvairam ślāghantyaṁ raghunaghushaṇṇigeshvapyā-
dṛiṣṭam ya tsarvvaṁ dvīpādhipatyam paramavijā[yina]
- (13.) mādaraiśchāryasāmāṁ pritaḥ prādātsayasmai mushitakalimude rājasiṁghāya¹ vedhā || (27) yasmādduḥkham
dvishantaḥ sunahad upachitam prāpurisṭā viśiṣṭāśchītram chittena vittam chiramabhiṣhitam yatta-
devārthīsārthāḥ bhṛityāśadbhogayogaṁ bhayavidhuradhiyaḥ prāpinastrāsanāśam vridhim dharmasya
viprāḥ sukhamabhiruchitam bandhumitrāptavarggāḥ || (28) yasyākhamdītavikramasya kṛtākenākramya
tṛakṣitīm saudhesmīṁkṛta-Gurjarendraruchite rāmye taistasthushaḥ snāntibhi tā-
garāgasurabhi
- (14.) protkaṁpīpadmākaram dhāritṛiṣhvapi pushkareṣhvapi nābhiśchiram || (29) yasyāstodayasaila-
sānuvanajeshūtkāṁpikarnotpalā[h] sārddham kāmijanaśrīlavasumanogandhāndhamuktālīshu vyākīrṇeshu
latāgriheshvaviralāḥ karppūrareṇūtkarai.

This fragmentary inscription is interesting, as it gives us two earlier kings of the great Rāshṭrakūṭa dynasty than are mentioned in the copperplates, viz., Dantivarmā and Indrarāja, who must have reigned about the beginning of the seventh century. It then continues the dynasty list with the usual names of Govinda I., Karka, Indra, and Danti-durga, the latter of whom is described as placing his feet on the necks of his enemies, and made the Vallabharāja (that is, the Western Chalukya king, Kirttivarma II.) his tributary, besides subjugating many other kings, whence he took the title of Śrī-Vallabha. There is mention made of a Maharāja Śarva, perhaps the brother or first minister of the king, who is also praised. The last two verses apparently describe him as coming with an army and staying at this temple. A Gurjara rāja is also mentioned.

This Dantidurga, we know from other inscriptions,² must have ruled about A.D. 725-755, and it is probable that the visit to Elurā mentioned in this inscription was connected with the dedication of the Kailāsa temple or of the Dāśa Avatāra one. Of his uncle and successor Krishna I., we are told that he established himself at a hill named Elā-pura, where there was a famous temple of Svayambu-Śiva: this place has not been identified, but may possibly have been on the hill above the Elurā caves, on which, beyond the modern town of Rozah, are the remains of an old Hindu city.

¹ Read *śiṁghāya.

² See *Reports*, vol. iii, pp. 31 ff; *Ind. Ant.*, vol. v, p. 144 f.; vol. vi, pp. 59-72; vol. i, pp. 205 ff; vol. vii, p. 210; and vol. xi, p. 108.

END OF VOL. V.



ELURA.-BUDDHIST CAVES.



1. TĀRĀ IN CAVE II.




2. TĀRĀ IN CAVE VI.



3. PILASTER IN CAVE V.

Scale of 1/2" 1 2 3 feet



6. BODHISATTVA IN CAVE IX.




4. ON THE RIGHT SIDE OF THE SHRINE IN CAVE VI




5. ON THE LEFT SIDE OF THE SHRINE CAVE VI.




ELURA.




2. TIN THAL-2ND. STOREY.






ELURÂ.


DON THAL SECOND FLOOR.



FIRST FLOOR.



DON THAL, GROUND PLAN.



Scale of 0 10 20 30 40 50 60 70 80 90 100 feet

THE UNIVERSITY OF CHICAGO
LIBRARY



ELURA BAUDDHA CAVES.




1. TRANSVERSE SECTION OF VISVAKARMA CAVE.



2. PADMAPANI IN CAVE IV.



4. PILLAR IN CAVE IX.



5. PILLAR IN UPPER FLOOR OF DON THAL.



3. SARASVATI IN CAVE VI.

THE UNIVERSITY OF CHICAGO
LIBRARY
CHICAGO, ILL.


THE UNIVERSITY OF CHICAGO
LIBRARY
CHICAGO, ILL.

THE UNIVERSITY OF CHICAGO
LIBRARY
CHICAGO, ILL.

DETAILS FROM VISWAKARMA CAVE.



1. SCULPTURE ON THE INNER SIDE OF THE GALLERY.



2. PART OF THE TRIFORM.



3. SCULPTURES FROM THE DAGOBA.


J. Burgess.

Scale of 1 2 3 4 5 6 7 8 9 10 feet

ELURA BUDDHIST CAVES.

ॐ नमो भगवते वासुदेवाय ॥ ॐ नमो भगवते वासुदेवाय ॥ ॐ नमो भगवते वासुदेवाय ॥
 ॐ नमो भगवते वासुदेवाय ॥ ॐ नमो भगवते वासुदेवाय ॥ ॐ नमो भगवते वासुदेवाय ॥

1. INSCRIPTION ON THE VIÉVAKARMA CAVE.



2. PILLAR UNDER THE GALLERY.
IN VIŠVAKARMA CAVE.

J. HUGGESS.



3. SCULPTURE IN THE TIN THAL CAVE.



4. BUDDHA AND ATTENDANTS.-BAGH CAVES.



ELURĀ

FIG. 1.



FIG. 2.




FEMALE HEADS
FROM VIŠVAKARMA CAVE.



5. SCULPTURE TO THE LEFT OF THE SHRINE DOOR IN THE TIN THAL, UPPER STOREY.



6. PANEL IN TIN THAL.




3. HEAD OF AVALOKITEŚVARA
FROM VIŠVAKARMA CAVE.



4. VAJRAPANI
FROM VIŠVAKARMA CAVE.






ELURÂ

BODHISATTVAS ON THE RIGHT SIDE OF THE SHRINE IN THE TIN THAL.

FIG. 1.



BODHISATTVAS FROM THE BAGH CAVES.

FIG. 2.






FIG. 3.





1. PILLAR IN DAS AVATARA.



3. SIVA IN THE FLAMING LINGA.



2. SHAFT OF PILASTER.



4. SIVA DANCING THE TANDAVA IN THE DAS AVATARA.

Scale of 12' 1 2 3 4 5 6 7 8 9 10 feet



ELURA.



1. NARASIMHA & HIRANYAKASIPU IN THE DAS AVATARA:



2. BHAIRAVA IN THE DAS AVATARA.

Scale of 12' 1 2 3 4 5 6 7 8 9 10 feet.

ELUF

I. TRANSVERSE



Scale of 10 feet

H. Cowen, del.

2. SECTION OF THE D...ARA CAVE




Scale of 10 feet

C. M. Sykes, del.





ELURA BRAHMANICAL CAVES.



1. SIVA RESCUING MĀRKANDEYA-FROM THE DAS AVATARA.

Scale of 1"

J. Burgess.




2. SIVA RESCUING MĀRKANDEYA-FROM KAILASA.

Scale of 1"

H. Goehner, del.

ELURA CAVE TEMPLES.



1. DOOR IN THE THIRD STOREY IN SOUTH SIDE OF THE COURT
IN KAILASA.



2. ON THE EAST SIDE OF THE SOUTH PORCH.
IN KAILASA.



3. ON THE WEST SIDE OF THE SOUTH PORCH.
IN KAILASA.



4. IN CAVE XXIV.



5. IN CAVE XXII

ELURA.-KAILASA.



1. SCULPTURE ON THE FRONT OF THE MANDAPA.



FIG. 3.

LIONS ON THE ROOF OF THE MANDAPA.



2. KAMADEVA AND RATI.

FIG. 4.



Scale to figs 1 & 2.

J. Burgess.

H. Cousins, del.



ELURA.

SCULPTURES FROM THE NORTH CORRIDOR IN THE COURT OF KAILASA.

FIG. 1.



FIG. 2.





FIG. 3.



J. Burgess.

Scale of 7 feet

S. J. Pacher, del.



Handwritten text in a cursive script, possibly a list or a short paragraph, located in the upper right quadrant of the page.

Handwritten text in a cursive script, possibly a signature or a short paragraph, located in the lower right quadrant of the page.




FIG. 1.






FIG. 2




J. Burgess.

ELURA-KAILAŚA COLUMNS.


H. Courtes, del.




FIG. 3.



ELURA.-KAILASA.



PILLAR IN THE CENTRAL AREA OF LANKESVARA



3. VARAHA ON THE BACK WALL.



2. IN THE FRONT AISLE OF LANKESVARA.

H. Cousens del.

Scale of Feet
1 2 3 4 5 6 7





1. SŪRYA IN LANKEŚVARA.



2. UMĀ IN LANKEŚVARA.



3. BRAHMA, ŚIVA, AND VIṢṆU IN LANKEŚVARA.

H. Cresson.

Scale of 16' 1 2 3 4 5 6 7 8 9 10 feet.



Handwritten text in Persian script, likely a title or description of the drawing.

Handwritten text in Persian script, likely a signature or date.

ELURA:-KAILASA ROCK-TEMPLE.


2. ANOTHER PANEL ON THE SOUTH SIDE OF THE SHRINE.



1. PANEL ON THE SOUTH SIDE OF THE SHRINE IN KAILASA.



3. ON THE SOUTH SIDE OF THE BASEMENT OF THE NANDI MANDAPA.



ELURÂ.

Fig 1.

CAVE XVII.

2. CAVE XIX.

PLAN OF CAVE XVIII.

3. PLAN OF CAVE XX.

4. CAVE XXII.


NILKANTH.

Scale of 0 10 20 30 40 50 60 feet


5. CAVE XXVI.-JANWABA.

ELURA.


3. PILLAR IN RAMESVARA



1. PILLAR IN CAVE XVII.



2. PILLAR IN CAVE XVII.



Scale of


feet



J. Burgin.

W. Grege, Photo-lith.

ELURA



1. SAPTAMĀTRIS IN RĀMĒSVARA.

2. END OF THE CHAPEL.



3. SAPTAMĀTRIS IN CAVE XXII.

Scale of 1
feet.

THE HISTORY OF THE




THE HISTORY OF THE

THE HISTORY OF THE

ELURA BRAHMANICAL CAVES.




1. BRAHMA AT THE END OF THE VERANDAH CAVE XVII.




2. PILLAR IN CAVE XXV.

3. PLAN OF KUMBARWADA CAVE XXV.




4. PLAN OF CAVE NO. XXVII.






ELURA BRAHMANICAL CAVES.




1. MARRIAGE OF SIVA AND PARVATI IN DUMAR LENA



2. NORTH-WEST CORNER OF THE SHRINE IN DUMAR LENA

Scale of 1" = 1 foot



ELURA.
PILLARS IN THE INDRA SABHA.

FIG. 3. IN THE CENTRAL HALL.




FIG. 4. IN THE CENTRAL HALL.




FIG. 2.
IN A SMALL CHAPEL.





FIG. 1.




J. Burgess.

Scale of feet


C. M. Sykes, del.

ELURA.-PILLARS IN THE UPPER FLOOR OF THE INDRA SABHA.


1. COLUMN BETWEEN THE VERANDAH & HALL.




2. COLUMN IN FRONT OF THE VERANDAH



3. PILLAR IN THE WEST WING
UPPER FLOOR.





4. ON THE OPPOSITE PILASTER.




Scale of 1 foot

J. Burgess.


ELURA JAINA CAVES.




1. ROOF OF THE MANDAPA IN THE COURT OF INDRA SABHÂ.



2. AMBIKÂ
FROM A CHAPEL OF THE INDRA SABHÂ.



4. PILLAR IN THE LAST JAINA CAVE.



3. PILLAR IN THE JAGANNÂTH SABHA
GROUND FLOOR.

1. GOMATESVARA, IN INDRA SABHA AT ELURA.





2. GENERAL PLAN OF BADAMI CAVES.



3. SIVA DANCING, WEST SIDE OF CAVE I. AT BADAMI.







AIHOLE.-BRAHMANICAL CAVE.




1. ŚIVA AND THE RIVER TRIAD.



2. ŚIVA.



3. VARAHA & PRITHVI.
IN THE ANTECHAMBER.



5. ŚIVA DANCING THE TANDAVA.



4. MAHISHAMARDINI
IN THE ANTECHAMBER.

J. Burgess.

H. Cousens, del.


Scale 1 2 3 4 5 feet

THE CAVE AT LONĀḌ.

1. LEFT PORTION OF THE FRIEZE.



2. CENTRAL DOOR.




3. SCULPTURE TO THE RIGHT OF THE FAÇADE




ELEPHANTA.


PLAN OF CAVE III.



PLAN OF CAVE II.



PLAN OF CAVE IV.



3. LONAD-KHANDESVARI CAVE.



Scale of Feet 0 10 20 30 40 50 60 70 80 90 100

HARIŚCHANDRAGADĀ CAVES.

FIG. 1.




FIG. 2.



FIG. 3.





4. PATNA: TRANSVERSE SECTION OF NAGARJUNA: KOTRI.




Scale of 1 2 3 4 5 feet.


5. PATNA: HALL DOOR OF ŚRINGAR CHĀVADI.




6. ANKA: DOOR OF JAINA CAVE NO. II, LOWER STOREY.



PATNA CAVES.




1. SECTION OF SRINGAR CHAYADI.



3. SECTION OF NAGARJUNA KOTRI.

Scale of ————— 10 ————— 20 ————— 30 feet.



2. PLAN OF SRINGAR CHAYADI.


Scale of ————— 10 ————— 20 ————— 30 feet.




4. PLAN OF NAGARJUNA KOTRI.

ANKAI CAVES.


1. SECTION OF JAINA CAVE NO. II.




2. PLAN OF UPPER STOREY




3. PLAN OF GROUND FLOOR OF CAVE II.



4. PLAN OF JAINA CAVE III.



5. PLAN OF JAINA CAVE IV.



6. BRAHMANICAL CAVE.





Scale of 2 3 4 5 6 7 8 9 10 feet

Scale of 2 3 4 5 6 7 8 9 10 feet


Scale to figs 1-3.

Scale to figs 4-6.

GESWARI



EASTERN DOOR A OF THE GREAT HALL.




Scale of 1 2 3 4 5 6 7 8 9 10 11 12 Feet

200 Feet



H. Cousens, del.

ANKAI CAVES



1. ROOF OF THE JAINA CAVE NO. III. AT ANKAI.

Scale of ft. 1 2 3 4 5 6 7 8 9 10 feet.




2. FRONT OF THE BRAHMANICAL CAVE NO. I



3. FIGURES AT THE ENTRANCE OF NO. I


THE BRAHMANICAL CAVE OF JO
ON THE
ISLAND OF SALGETTE



Scale of

0 10 20 30 40 50 60 70 80 90 100 110 120 130 140


J. Burgess.


1. 


2. 


3. 


4. 


5. 


6. 


7. 


8. 


9. 

10. 

11. 

12. 

13. 

14. 

KANHERI CAVE INSCRIPTIONS

Pandit Bagwanlal Indraj.

15. 


16. 


17. 

18. 

19. 

KANHERI CAVE INSCRIPTIONS.

20. 

21. 

Pandit Bagwanlal Indraj.

J. B.

H. C.



